

---

# kwcoco Documentation

*Release 0.5.8*

**Jon Crall**

**Mar 17, 2023**



# PACKAGE LAYOUT

<b>1 CocoDataset API</b>	<b>5</b>
1.1 CocoDataset classmethods (via MixinCocoExtras) . . . . .	5
1.2 CocoDataset classmethods (via CocoDataset) . . . . .	5
1.3 CocoDataset slots . . . . .	5
1.4 CocoDataset properties . . . . .	6
1.5 CocoDataset methods (via MixinCocoAddRemove) . . . . .	6
1.6 CocoDataset methods (via MixinCocoObjects) . . . . .	7
1.7 CocoDataset methods (via MixinCocoStats) . . . . .	7
1.8 CocoDataset methods (via MixinCocoAccessors) . . . . .	7
1.9 CocoDataset methods (via CocoDataset) . . . . .	8
1.10 CocoDataset methods (via MixinCocoExtras) . . . . .	8
1.11 CocoDataset methods (via MixinCocoDraw) . . . . .	8
<b>2 kwcoco</b>	<b>9</b>
2.1 kwcoco package . . . . .	9
2.1.1 Subpackages . . . . .	9
2.1.1.1 kwcoco.cli package . . . . .	9
2.1.1.1.1 Submodules . . . . .	9
2.1.1.1.1.1 kwcoco.cli.coco_conform module . . . . .	9
2.1.1.1.1.2 kwcoco.cli.coco_eval module . . . . .	10
2.1.1.1.1.3 kwcoco.cli.coco_grab module . . . . .	12
2.1.1.1.1.4 kwcoco.cli.coco_modify_categories module . . . . .	12
2.1.1.1.1.5 kwcoco.cli.coco_reroot module . . . . .	13
2.1.1.1.1.6 kwcoco.cli.coco_show module . . . . .	14
2.1.1.1.1.7 kwcoco.cli.coco_split module . . . . .	14
2.1.1.1.1.8 kwcoco.cli.coco_stats module . . . . .	15
2.1.1.1.1.9 kwcoco.cli.coco_subset module . . . . .	16
2.1.1.1.1.10 kwcoco.cli.coco_toydata module . . . . .	18
2.1.1.1.1.11 kwcoco.cli.coco_union module . . . . .	18
2.1.1.1.1.12 kwcoco.cli.coco_validate module . . . . .	19
2.1.1.1.2 Module contents . . . . .	20
2.1.1.2 kwcoco.data package . . . . .	20
2.1.1.2.1 Submodules . . . . .	20
2.1.1.2.1.1 kwcoco.data.grab_camvid module . . . . .	20
2.1.1.2.1.2 kwcoco.data.grab_cifar module . . . . .	21
2.1.1.2.1.3 kwcoco.data.grab_datasets module . . . . .	21
2.1.1.2.1.4 kwcoco.data.grab_domainnet module . . . . .	22
2.1.1.2.1.5 kwcoco.data.grab_spacenet module . . . . .	22
2.1.1.2.1.6 kwcoco.data.grab_voc module . . . . .	23
2.1.1.2.2 Module contents . . . . .	23

2.1.1.3	kwcoco.demo package . . . . .	23
2.1.1.3.1	Submodules . . . . .	23
2.1.1.3.1.1	kwcoco.demo.boids module . . . . .	23
2.1.1.3.1.2	kwcoco.demo.perterb module . . . . .	28
2.1.1.3.1.3	kwcoco.demo.toydata module . . . . .	29
2.1.1.3.1.4	kwcoco.demo.toydata_image module . . . . .	42
2.1.1.3.1.5	kwcoco.demo.toydata_video module . . . . .	48
2.1.1.3.1.6	kwcoco.demo.toypatterns module . . . . .	63
2.1.1.3.2	Module contents . . . . .	66
2.1.1.4	kwcoco.examples package . . . . .	66
2.1.1.4.1	Submodules . . . . .	66
2.1.1.4.1.1	kwcoco.examples.bench_large_hyperspectral module . . . . .	66
2.1.1.4.1.2	kwcoco.examples.draw_gt_and_predicted_boxes module . . . . .	66
2.1.1.4.1.3	kwcoco.examples.faq module . . . . .	67
2.1.1.4.1.4	kwcoco.examples.getting_started_existing_dataset module . . . . .	67
2.1.1.4.1.5	kwcoco.examples.loading_multispectral_data module . . . . .	68
2.1.1.4.1.6	kwcoco.examples.modification_example module . . . . .	68
2.1.1.4.1.7	kwcoco.examples.simple_kwcoco_torch_dataset module . . . . .	68
2.1.1.4.1.8	kwcoco.examples.vectorized_interface module . . . . .	69
2.1.1.4.2	Module contents . . . . .	69
2.1.1.5	kwcoco.metrics package . . . . .	69
2.1.1.5.1	Submodules . . . . .	69
2.1.1.5.1.1	kwcoco.metrics.assignment module . . . . .	69
2.1.1.5.1.2	kwcoco.metrics.clf_report module . . . . .	70
2.1.1.5.1.3	kwcoco.metrics.confusion_measures module . . . . .	72
2.1.1.5.1.4	kwcoco.metrics.confusion_vectors module . . . . .	83
2.1.1.5.1.5	kwcoco.metrics.detect_metrics module . . . . .	91
2.1.1.5.1.6	kwcoco.metrics.drawing module . . . . .	101
2.1.1.5.1.7	kwcoco.metrics.functional module . . . . .	108
2.1.1.5.1.8	kwcoco.metrics.sklearn_alts module . . . . .	108
2.1.1.5.1.9	kwcoco.metrics.util module . . . . .	109
2.1.1.5.1.10	kwcoco.metrics.voc_metrics module . . . . .	109
2.1.1.5.2	Module contents . . . . .	111
2.1.1.6	kwcoco.util package . . . . .	137
2.1.1.6.1	Subpackages . . . . .	137
2.1.1.6.1.1	kwcoco.util.delayed_ops package . . . . .	137
2.1.1.6.1.2	Module contents . . . . .	137
2.1.1.6.2	Submodules . . . . .	164
2.1.1.6.2.1	kwcoco.util.dict_like module . . . . .	164
2.1.1.6.2.2	kwcoco.util.jsonschema_elements module . . . . .	166
2.1.1.6.2.3	kwcoco.util.lazy_frame_backends module . . . . .	172
2.1.1.6.2.4	kwcoco.util.util_archive module . . . . .	172
2.1.1.6.2.5	kwcoco.util.util_futures module . . . . .	173
2.1.1.6.2.6	kwcoco.util.util_json module . . . . .	177
2.1.1.6.2.7	kwcoco.util.util_monkey module . . . . .	179
2.1.1.6.2.8	kwcoco.util.util_reroot module . . . . .	180
2.1.1.6.2.9	kwcoco.util.util_sklearn module . . . . .	182
2.1.1.6.2.10	kwcoco.util.util_truncate module . . . . .	182
2.1.1.6.3	Module contents . . . . .	182
2.1.2	Submodules . . . . .	200
2.1.2.1	kwcoco.abstract_coco_dataset module . . . . .	200
2.1.2.2	kwcoco.category_tree module . . . . .	200
2.1.2.3	kwcoco.channel_spec module . . . . .	205
2.1.2.4	kwcoco.coco_dataset module . . . . .	205

2.1.2.5	kwcoco.coco_evaluator module . . . . .	249
2.1.2.6	kwcoco.coco_image module . . . . .	254
2.1.2.7	kwcoco.coco_objects1d module . . . . .	263
2.1.2.8	kwcoco.coco_schema module . . . . .	273
2.1.2.9	kwcoco.coco_sql_dataset module . . . . .	274
2.1.2.10	kwcoco.compat_dataset module . . . . .	285
2.1.2.11	kwcoco.exceptions module . . . . .	289
2.1.2.12	kwcoco.kpf module . . . . .	289
2.1.2.13	kwcoco.kw18 module . . . . .	289
2.1.2.14	kwcoco.sensorchan_spec module . . . . .	292
2.1.3	Module contents . . . . .	292
2.1.3.1	CocoDataset API . . . . .	294
2.1.3.1.1	CocoDataset classmethods (via MixinCocoExtras) . . . . .	294
2.1.3.1.2	CocoDataset classmethods (via CocoDataset) . . . . .	295
2.1.3.1.3	CocoDataset slots . . . . .	295
2.1.3.1.4	CocoDataset properties . . . . .	295
2.1.3.1.5	CocoDataset methods (via MixinCocoAddRemove) . . . . .	296
2.1.3.1.6	CocoDataset methods (via MixinCocoObjects) . . . . .	296
2.1.3.1.7	CocoDataset methods (via MixinCocoStats) . . . . .	297
2.1.3.1.8	CocoDataset methods (via MixinCocoAccessors) . . . . .	297
2.1.3.1.9	CocoDataset methods (via CocoDataset) . . . . .	297
2.1.3.1.10	CocoDataset methods (via MixinCocoExtras) . . . . .	298
2.1.3.1.11	CocoDataset methods (via MixinCocoDraw) . . . . .	298
	<b>Bibliography</b>	<b>343</b>
	<b>Python Module Index</b>	<b>345</b>
	<b>Index</b>	<b>347</b>



If you are new, please see our getting started document: [getting\\_started](#)

Please also see information in the repo [README](#), which contains similar but complementary information.

Documentation about higher level kwcoco concepts can be found here. The Kitware COCO module defines a variant of the Microsoft COCO format, originally developed for the “collected images in context” object detection challenge. We are backwards compatible with the original module, but we also have improved implementations in several places, including segmentations, keypoints, annotation tracks, multi-spectral images, and videos (which represents a generic sequence of images).

A kwcoco file is a “manifest” that serves as a single reference that points to all images, categories, and annotations in a computer vision dataset. Thus, when applying an algorithm to a dataset, it is sufficient to have the algorithm take one dataset parameter: the path to the kwcoco file. Generally a kwcoco file will live in a “bundle” directory along with the data that it references, and paths in the kwcoco file will be relative to the location of the kwcoco file itself.

The main data structure in this model is largely based on the implementation in <https://github.com/cocodataset/cocoapi>. It uses the same efficient core indexing data structures, but in our implementation the indexing can be optionally turned off, functions are silent by default (with the exception of long running processes, which optionally show progress by default). We support helper functions that add and remove images, categories, and annotations.

The `kwcoco.CocoDataset` class is capable of dynamic addition and removal of categories, images, and annotations. Has better support for keypoints and segmentation formats than the original COCO format. Despite being written in Python, this data structure is reasonably efficient.

```
>>> import kwcoco
>>> import json
>>> # Create demo data
>>> demo = kwcoco.CocoDataset.demo()
>>> # Reroot can switch between absolute / relative-paths
>>> demo.reroot(absolute=True)
>>> # could also use demo.dump / demo.dumps, but this is more explicit
>>> text = json.dumps(demo.dataset)
>>> with open('demo.json', 'w') as file:
>>>     file.write(text)

>>> # Read from disk
>>> self = kwcoco.CocoDataset('demo.json')

>>> # Add data
>>> cid = self.add_category('Cat')
>>> gid = self.add_image('new-img.jpg')
>>> aid = self.add_annotation(image_id=gid, category_id=cid, bbox=[0, 0, 100, 100])

>>> # Remove data
>>> self.remove_annotations([aid])
>>> self.remove_images([gid])
>>> self.remove_categories([cid])

>>> # Look at data
>>> import ubelt as ub
>>> print(ub.repr2(self.basic_stats(), nl=1))
>>> print(ub.repr2(self.extended_stats(), nl=2))
>>> print(ub.repr2(self.boxsize_stats(), nl=3))
>>> print(ub.repr2(self.category_annotation_frequency()))
```

(continues on next page)

(continued from previous page)

```
>>> # Inspect data
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> import kwplot
>>> kwplot.autompl1()
>>> self.show_image(gid=1)

>>> # Access single-item data via imgs, cats, anns
>>> cid = 1
>>> self.cats[cid]
{'id': 1, 'name': 'astronaut', 'supercategory': 'human'}

>>> gid = 1
>>> self.imgs[gid]
{'id': 1, 'file_name': '...astro.png', 'url': 'https://i.imgur.com/KXhKM72.png'}

>>> aid = 3
>>> self.anns[aid]
{'id': 3, 'image_id': 1, 'category_id': 3, 'line': [326, 369, 500, 500]}

>>> # Access multi-item data via the annots and images helper objects
>>> aids = self.index.gid_to_aids[2]
>>> annots = self.annots(aids)

>>> print('annots = {}'.format(ub.repr2(annots, nl=1, sv=1)))
annots = <Annos(num=2)>

>>> annots.lookup('category_id')
[6, 4]

>>> annots.lookup('bbox')
[[37, 6, 230, 240], [124, 96, 45, 18]]

>>> # built in conversions to efficient kwimage array DataStructures
>>> print(ub.repr2(annots.detections.data, sv=1))
{
    'boxes': <Boxes(xywh,
                      array([[ 37.,   6., 230., 240.],
                             [124.,  96.,  45.,  18.]], dtype=float32))>,
    'class_idxs': [5, 3],
    'keypoints': <PointsList(n=2)>,
    'segmentations': <PolygonList(n=2)>,
}

>>> gids = list(self.imgs.keys())
>>> images = self.images(gids)
>>> print('images = {}'.format(ub.repr2(images, nl=1, sv=1)))
images = <Images(num=3)>

>>> images.lookup('file_name')
['...astro.png', '...carl.png', '...stars.png']

>>> print('images.annots = {}'.format(images.annots))
```

(continues on next page)

(continued from previous page)

```
images.annots = <AnnotGroups(n=3, m=3.7, s=3.9)>  
  
=> print('images.annots.cids = {!r}'.format(images.annots.cids))  
images.annots.cids = [[1, 2, 3, 4, 5, 5, 5, 5], [6, 4], []]
```



## COCODATASET API

The following is a logical grouping of the public `kwcoco.CocoDataset` API attributes and methods. See the in-code documentation for further details.

### 1.1 CocoDataset classmethods (via MixinCocoExtras)

- `kwcoco.CocoDataset.coerce` - Attempt to transform the input into the intended CocoDataset.
- `kwcoco.CocoDataset.demo` - Create a toy coco dataset for testing and demo puposes
- `kwcoco.CocoDataset.random` - Creates a random CocoDataset according to distribution parameters

### 1.2 CocoDataset classmethods (via CocoDataset)

- `kwcoco.CocoDataset.from_coco_paths` - Constructor from multiple coco file paths.
- `kwcoco.CocoDataset.from_data` - Constructor from a json dictionary
- `kwcoco.CocoDataset.from_image_paths` - Constructor from a list of images paths.

### 1.3 CocoDataset slots

- `kwcoco.CocoDataset.index` - an efficient lookup index into the coco data structure. The index defines its own attributes like `anns`, `cats`, `imgs`, `gid_to_aids`, `file_name_to_img`, etc. See `CocoIndex` for more details on which attributes are available.
- `kwcoco.CocoDataset.hashid` - If computed, this will be a hash uniquely identifying the dataset. To ensure this is computed see `kwcoco.coco_dataset.MixinCocoExtras._build_hashid()`.
- `kwcoco.CocoDataset.hashid_parts` -
- `kwcoco.CocoDataset.tag` - A tag indicating the name of the dataset.
- `kwcoco.CocoDataset.dataset` - raw json data structure. This is the base dictionary that contains {‘annotations’: List, ‘images’: List, ‘categories’: List}
- `kwcoco.CocoDataset.bundle_dpath` - If known, this is the root path that all image file names are relative to. This can also be manually overwritten by the user.
- `kwcoco.CocoDataset.assets_dpath` -
- `kwcoco.CocoDataset.cache_dpath` -

## 1.4 CocoDataset properties

- `kwcoco.CocoDataset.anns` -
- `kwcoco.CocoDataset.cats` -
- `kwcoco.CocoDataset.cid_to_aids` -
- `kwcoco.CocoDataset.data_fpath` -
- `kwcoco.CocoDataset.data_root` -
- `kwcoco.CocoDataset.fpath` - if known, this stores the filepath the dataset was loaded from
- `kwcoco.CocoDataset.gid_to_aids` -
- `kwcoco.CocoDataset.img_root` -
- `kwcoco.CocoDataset imgs` -
- `kwcoco.CocoDataset.n_annot`s -
- `kwcoco.CocoDataset.n_cat`s -
- `kwcoco.CocoDataset.n_imag`e -
- `kwcoco.CocoDataset.n_vide`o -
- `kwcoco.CocoDataset.name_to_cat` -

## 1.5 CocoDataset methods (via MixinCocoAddRemove)

- `kwcoco.CocoDataset.add_annotation` - Add an annotation to the dataset (dynamically updates the index)
- `kwcoco.CocoDataset.add_annotations` - Faster less-safe multi-item alternative to add\_annotation.
- `kwcoco.CocoDataset.add_category` - Adds a category
- `kwcoco.CocoDataset.add_image` - Add an image to the dataset (dynamically updates the index)
- `kwcoco.CocoDataset.add_images` - Faster less-safe multi-item alternative
- `kwcoco.CocoDataset.add_video` - Add a video to the dataset (dynamically updates the index)
- `kwcoco.CocoDataset.clear_annotation`s - Removes all annotations (but not images and categories)
- `kwcoco.CocoDataset.clear_images` - Removes all images and annotations (but not categories)
- `kwcoco.CocoDataset.ensure_category` - Like add\_category(), but returns the existing category id if it already exists instead of failing. In this case all metadata is ignored.
- `kwcoco.CocoDataset.ensure_image` - Like add\_image(), but returns the existing image id if it already exists instead of failing. In this case all metadata is ignored.
- `kwcoco.CocoDataset.remove_annotation` - Remove a single annotation from the dataset
- `kwcoco.CocoDataset.remove_annotation_keypoints` - Removes all keypoints with a particular category
- `kwcoco.CocoDataset.remove_annotation`s - Remove multiple annotations from the dataset.
- `kwcoco.CocoDataset.remove_categories` - Remove categories and all annotations in those categories. Currently does not change any hierarchy information
- `kwcoco.CocoDataset.remove_images` - Remove images and any annotations contained by them

- `kwcoco.CocoDataset.remove_keypoint_categories` - Removes all keypoints of a particular category as well as all annotation keypoints with those ids.
- `kwcoco.CocoDataset.remove_videos` - Remove videos and any images / annotations contained by them
- `kwcoco.CocoDataset.set_annotation_category` - Sets the category of a single annotation

## 1.6 CocoDataset methods (via MixinCocoObjects)

- `kwcoco.CocoDataset.annots` - Return vectorized annotation objects
- `kwcoco.CocoDataset.categories` - Return vectorized category objects
- `kwcoco.CocoDataset.images` - Return vectorized image objects
- `kwcoco.CocoDataset.videos` - Return vectorized video objects

## 1.7 CocoDataset methods (via MixinCocoStats)

- `kwcoco.CocoDataset.basic_stats` - Reports number of images, annotations, and categories.
- `kwcoco.CocoDataset.boxsize_stats` - Compute statistics about bounding box sizes.
- `kwcoco.CocoDataset.category_annotation_frequency` - Reports the number of annotations of each category
- `kwcoco.CocoDataset.category_annotation_type_frequency` - Reports the number of annotations of each type for each category
- `kwcoco.CocoDataset.conform` - Make the COCO file conform a stricter spec, infers attributes where possible.
- `kwcoco.CocoDataset.extended_stats` - Reports number of images, annotations, and categories.
- `kwcoco.CocoDataset.find_representative_images` - Find images that have a wide array of categories. Attempt to find the fewest images that cover all categories using images that contain both a large and small number of annotations.
- `kwcoco.CocoDataset.keypoint_annotation_frequency` -
- `kwcoco.CocoDataset.stats` - This function corresponds to `kwcoco.cli.coco_stats`.
- `kwcoco.CocoDataset.validate` - Performs checks on this coco dataset.

## 1.8 CocoDataset methods (via MixinCocoAccessors)

- `kwcoco.CocoDataset.category_graph` - Construct a networkx category hierarchy
- `kwcoco.CocoDataset.delayed_load` - Experimental method
- `kwcoco.CocoDataset.get_auxiliary_fpath` - Returns the full path to auxiliary data for an image
- `kwcoco.CocoDataset.get_image_fpath` - Returns the full path to the image
- `kwcoco.CocoDataset.keypoint_categories` - Construct a consistent CategoryTree representation of key-point classes
- `kwcoco.CocoDataset.load_annot_sample` - Reads the chip of an annotation. Note this is much less efficient than using a sampler, but it doesn't require disk cache.

- `kwcoco.CocoDataset.load_image` - Reads an image from disk and
- `kwcoco.CocoDataset.object_categories` - Construct a consistent CategoryTree representation of object classes

## 1.9 CocoDataset methods (via CocoDataset)

- `kwcoco.CocoDataset.copy` - Deep copies this object
- `kwcoco.CocoDataset.dump` - Writes the dataset out to the json format
- `kwcoco.CocoDataset.dumps` - Writes the dataset out to the json format
- `kwcoco.CocoDataset.subset` - Return a subset of the larger coco dataset by specifying which images to port. All annotations in those images will be taken.
- `kwcoco.CocoDataset.union` - Merges multiple CocoDataset items into one. Names and associations are retained, but ids may be different.
- `kwcoco.CocoDataset.view_sql` - Create a cached SQL interface to this dataset suitable for large scale multiproCESSing use cases.

## 1.10 CocoDataset methods (via MixinCocoExtras)

- `kwcoco.CocoDataset.corrupted_images` - Check for images that don't exist or can't be opened
- `kwcoco.CocoDataset.missing_images` - Check for images that don't exist
- `kwcoco.CocoDataset.rename_categories` - Rename categories with a potentially coarser categorization.
- `kwcoco.CocoDataset.reroot` - Rebase image/data paths onto a new image/data root.

## 1.11 CocoDataset methods (via MixinCocoDraw)

- `kwcoco.CocoDataset.draw_image` - Use kwimage to draw all annotations on an image and return the pixels as a numpy array.
- `kwcoco.CocoDataset.imread` - Loads a particular image
- `kwcoco.CocoDataset.show_image` - Use matplotlib to show an image with annotations overlaid

---

CHAPTER  
TWO

---

KWCOCO

## 2.1 kwcoco package

### 2.1.1 Subpackages

#### 2.1.1.1 kwcoco.cli package

##### 2.1.1.1.1 Submodules

###### 2.1.1.1.1.1 kwcoco.cli.coco\_conform module

```
class kwcoco.cli.coco_conform.CocoConformCLI
    Bases: object
    name = 'conform'

    class CLICConfig(data=None, default=None, cmdline=False)
        Bases: Config
        Infer properties to make the COCO file conform to different specs.

        Arguments can be used to control which information is inferred. By default, information such as image size, annotation area, are added to the file.

        Other arguments like --legacy and --mmlab can be used to conform to specifications expected by external tooling.

        epilog = '\n Example Usage:\n kwcoco conform --help\n kwcoco conform
--src=shapes8 --dst conformed.json\n kwcoco conform special:shapes8
conformed.json\n '

        default = {'compress': <Value(None: 'auto')>, 'dst': <Value(None: None)>,
        'ensure_imgszie': <Value(None: True)>, 'legacy': <Value(None: False)>,
        'mmlab': <Value(None: False)>, 'pycocotools_info': <Value(None: True)>,
        'src': <Value(None: None)>, 'workers': <Value(None: 8)>}

    @classmethod main(cmdline=True, **kw)
```

## Example

```
>>> from kwcococo.cli.coco_conform import * # NOQA
>>> import kwcococo
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwcococo/tests/cli/conform').ensuredir()
>>> dst = dpath / 'out.kwcoco.json'
>>> kw = {'src': 'special:shapes8', 'dst': dst, 'compress': True}
>>> cmdline = False
>>> cls = CocoConformCLI
>>> cls.main(cmdline, **kw)
```

### 2.1.1.1.2 kwcococo.cli.coco\_eval module

Wraps the logic in kwcococo/coco\_evaluator.py with a command line script

```
class kwcococo.cli.coco_eval.CocoEvalCLICConfig(data=None, default=None, cmdline=False)
    Bases: Config

    Evaluate and score predicted versus truth detections / classifications in a COCO dataset

    default = {'ap_method': <Value(None: 'pycocotools')>, 'area_range': <Value(None: ['all'])>, 'assign_workers': <Value(None: 8)>, 'classes_of_interest': <Value(<class 'list'>: None)>, 'compat': <Value(None: 'mutex')>, 'draw': <Value(None: True)>, 'expt_title': <Value(<class 'str'>: '')>, 'force_pycocoutils': <Value(None: False)>, 'fp_cutoff': <Value(None: inf)>, 'ignore_classes': <Value(<class 'list'>: None)>, 'implicit_ignore_classes': <Value(None: ['ignore'])>, 'implicit_negative_classes': <Value(None: ['background'])>, 'iou_bias': <Value(None: 1)>, 'iou_thresh': <Value(None: 0.5)>, 'load_workers': <Value(None: 0)>, 'max_dets': <Value(None: inf)>, 'monotonic_ppv': <Value(None: True)>, 'out_dpath': <Value(<class 'str'>: './coco_metrics')>, 'ovthresh': <Value(None: None)>, 'pred_dataset': <Value(<class 'str'>: None)>, 'true_dataset': <Value(<class 'str'>: None)>, 'use_area_attr': <Value(None: 'try')>, 'use_image_names': <Value(None: False)>}

class kwcococo.cli.coco_eval.CocoEvalCLI
    Bases: object

    name = 'eval'

    CLIConfig
        alias of CocoEvalCLICConfig

    classmethod main(cmdline=True, **kw)
```

## Example

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> from kwcoco.cli.coco_eval import * # NOQA
>>> import ubelt as ub
>>> from kwcoco.cli.coco_eval import * # NOQA
>>> from os.path import join
>>> import kwcoco
>>> dpath = ub.Path.appdir('kwcoco/tests/eval').ensuredir()
>>> true_dset = kwcoco.CocoDataset.demo('shapes8')
>>> from kwcoco.demo.perterb import perterb_coco
>>> kwargs = {
>>>     'box_noise': 0.5,
>>>     'n_fp': (0, 10),
>>>     'n_fn': (0, 10),
>>> }
>>> pred_dset = perterb_coco(true_dset, **kwargs)
>>> true_dset.fpath = join(dpath, 'true.mscoco.json')
>>> pred_dset.fpath = join(dpath, 'pred.mscoco.json')
>>> true_dset.dump(true_dset.fpath)
>>> pred_dset.dump(pred_dset.fpath)
>>> draw = False # set to false for faster tests
>>> CocoEvalCLI.main(
>>>     true_dataset=true_dset.fpath,
>>>     pred_dataset=pred_dset.fpath,
>>>     draw=draw, out_dpath=dpath)
```

`kwcoco.cli.coco_eval.main(cmdline=True, **kw)`

---

### Todo:

- [X] should live in `kwcoco.cli.coco_eval`
- 

## CommandLine

```
# Generate test data
xdoctest -m kwcoco.cli.coco_eval CocoEvalCLI.main

kwcoco eval \
    --true_dataset=$HOME/.cache/kwcoco/tests/eval/true.mscoco.json \
    --pred_dataset=$HOME/.cache/kwcoco/tests/eval/pred.mscoco.json \
    --out_dpath=$HOME/.cache/kwcoco/tests/eval/out \
    --force_pycocoutils=False \
    --area_range=all,0-4096,4096-inf

nautilus $HOME/.cache/kwcoco/tests/eval/out
```

### 2.1.1.1.3 kwcoco.cli.coco\_grab module

```
class kwcoco.cli.coco_grab.CocoGrabCLI
    Bases: object
    name = 'grab'

class CLIConfig(data=None, default=None, cmdline=False)
    Bases: Config
    Grab standard datasets.
```

#### Example

```
kwcoco grab cifar10 camvid
default = {'dpath': <Path(<class 'str'>: Path('/home/docs/.cache/kwcoco/data'))>, 'names': <Value(None: [])>}

@classmethod def main(cmdline=True, **kw)
```

### 2.1.1.1.4 kwcoco.cli.coco\_modify\_categories module

```
class kwcoco.cli.coco_modify_categories.CocoModifyCatsCLI
    Bases: object
    Remove, rename, or coarsen categories.

    name = 'modify_categories'

class CLIConfig(data=None, default=None, cmdline=False)
    Bases: Config
    Rename or remove categories

    epilog = '\n Example Usage:\n kwcoco modify_categories --help\n kwcoco
    modify_categories --src=special:shapes8 --dst modcats.json\n kwcoco
    modify_categories --src=special:shapes8 --dst modcats.json --rename
    eff:F,star:sun\n kwcoco modify_categories --src=special:shapes8 --dst
    modcats.json --remove eff,star\n kwcoco modify_categories --src=special:shapes8
    --dst modcats.json --keep eff,\n\n kwcoco modify_categories
    --src=special:shapes8 --dst modcats.json --keep=[] --keep_annot=True\n '

    default = {'compress': <Value(None: 'auto')>, 'dst': <Value(None: None)>,
    'keep': <Value(None: None)>, 'keep_annot': <Value(None: False)>, 'remove':
    <Value(None: None)>, 'rename': <Value(<class 'str'>: None)>, 'src':
    <Value(None: None)>}

    @classmethod def main(cmdline=True, **kw)
```

## Example

```
>>> # xdoctest: +SKIP
>>> kw = {'src': 'special:shapes8'}
>>> cmdline = False
>>> cls = CocoModifyCatsCLI
>>> cls.main(cmdline, **kw)
```

### 2.1.1.1.5 kwcoco.cli.coco\_reroot module

```
class kwcoco.cli.coco_reroot.CocoRerootCLI
    Bases: object

    name = 'reroot'

    class CLIConfig(data=None, default=None, cmdline=False)
        Bases: Config

        Reroot image paths onto a new image root.

        Modify the root of a coco dataset such to either make paths relative to a new root or make paths absolute.
```

---

#### Todo:

- [ ] Evaluate that all tests cases work
- 

```
epilog = '\n\n Example Usage:\n kwcoco reroot --help\n kwcoco reroot\n--src=special:shapes8 --dst rerooted.json\n kwcoco reroot --src=special:shapes8\n--new_prefix=foo --check=True --dst rerooted.json\n'

default = {'absolute': <Value(None: True)>, 'autofix': <Value(None: False)>,
'check': <Value(None: True)>, 'compress': <Value(None: 'auto')>, 'dst':
<Value(None: None)>, 'new_prefix': <Value(None: None)>, 'old_prefix':
<Value(None: None)>, 'src': <Value(None: None)>}
```

```
classmethod main(cmdline=True, **kw)
```

## Example

```
>>> # xdoctest: +SKIP
>>> kw = {'src': 'special:shapes8'}
>>> cmdline = False
>>> cls = CocoRerootCLI
>>> cls.main(cmdline, **kw)
```

`kwcoco.cli.coco_reroot.find_reroot_autofix(dset)`

### 2.1.1.1.6 kwcoco.cli.coco\_show module

```
class kwcoco.cli.coco_show.CocoShowCLI
    Bases: object
    name = 'show'

    class CLIConfig(data=None, default=None, cmdline=False)
        Bases: Config

        Visualize a COCO image using matplotlib or opencv, optionally writing it to disk

        epilog = '\n Example Usage:\n kwcoco show --help\n kwcoco show
--src=special:shapes8 --gid=1\n kwcoco show --src=special:shapes8 --gid=1 --dst
out.png\n '

        default = {'aid': <Value(None: None)>, 'channels': <Value(<class 'str'>):
None)>, 'dst': <Value(None: None)>, 'gid': <Value(None: None)>, 'mode':
<Value(None: 'matplotlib')>, 'show_annot': <Value(None: True)>,
'show_labels': <Value(None: False)>, 'src': <Value(None: None)>}

    classmethod main(cmdline=True, **kw)
```

---

#### Todo:

- [ ] Visualize auxiliary data
- 

#### Example

```
>>> # xdoctest: +SKIP
>>> kw = {'src': 'special:shapes8'}
>>> cmdline = False
>>> cls = CocoShowCLI
>>> cls.main(cmdline, **kw)
```

### 2.1.1.1.7 kwcoco.cli.coco\_split module

```
class kwcoco.cli.coco_split.CocoSplitCLI
```

Bases: object

Splits a coco files into two parts base on some criteria.

Useful for generating quick and dirty train/test splits, but in general users should opt for using `kwcoco subset` instead to explicitly construct these splits based on domain knowledge.

`name = 'split'`

```
class CLIConfig(data=None, default=None, cmdline=False)
```

Bases: Config

Split a single COCO dataset into two sub-datasets.

```

default = {'balance_categories': <Value(None: True)>, 'compress':
<Value(None: 'auto')>, 'dst1': <Value(None: 'split1.kwcoco.json')>, 'dst2':
<Value(None: 'split2.kwcoco.json')>, 'factor': <Value(None: 3)>, 'num_write':
<Value(None: 1)>, 'rng': <Value(None: None)>, 'splitter': <Value(None:
'auto')>, 'src': <Value(None: None)>}

epilog = '\n Example Usage:\n kwCOCO split --src special:shapes8
--dst1=learn.kwcoco.json --dst2=test.kwcoco.json --factor=3 --rng=42\n\n kwCOCO
split --src special:shapes8 --dst1="train_{03:d}.kwcoco.json"
--dst2="vali_{0:3d}.kwcoco.json" --factor=3 --rng=42\n '

classmethod main(cmdline=True, **kw)

```

### Example

```

>>> from kwCOCO.cli.coco_split import * # NOQA
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwCOCO/tests/cli/split').ensuredir()
>>> kw = {'src': 'special:vidshapes8',
>>>       'dst1': dpath / 'train.json',
>>>       'dst2': dpath / 'test.json'}
>>> cmdline = False
>>> cls = CocoSplitCLI
>>> cls.main(cmdline, **kw)

```

#### 2.1.1.1.8 kwCOCO.cli.coco\_stats module

```

class kwCOCO.cli.coco_stats.CocoStatsCLI
    Bases: object

    name = 'stats'

class CLIConfig(data=None, default=None, cmdline=False)
    Bases: Config

    Compute summary statistics about a COCO dataset

    default = {'annot_attrs': <Value(None: False)>, 'basic': <Value(None:
True)>, 'boxes': <Value(None: False)>, 'catfreq': <Value(None: True)>,
'embed': <Value(None: False)>, 'extended': <Value(None: True)>,
'image_attrs': <Value(None: False)>, 'image_size': <Value(None: False)>,
'src': <Value(None: ['special:shapes8'])>, 'video_attrs': <Value(None:
False)>}

    epilog = '\n Example Usage:\n kwCOCO stats --src=special:shapes8\n kwCOCO stats
--src=special:shapes8 --boxes=True\n '

    classmethod main(cmdline=True, **kw)

```

### Example

```
>>> kw = {'src': 'special:shapes8'}
>>> cmdline = False
>>> cls = CocoStatsCLI
>>> cls.main(cmdline, **kw)
```

#### 2.1.1.1.9 `kwCOCO.cli.coco_subset` module

```
class kwCOCO.cli.coco_subset.CocoSubsetCLI
    Bases: object
    name = 'subset'

    class CLIConfig(data=None, default=None, cmdline=False)
        Bases: Config
        Take a subset of this dataset and write it to a new file

        default = {'absolute': <Value(None: 'auto')>, 'channels': <Value(None: None)>, 'compress': <Value(None: 'auto')>, 'copy_assets': <Value(None: False)>, 'dst': <Value(None: None)>, 'gids': <Value(None: None)>, 'include_categories': <Value(<class 'str'>: None)>, 'select_images': <Value(<class 'str'>: None)>, 'select_videos': <Value(None: None)>, 'src': <Value(None: None)>}

        epilog = '\n Example Usage:\nkwCOCO subset --src special:shapes8\n--dst=foo.kwCOCO.json\n\n# Take only the even image-ids\nkwCOCO subset --src\nspecial:shapes8 --dst=foo-even.kwCOCO.json --select_images \'.id % 2 == 0\'\n\n# Take only the videos where the name ends with 2\nkwCOCO subset --src\nspecial:vidshapes8 --dst=vidsub.kwCOCO.json --select_videos \'.name |\nendswith("2")\'\n'

    @classmethod main(cmdline=True, **kw)
```

### Example

```
>>> from kwCOCO.cli.coco_subset import * # NOQA
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwCOCO/tests/cli/union').ensuredir()
>>> kw = {'src': 'special:shapes8',
>>>       'dst': dpath / 'subset.json',
>>>       'include_categories': 'superstar'}
>>> cmdline = False
>>> cls = CocoSubsetCLI
>>> cls.main(cmdline, **kw)
```

`kwCOCO.cli.coco_subset.query_subset(dset, config)`

## Example

```
>>> # xdoctest: +REQUIRES(module:jq)
>>> from kwcoco.cli.coco_subset import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> assert dset.n_images == 3
>>> #
>>> config = CocoSubsetCLI.CLICConfig({'select_images': '.id < 3'})
>>> new_dset = query_subset(dset, config)
>>> assert new_dset.n_images == 2
>>> #
>>> config = CocoSubsetCLI.CLICConfig({'select_images': '.file_name | test(".*.png")'})
>>> new_dset = query_subset(dset, config)
>>> assert all(n.endswith('.png') for n in new_dset.images().lookup('file_name'))
>>> assert new_dset.n_images == 2
>>> #
>>> config = CocoSubsetCLI.CLICConfig({'select_images': '.file_name | test(".*.png")' | not'})
>>> new_dset = query_subset(dset, config)
>>> assert not any(n.endswith('.png') for n in new_dset.images().lookup('file_name'))
>>> assert new_dset.n_images == 1
>>> #
>>> config = CocoSubsetCLI.CLICConfig({'select_images': '.id < 3 and (.file_name | test(".*.png"))'})
>>> new_dset = query_subset(dset, config)
>>> assert new_dset.n_images == 1
>>> #
>>> config = CocoSubsetCLI.CLICConfig({'select_images': '.id < 3 or (.file_name | test(".*.png"))'})
>>> new_dset = query_subset(dset, config)
>>> assert new_dset.n_images == 3
```

## Example

```
>>> # xdoctest: +REQUIRES(module:jq)
>>> from kwcoco.cli.coco_subset import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8')
>>> assert dset.n_videos == 8
>>> assert dset.n_images == 16
>>> config = CocoSubsetCLI.CLICConfig({'select_videos': '.name == "toy_video_3"'})
>>> new_dset = query_subset(dset, config)
>>> assert new_dset.n_images == 2
>>> assert new_dset.n_videos == 1
```

### 2.1.1.1.10 kwCOCO.cli.coco\_toydata module

```
class kwCOCO.cli.coco_toydata.CocoToyDataCLI
    Bases: object

    name = 'toydata'

    class CLIConfig(data=None, default=None, cmdline=False)
        Bases: Config

        Create COCO toydata for demo and testing purposes.

        default = {'bundle_dpath': <Value(None: None)>, 'dst': <Value(None: None)>,
                   'key': <Value(None: 'shapes8')>, 'use_cache': <Value(None: True)>,
                   'verbose': <Value(None: False)>}

        epilog = '\n Example Usage:\n kwCOCO toydata --key=shapes8
--dst=toydata.kwCOCO.json\n\n kwCOCO toydata --key=shapes8
--bundle_dpath=my_test_bundle_v1\n kwCOCO toydata --key=shapes8
--bundle_dpath=my_test_bundle_v1\n\n kwCOCO toydata \\\n
--key=vidshapes1-frames32 \\\n --dst=./mytoybundle/dataset.kwCOCO.json\n\n
TODO:\n - [ ] allow specification of images directory\n '

    classmethod main(cmdline=True, **kw)
```

#### Example

```
>>> from kwCOCO.cli.coco_toydata import * # NOQA
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwCOCO/tests/cli/demo').ensuredir()
>>> kw = {'key': 'shapes8', 'dst': dpath / 'test.json'}
>>> cmdline = False
>>> cls = CocoToyDataCLI
>>> cls.main(cmdline, **kw)
```

### 2.1.1.1.11 kwCOCO.cli.coco\_union module

```
class kwCOCO.cli.coco_union.CocoUnionCLI
    Bases: object

    name = 'union'

    class CLIConfig(data=None, default=None, cmdline=False)
        Bases: Config

        Combine multiple COCO datasets into a single merged dataset.

        default = {'absolute': <Value(None: False)>, 'compress': <Value(None:
                      'auto')>, 'dst': <Value(None: 'combo.kwCOCO.json')>, 'src': <Value(None:
                      [])>}

        epilog = '\n Example Usage:\n kwCOCO union --src special:shapes8 special:shapes1
--dst=combo.kwCOCO.json\n '

    classmethod main(cmdline=True, **kw)
```

**Example**

```
>>> from kwcoco.cli.coco_union import * # NOQA
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwcoco/tests/cli/union').ensuredir()
>>> dst_fpath = dpath / 'combo.kwcoco.json'
>>> kw = {
>>>     'src': ['special:shapes8', 'special:shapes1'],
>>>     'dst': dst_fpath
>>> }
>>> cmdline = False
>>> cls = CocoUnionCLI
>>> cls.main(cmdline, **kw)
```

**2.1.1.1.12 kwcoco.cli.coco\_validate module**

```
class kwcoco.cli.coco_validate.CocoValidateCLI
    Bases: object
    name = 'validate'

class CLIConfig(data=None, default=None, cmdline=False)
    Bases: Config
    Validates that a coco file satisfies expected properties.

    Checks that a coco file conforms to the json schema, that assets exist, and that other expected properties
    are satisfied.

    This also has the ability to fix corrupted assets by removing them, but that functionality may be moved to
    a new command in the future.

    default = {'channels': <Value(None: True)>, 'corrupted': <Value(None:
        False)>, 'dst': <Value(None: None)>, 'fastfail': <Value(None: False)>,
    'fix': <Value(None: None)>, 'imgAttrs': <Value(None: 'warn')>, 'missing':
    <Value(None: True)>, 'require_relative': <Value(None: False)>, 'schema':
    <Value(None: True)>, 'src': <Value(None: ['special:shapes8'])>, 'unique':
    <Value(None: True)>, 'verbose': <Value(None: 1)>}

    epilog = '\n Example Usage:\n kwcoco toydata --dst foo.json
    --key=special:shapes8\n kwcoco validate --src=foo.json --corrupted=True\n '


    classmethod main(cmdline=True, **kw)
```

**Example**

```
>>> from kwcoco.cli.coco_validate import * # NOQA
>>> kw = {'src': 'special:shapes8'}
>>> cmdline = False
>>> cls = CocoValidateCLI
>>> cls.main(cmdline, **kw)
```

### 2.1.1.1.2 Module contents

#### 2.1.1.2 kwcoco.data package

##### 2.1.1.2.1 Submodules

###### 2.1.1.2.1.1 kwcoco.data.grab\_camvid module

Downloads the CamVid data if necessary, and converts it to COCO.

```
kwcoco.data.grab_camvid.grab_camvid_train_val_splits(coco_dset, mode='segnet')
```

```
kwcoco.data.grab_camvid.grab_camvid_sampler()
```

Grab a kwcoco.CocoSampler object for the CamVid dataset.

##### Returns

```
sampler
```

##### Return type

```
kwcoco.CocoSampler
```

#### Example

```
>>> # xdoctest: +REQUIRES(--download)
>>> sampler = grab_camvid_sampler()
>>> print('sampler = {!r}'.format(sampler))
>>> # sampler.load_sample()
>>> for gid in ub.ProgIter(sampler.image_ids, desc='load image'):
>>>     img = sampler.load_image(gid)
```

```
kwcoco.data.grab_camvid.grab_coco_camvid()
```

#### Example

```
>>> # xdoctest: +REQUIRES(--download)
>>> dset = grab_coco_camvid()
>>> print('dset = {!r}'.format(dset))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> plt = kwplot.autoplts()
>>> plt.clf()
>>> dset.show_image(gid=1)
```

```
kwcoco.data.grab_camvid.grab_raw_camvid()
```

Grab the raw camvid data.

```
kwcoco.data.grab_camvid.rgb_to_cid(r, g, b)
```

```
kwcoco.data.grab_camvid.cid_to_rgb(cid)
```

```
kwcoco.data.grab_camvid.convert_camvid_raw_to_coco(camvid_raw_info)
```

Converts the raw camvid format to an MSCOCO based format, ( which lets use use kwcoco's COCO backend).

## Example

```
>>> # xdoctest: +REQUIRES(--download)
>>> camvid_raw_info = grab_raw_camvid()
>>> # test with a reduced set of data
>>> del camvid_raw_info['img_paths'][2:]
>>> del camvid_raw_info['mask_paths'][2:]
>>> dset = convert_camvid_raw_to_coco(camvid_raw_info)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> plt = kwplot.autoplts()
>>> kwplot.figure(fnum=1, pnum=(1, 2, 1))
>>> dset.show_image(gid=1)
>>> kwplot.figure(fnum=1, pnum=(1, 2, 2))
>>> dset.show_image(gid=2)
```

`kwcoco.data.grab_camvid.main()`

Dump the paths to the coco file to stdout

**By default these will go to in the path:**

`~/cache/kwcoco/camvid/camvid-master`

**The four files will be:**

`~/cache/kwcoco/camvid/camvid-master/camvid-full.ms coco.json`      `~/cache/kwcoco/camvid/camvid-master/camvid-train.ms coco.json`      `~/cache/kwcoco/camvid/camvid-master/camvid-vali.ms coco.json`  
`~/cache/kwcoco/camvid/camvid-master/camvid-test.ms coco.json`

### 2.1.1.2.1.2 `kwcoco.data.grab_cifar` module

### 2.1.1.2.1.3 `kwcoco.data.grab_datasets` module

#### Todo:

- [ ] UCF101 - Action Recognition Data Set - <https://www.crcv.ucf.edu/data/UCF101.php>
- [ ] HMDB: a large human motion database - <https://serre-lab.clps.brown.edu/resource/hmdb-a-large-human-motion-database/>
- [ ] <https://paperswithcode.com/dataset/imagenet>
- [ ] <https://paperswithcode.com/dataset/coco>
- [ ] <https://paperswithcode.com/dataset/fashion-mnist>
- [ ] <https://paperswithcode.com/dataset/visual-question-answering>
- [ ] <https://paperswithcode.com/dataset/lfw>
- [ ] <https://paperswithcode.com/dataset/lsun>
- [ ] <https://paperswithcode.com/dataset/ava>
- [ ] <https://paperswithcode.com/dataset/activitynet>
- [ ] <https://paperswithcode.com/dataset/clevr>

### 2.1.1.2.1.4 kwcoco.data.grab\_domainnet module

#### References

<http://ai.bu.edu/M3SDA/#dataset>

`kwcoco.data.grab_domainnet.grab_domain_net()`

---

#### Todo:

- [ ] Allow the user to specify the download directory, generalize this pattern across the data grab scripts.
- 

### 2.1.1.2.1.5 kwcoco.data.grab\_spacenet module

#### References

<https://medium.com/the-downlinq/the-spacenet-7-multi-temporal-urban-development-challenge-algorithmic-baseline-4515ec9bd9fe>  
<https://arxiv.org/pdf/2102.11958.pdf> <https://spacenet.ai/sn7-challenge/>

`kwcoco.data.grab_spacenet.grab_spacenet7(data_dpath)`

#### References

<https://spacenet.ai/sn7-challenge/>

#### Requires:

awscli

`kwcoco.data.grab_spacenet.convert_spacenet_to_kwcoco(extract_dpath, coco_fpath)`

Converts the raw SpaceNet7 dataset to kwcoco

---

#### Note:

- The “train” directory contains 60 “videos” representing a region over time.
- **Each “video” directory contains :**
  - images - unmasked images
  - images\_masked - images with masks applied
  - labels - geojson polys in wgs84?
  - labels\_match - geojson polys in wgs84 with track ids?
  - labels\_match\_pix - geojson polys in pixels with track ids?
  - UDM\_masks - unusable data masks (binary data corresponding with an image, may not exist)

#### File names appear like:

“global\_monthly\_2018\_01\_mosaic\_L15-1538E-1163N\_6154\_3539\_13”

---

`kwcoco.data.grab_spacenet.main()`

### 2.1.1.2.1.6 kwcoco.data.grab\_voc module

```
kwcoco.data.grab_voc.convert_voc_to_coco(dpath=None)
```

```
kwcoco.data.grab_voc.ensure_voc_data(dpath=None, force=False, years=[2007, 2012])
```

Download the Pascal VOC data if it does not already exist.

---

#### Note:

- [ ] These URLs seem to be dead
- 

#### Example

```
>>> # xdoctest: +REQUIRES(--download)
>>> devkit_dpath = ensure_voc_data()
```

```
kwcoco.data.grab_voc.ensure_voc_coco(dpath=None)
```

Download the Pascal VOC data and convert it to coco, if it does exit.

#### Parameters

**dpath** (*str* | *None*) – download directory. Defaults to “~/data/VOC”.

#### Returns

**mapping from dataset tags to coco file paths.**

The original datasets have keys prefixed with underscores. The standard splits keys are train, vali, and test.

#### Return type

*Dict*[*str*, *str*]

```
kwcoco.data.grab_voc.main()
```

### 2.1.1.2.2 Module contents

### 2.1.1.3 kwcoco.demo package

#### 2.1.1.3.1 Submodules

##### 2.1.1.3.1.1 kwcoco.demo.boids module

```
class kwcoco.demo.Boids(num, dims=2, rng=None, **kwargs)
```

Bases: *NiceRepr*

Efficient numpy based backend for generating boid positions.


BOID = bird-oid object

## References

<https://www.youtube.com/watch?v=mhjuuHl6qHM> <https://medium.com/better-programming/boids-simulating-birds-flock-behavior-in-python-9fff99375118> <https://en.wikipedia.org/wiki/Boids>

## Example

```
>>> from kwcoc.demo.boids import * # NOQA
>>> num_frames = 10
>>> num_objects = 3
>>> rng = None
>>> self = Boids(num=num_objects, rng=rng).initialize()
>>> paths = self.paths(num_frames)
>>> #
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> plt = kwplot.autopl()
>>> from mpl_toolkits.mplot3d import Axes3D # NOQA
>>> ax = plt.gca(projection='3d')
>>> ax.cla()
>>> #
>>> for path in paths:
>>>     time = np.arange(len(path))
>>>     ax.plot(time, path.T[0] * 1, path.T[1] * 1, ',-')
>>> ax.set_xlim(0, num_frames)
>>> ax.set_ylim(-.01, 1.01)
>>> ax.set_zlim(-.01, 1.01)
>>> ax.set_xlabel('time')
>>> ax.set_ylabel('u-pos')
>>> ax.set_zlabel('v-pos')
>>> kwplot.show_if_requested()
```



```
import xdev _ = xdev.profile_now(self.compute_forces()) _ = xdev.profile_now(self.update_neighbors())
```

### Example

```
>>> # Test determinism
>>> from kwcoc.demo.boids import * # NOQA
>>> num_frames = 2
>>> num_objects = 1
>>> rng = 4532
>>> self = Boids(num=num_objects, rng=rng).initialize()
>>> #print(ub.hash_data(self.pos))
>>> #print(ub.hash_data(self.vel))
>>> #print(ub.hash_data(self.acc))
>>> tocheck = []
>>> for i in range(100):
>>>     self = Boids(num=num_objects, rng=rng).initialize()
>>>     self.step()
>>>     self.step()
>>>     self.step()
>>>     tocheck.append(self.pos.copy())
>>> assert ub.allsame(list(map(ub.hash_data, tocheck)))
```

`initialize()`

```
update_neighbors()
compute_forces()
boundary_conditions()
step()
    Update positions, velocities, and accelerations
paths(num_steps)

kwcoc.demo.boids.clamp_mag(vec, mag, axis=None)
vec = np.random.rand(10, 2) mag = 1.0 axis = 1 new_vec = clamp_mag(vec, mag, axis) np.linalg.norm(new_vec,
axis=axis)

kwcoc.demo.boids.triu_condense_multi_index(multi_index, dims, symmetric=False)
Like np.ravel_multi_index but returns positions in an upper triangular condensed square matrix
```

## Examples

### multi\_index (Tuple[ArrayLike]):

indexes for each dimension into the square matrix

### dims (Tuple[int]):

shape of each dimension in the square matrix (should all be the same)

### symmetric (bool):

if True, converts lower triangular indices to their upper triangular location. This may cause a copy to occur.

## References

<https://stackoverflow.com/a/36867493/887074> [https://numpy.org/doc/stable/reference/generated/numpy.ravel\\_multi\\_index.html#numpy.ravel\\_multi\\_index](https://numpy.org/doc/stable/reference/generated/numpy.ravel_multi_index.html#numpy.ravel_multi_index)

## Examples

```
>>> dims = (3, 3)
>>> symmetric = True
>>> multi_index = (np.array([0, 0, 1]), np.array([1, 2, 2]))
>>> condensed_idxs = triu_condense_multi_index(multi_index, dims, symmetric=symmetric)
>>> assert condensed_idxs.tolist() == [0, 1, 2]
```

```
>>> n = 7
>>> symmetric = True
>>> multi_index = np.triu_indices(n=n, k=1)
>>> condensed_idxs = triu_condense_multi_index(multi_index, [n] * 2, ↵
    ↵symmetric=symmetric)
>>> assert condensed_idxs.tolist() == list(range(n * (n - 1) // 2))
>>> from scipy.spatial.distance import pdist, squareform
>>> square_mat = np.zeros((n, n))
>>> condens_mat = squareform(square_mat)
>>> condens_mat[condensed_idxs] = np.arange(len(condensed_idxs)) + 1
>>> square_mat = squareform(condens_mat)
>>> print('square_mat =\n{}\n'.format(ub.repr2(square_mat, nl=1)))
```

```
>>> n = 7
>>> symmetric = True
>>> multi_index = np.tril_indices(n=n, k=-1)
>>> condensed_idxs = triu_condense_multi_index(multi_index, [n] * 2, ↴
    ↪symmetric=symmetric)
>>> assert sorted(condensed_idxs.tolist()) == list(range(n * (n - 1) // 2))
>>> from scipy.spatial.distance import pdist, squareform
>>> square_mat = np.zeros((n, n))
>>> condens_mat = squareform(square_mat, checks=False)
>>> condens_mat[condensed_idxs] = np.arange(len(condensed_idxs)) + 1
>>> square_mat = squareform(condens_mat)
>>> print('square_mat =\n{}'.format(ub.repr2(square_mat, nl=1)))
```

`kwcoco.demo.boids.closest_point_on_line_segment(pts, e1, e2)`

Finds the closet point from p on line segment (e1, e2)

#### Parameters

- `pts (ndarray)` – xy points [Nx2]
- `e1 (ndarray)` – the first xy endpoint of the segment
- `e2 (ndarray)` – the second xy endpoint of the segment

#### Returns

`pt_on_seg` - the closest xy point on (e1, e2) from ptp

#### Return type

`ndarray`

## References

[http://en.wikipedia.org/wiki/Distance\\_from\\_a\\_point\\_to\\_a\\_line](http://en.wikipedia.org/wiki/Distance_from_a_point_to_a_line)    <http://stackoverflow.com/questions/849211/shortest-distance-between-a-point-and-a-line-segment>

## Example

```
>>> # ENABLE_DOCTEST
>>> from kwcoco.demo.boids import * # NOQA
>>> verts = np.array([[ 21.83012702,  13.16987298],
>>>                   [ 16.83012702,  21.83012702],
>>>                   [  8.16987298,  16.83012702],
>>>                   [ 13.16987298,   8.16987298],
>>>                   [ 21.83012702,  13.16987298]])
```

### 2.1.1.3.1.2 kwcoco.demo.perterb module

`kwcoco.demo.perterb.perterb_coco(coco_dset, **kwargs)`


Perterbs a coco dataset

#### Parameters

- `rng (int, default=0)`
- `box_noise (int, default=0)`
- `cls_noise (int, default=0)`
- `null_pred (bool, default=False)`
- `with_probs (bool, default=False)`
- `score_noise (float, default=0.2)`
- `hacked (int, default=1)`

#### Example

```
>>> from kwcoco.demo.perterb import * # NOQA
>>> from kwcoco.demo.perterb import _demo_construct_probs
>>> import kwcoco
>>> coco_dset = true_dset = kwcoco.CocoDataset.demo('shapes2')
>>> kwargs = {
>>>     'box_noise': 0.5,
>>>     'n_fp': 3,
>>>     'with_probs': 1,
>>>     'with_heatmaps': 1,
>>> }
>>> pred_dset = perterb_coco(true_dset, **kwargs)
>>> pred_dset._check_json_serializable()
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> gid = 1
>>> canvas = true_dset.delayed_load(gid).finalize()
>>> canvas = true_dset.annots(gid=gid).detections.draw_on(canvas, color='green')
>>> canvas = pred_dset.annots(gid=gid).detections.draw_on(canvas, color='blue')
>>> kwplot.imshow(canvas)
```



### 2.1.1.3.1.3 `kwcoco.demo.toydata module`

Generates “toydata” for demo and testing purposes.

---

**Note:** The implementation of `demodata_toy_img` and `demodata_toy_dset` should be redone using the tools built for `random_video_dset`, which have more extensible implementations.

---

```
kwcoco.demo.toydata.demodata_toy_dset(image_size=(600, 600), n_imgs=5, verbose=3, rng=0,
                                         newstyle=True, dpath=None, fpath=None, bundle_dpath=None,
                                         aux=None, use_cache=True, **kwargs)
```

Create a toy detection problem

#### Parameters

- **image\_size** (`Tuple[int, int]`) – The width and height of the generated images
- **n\_imgs** (`int`) – number of images to generate
- **rng** (`int | RandomState | None`) – random number generator or seed. Defaults to 0.
- **newstyle** (`bool`) – create newstyle kwcoco data. default=True
- **dpath** (`str | PathLike | None`) – path to the directory that will contain the bundle, (defaults to a kwcoco cache dir). Ignored if `bundle_dpath` is given.

- **fpath** (*str | PathLike | None*) – path to the kwcoco file. The parent will be the bundle if it is not specified. Should be a descendant of the dpath if specified.
- **bundle\_dpath** (*str | PathLike | None*) – path to the directory that will store images. If specified, dpath is ignored. If unspecified, a bundle will be written inside *dpath*.
- **aux** (*bool | None*) – if True generates dummy auxiliary channels
- **verbose** (*int*) – verbosity mode. default=3
- **use\_cache** (*bool*) – if True caches the generated json in the *dpath*. Default=True
- **\*\*kwargs** – used for old backwards compatible argument names gsize - alias for image\_size

**Return type**

*kwcoco.CocoDataset*

**SeeAlso:**

`random_video_dset`

**CommandLine**

```
xdoctest -m kwcoco.demo.toydata_image demodata_toy_dset --show
```

---

**Todo:**

- [ ] Non-homogeneous images sizes
- 


**Example**

```
>>> from kwcoco.demo.toydata_image import *
>>> import kwcoco
>>> dset = demodata_toy_dset(image_size=(300, 300), aux=True, use_cache=False)
>>> # xdoctest: +REQUIRES(--show)
>>> print(ub.repr2(dset.dataset, nl=2))
>>> import kwplot
>>> kwplot.autompl()
>>> dset.show_image(gid=1)
>>> ub.startfile(dset.bundle_dpath)
```

`dset._tree()`

```
>>> from kwcoco.demo.toydata_image import *
>>> import kwcoco
```

```
cs.cache/kwcoco/demodata_bundles/shapes_5_gjnxqrhunjrzxt/_assets/images/0
```



```
dset = demodata_toy_dset(image_size=(300, 300), aux=True, use_cache=False) print(dset.imgs[1]) dset._tree()
dset = demodata_toy_dset(image_size=(300, 300), aux=True, use_cache=False,
                         bundle_dpath='test_bundle')
print(dset.imgs[1]) dset._tree()
dset = demodata_toy_dset(
    image_size=(300, 300), aux=True, use_cache=False, dpath='test_cache_dpath')
kwCOCO.demo.toydata.random_single_video_dset(image_size=(600, 600), num_frames=5, num_tracks=3,
                                              tid_start=1, gid_start=1, video_id=1, anchors=None,
                                              rng=None, render=False, dpath=None, autobuild=True,
                                              verbose=3, aux=None, multispectral=False,
                                              max_speed=0.01, channels=None, multisensor=False,
                                              **kwargs)
```

Create the video scene layout of object positions.

---

**Note:** Does not render the data unless specified.

---

#### Parameters

- **image\_size** (*Tuple[int, int]*) – size of the images
- **num\_frames** (*int*) – number of frames in this video
- **num\_tracks** (*int*) – number of tracks in this video

- **tid\_start** (*int*) – track-id start index, default=1
- **gid\_start** (*int*) – image-id start index, default=1
- **video\_id** (*int*) – video-id of this video, default=1
- **anchors** (*ndarray | None*) – base anchor sizes of the object boxes we will generate.
- **rng** (*RandomState | None | int*) – random state / seed
- **render** (*bool | dict*) – if truthy, does the rendering according to provided params in the case of dict input.
- **autobuild** (*bool*) – prebuild coco lookup indexes, default=True
- **verbose** (*int*) – verbosity level
- **aux** (*bool | None | List[str]*) – if specified generates auxiliary channels
- **multispectral** (*bool*) – if specified simulates multispectral imagery This is similar to aux, but has no “main” file.
- **max\_speed** (*float*) – max speed of movers
- **channels** (*str | None | kwcoco.ChannelSpec*) – if specified generates multispectral images with dummy channels
- **multisensor** (*bool*) –  
if True, generates demodata from “multiple sensors”, in  
other words, observations may have different “bands”.
- **\*\*kwargs** – used for old backwards compatible argument names gsize - alias for image\_size

---

**Todo:**

- [ ] Need maximum allowed object overlap measure
  - [ ] Need better parameterized path generation
- 

**Example**

```
>>> import numpy as np
>>> from kwcoco.demo.toydata_video import random_single_video_dset
>>> anchors = np.array([ [0.3, 0.3], [0.1, 0.1] ])
>>> dset = random_single_video_dset(render=True, num_frames=5,
>>>                               num_tracks=3, anchors=anchors,
>>>                               max_speed=0.2, rng=91237446)
>>> # xdoctest: +REQUIRES(--show)
>>> # Show the tracks in a single image
>>> import kwplot
>>> import kwimage
>>> #kwplot.autosns()
>>> kwplot.autoplt()
>>> # Group track boxes and centroid locations
>>> paths = []
>>> track_boxes = []
>>> for tid, aids in dset.index.trackid_to_aids.items():
```

(continues on next page)



(continued from previous page)

```

>>> boxes = dset.annots(aids).boxes.to_cxywh()
>>> path = boxes.data[:, 0:2]
>>> paths.append(path)
>>> track_boxes.append(boxes)
>>> # Plot the tracks over time
>>> ax = kwplot.figure(fnum=1, doclf=1).gca()
>>> colors = kwimage.Color.distinct(len(track_boxes))
>>> for i, boxes in enumerate(track_boxes):
>>>     color = colors[i]
>>>     path = boxes.data[:, 0:2]
>>>     boxes.draw(color=color, centers={'radius': 0.01}, alpha=0.8)
>>>     ax.plot(path.T[0], path.T[1], 'x-', color=color)
>>> ax.invert_yaxis()
>>> ax.set_title('Track locations flattened over time')
>>> # Plot the image sequence
>>> fig = kwplot.figure(fnum=2, doclf=1)
>>> gids = list(dset.imgs.keys())
>>> pnums = kwplot.PlotNums(nRows=1, nSubplots=len(gids))
>>> for gid in gids:
>>>     dset.show_image(gid, pnum=pnums(), fnum=2, title=f'Image {gid}', show_aid=0,
>>>     ↪ setlim='image')
>>> fig.suptitle('Video Frames')
>>> fig.set_size_inches(15.4, 4.0)
>>> fig.tight_layout()
>>> kwplot.show_if_requested()

```

Track locations flattened over time




## Example

```
>>> from kwCOCO.demo.toydata_video import * # NOQA
>>> anchors = np.array([ [0.2, 0.2], [0.1, 0.1] ])
>>> gsize = np.array([(600, 600)])
>>> print(anchors * gsize)
>>> dset = random_single_video_dset(render=True, num_frames=10,
>>>                               anchors=anchors, num_tracks=10,
>>>                               image_size='random')
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> plt = kwplot.autoplot()
>>> plt.clf()
```

(continues on next page)

(continued from previous page)

```
>>> gids = list(dset.imgs.keys())
>>> pnums = kwplot.PlotNums(nSubplots=len(gids))
>>> for gid in gids:
>>>     dset.show_image(gid, pnum=pnums(), fnum=1, title=f'Image {gid}')
>>> kwplot.show_if_requested()
```




```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> dset = random_single_video_dset(num_frames=10, num_tracks=10, aux=True)
>>> assert 'auxiliary' in dset.imgs[1]
>>> assert dset.imgs[1]['auxiliary'][0]['channels']
>>> assert dset.imgs[1]['auxiliary'][1]['channels']
```

## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> multispectral = True
>>> dset = random_single_video_dset(num_frames=1, num_tracks=1, multispectral=True)
>>> dset._check_json_serializable()
>>> dset.dataset['images']
>>> assert dset.imgs[1]['auxiliary'][1]['channels']
>>> # test that we can render
>>> render_toy_dataset(dset, rng=0, dpath=None, renderkw={})
```

## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> dset = random_single_video_dset(num_frames=4, num_tracks=1, multispectral=True, ↴
    ↪multisensor=True, image_size='random', rng=2338)
>>> dset._check_json_serializable()
>>> assert dset.imgs[1]['auxiliary'][1]['channels']
>>> # Print before and after render
>>> #print('multisensor-images = {}'.format(ub.repr2(dset.dataset['images'], nl=-2)))
>>> #print('multisensor-images = {}'.format(ub.repr2(dset.dataset, nl=-2)))
>>> print(ub.hash_data(dset.dataset))
>>> # test that we can render
>>> render_toy_dataset(dset, rng=0, dpath=None, renderkw={})
>>> #print('multisensor-images = {}'.format(ub.repr2(dset.dataset['images'], nl=-2)))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> from kwcoco.demo.toydata_video import _draw_video_sequence # NOQA
>>> gids = [1, 2, 3, 4]
>>> final = _draw_video_sequence(dset, gids)
>>> print('dset.fpath = {!r}'.format(dset.fpath))
>>> kwplot.imshow(final)
```



```
kwCOCO.demo.toydata.random_video_dset(num_videos=1, num_frames=2, num_tracks=2, anchors=None,  
                                         image_size=(600, 600), verbose=3, render=False, aux=None,  
                                         multispectral=False, multisensor=False, rng=None, dpath=None,  
                                         max_speed=0.01, channels=None, **kwargs)
```

Create a toy Coco Video Dataset

#### Parameters


- **num\_videos** (*int*) – number of videos
- **num\_frames** (*int*) – number of images per video
- **num\_tracks** (*int*) – number of tracks per video
- **image\_size** (*Tuple[int, int]*) – The width and height of the generated images
- **render** (*bool | dict*) – if truthy the toy annotations are synthetically rendered. See `render_toy_image()` for details.
- **rng** (*int | None | RandomState*) – random seed / state
- **dpath** (*str | PathLike | None*) – only used if render is truthy, place to write rendered images.
- **verbose** (*int*) – verbosity mode, default=3
- **aux** (*bool | None*) – if True generates dummy auxiliary channels
- **multispectral** (*bool*) – similar to aux, but does not have the concept of a “main” image.
- **max\_speed** (*float*) – max speed of movers
- **channels** (*str | None*) – experimental new way to get MSI with specific band distributions.

- **\*\*kwargs** – used for old backwards compatible argument names gsize - alias for image\_size

**SeeAlso:**[random\\_single\\_video\\_dset](#)**Example**


```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> dset = random_video_dset(render=True, num_videos=3, num_frames=2,
>>>                               num_tracks=5, image_size=(128, 128))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> dset.show_image(1, doclf=True)
>>> dset.show_image(2, doclf=True)
```

```
>>> from kwcoco.demo.toydata_video import * # NOQA
dset = random_video_dset(render=False, num_videos=3, num_frames=2,
    num_tracks=10)
dset._tree()
dset.imgs[1]
```



## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> # Test small images
>>> dset = random_video_dset(render=True, num_videos=1, num_frames=1,
>>>                      num_tracks=1, image_size=(2, 2))
>>> ann = dset.annots().peek()
>>> print('ann = {}'.format(ub.urepr(ann, nl=2)))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> dset.show_image(1, doclf=True)
```



`kwcoco.demo.toydata.demodata_toy_img(anchors=None, image_size=(104, 104), categories=None, n_annot=(0, 50), fg_scale=0.5, bg_scale=0.8, bg_intensity=0.1, fg_intensity=0.9, gray=True, centerobj=None, exact=False, newstyle=True, rng=None, aux=None, **kwargs)`

Generate a single image with non-overlapping toy objects of available categories.

---

### Todo:

#### DEPRECATE IN FAVOR OF

`random_single_video_dset + render_toy_image`

---

## Parameters

- **anchors** (*ndarray | None*) – Nx2 base width / height of boxes
- **gsize** (*Tuple[int, int]*) – width / height of the image
- **categories** (*List[str] | None*) – list of category names
- **n\_annot** (*Tuple | int*) – controls how many annotations are in the image. if it is a tuple, then it is interpreted as uniform random bounds
- **fg\_scale** (*float*) – standard deviation of foreground intensity
- **bg\_scale** (*float*) – standard deviation of background intensity
- **bg\_intensity** (*float*) – mean of background intensity
- **fg\_intensity** (*float*) – mean of foreground intensity
- **centerobj** (*bool | None*) – if ‘pos’, then the first annotation will be in the center of the image, if ‘neg’, then no annotations will be in the center.
- **exact** (*bool*) – if True, ensures that exactly the number of specified annots are generated.
- **newstyle** (*bool*) – use new-style kwcoco format
- **rng** (*RandomState | int | None*) – the random state used to seed the process
- **aux** (*bool | None*) – if specified builds auxiliary channels
- **\*\*kwargs** – used for old backwards compatible argument names. gsize - alias for image\_size

## CommandLine

```
xdotest -m kwcoco.demo.toydata_image demodata_toy_img:0 --profile  
xdotest -m kwcoco.demo.toydata_image demodata_toy_img:1 --show
```

## Example

```
>>> from kwcoco.demo.toydata_image import * # NOQA  
>>> img, anns = demodata_toy_img(image_size=(32, 32), anchors=[[.3, .3]], rng=0)  
>>> img['imdata'] = '<ndarray shape={}>'.format(img['imdata'].shape)  
>>> print('img = {}'.format(ub.repr2(img)))  
>>> print('anns = {}'.format(ub.repr2(anns, nl=2, cbr=True)))  
>>> # xdotest: +IGNORE_WANT  
img = {  
    'height': 32,  
    'imdata': '<ndarray shape=(32, 32, 3)>',  
    'width': 32,  
}  
anns = [{  
    'bbox': [15, 10, 9, 8],  
    'category_name': 'star',  
    'keypoints': [],  
    'segmentation': {'counts': '[`06j0000020N1000e8', 'size': [32, 32]},},  
{'bbox': [11, 20, 7, 7],  
    'category_name': 'star',  
    'keypoints': [],  
    'segmentation': {'counts': 'g;1m04N0020N102L[=', 'size': [32, 32]},},
```



(continues on next page)

(continued from previous page)

```
{'bbox': [4, 4, 8, 6],
 'category_name': 'superstar',
 'keypoints': [{'keypoint_category': 'left_eye', 'xy': [7.25, 6.8125]}, {'keypoint_category': 'right_eye', 'xy': [8.75, 6.8125]}],
 'segmentation': {'counts': 'U4210j0300001010000MV00ed0', 'size': [32, 32]},},
{'bbox': [3, 20, 6, 7],
 'category_name': 'star',
 'keypoints': [],
 'segmentation': {'counts': 'g31m04N000002L[f0', 'size': [32, 32]},},]
```


## Example

```
>>> # xdoctest: +REQUIRES(--show)
>>> img, anns = demodata_toy_img(image_size=(172, 172), rng=None, aux=True)
>>> print('anns = {}'.format(ub.repr2(anns, nl=1)))
>>> import kwplot
>>> kwplot.autompl()
>>> kwplot.imshow(img['imdata'], pnum=(1, 2, 1), fnum=1)
>>> auxdata = img['auxiliary'][0]['imdata']
>>> kwplot.imshow(auxdata, pnum=(1, 2, 2), fnum=1)
>>> kwplot.show_if_requested()
```



## Example

```
>>> # xdoctest: +REQUIRES(--show)
>>> img, anns = demodata_toy_img(image_size=(172, 172), rng=None, aux=True)
>>> print('anns = {}'.format(ub.repr2(anns, nl=1)))
>>> import kwplot
>>> kwplot.autopl()
>>> kwplot.imshow(img['imdata'], pnum=(1, 2, 1), fnum=1)
>>> auxdata = img['auxiliary'][0]['imdata']
>>> kwplot.imshow(auxdata, pnum=(1, 2, 2), fnum=1)
>>> kwplot.show_if_requested()
```



### 2.1.1.3.1.4 kwcoc.demo.toydata\_image module

Generates “toydata” for demo and testing purposes.

Loose image version of the toydata generators.

---

**Note:** The implementation of *demodata\_toy\_img* and *demodata\_toy\_dset* should be redone using the tools built for *random\_video\_dset*, which have more extensible implementations.

---

---

```
kwcoco.demo.toydata_image.demodata_toy_dset(image_size=(600, 600), n_imgs=5, verbose=3, rng=0,
                                              newstyle=True, dpath=None, fpath=None,
                                              bundle_dpath=None, aux=None, use_cache=True,
                                              **kwargs)
```

Create a toy detection problem

#### Parameters

- **image\_size** (*Tuple[int, int]*) – The width and height of the generated images
- **n\_imgs** (*int*) – number of images to generate
- **rng** (*int | RandomState | None*) – random number generator or seed. Defaults to 0.
- **newstyle** (*bool*) – create newstyle kwcoco data. default=True
- **dpath** (*str | PathLike | None*) – path to the directory that will contain the bundle, (defaults to a kwcoco cache dir). Ignored if *bundle\_dpath* is given.
- **fpath** (*str | PathLike | None*) – path to the kwcoco file. The parent will be the bundle if it is not specified. Should be a descendant of the dpath if specified.
- **bundle\_dpath** (*str | PathLike | None*) – path to the directory that will store images. If specified, dpath is ignored. If unspecified, a bundle will be written inside *dpath*.
- **aux** (*bool | None*) – if True generates dummy auxiliary channels
- **verbose** (*int*) – verbosity mode. default=3
- **use\_cache** (*bool*) – if True caches the generated json in the *dpath*. Default=True
- **\*\*kwargs** – used for old backwards compatible argument names gsize - alias for image\_size

#### Return type

*kwcoco.CocoDataset*

#### SeeAlso:

[random\\_video\\_dset](#)

#### CommandLine

```
xdoctest -m kwcoco.demo.toydata_image demodata_toy_dset --show
```

---

#### Todo:

- [ ] Non-homogeneous images sizes
- 

#### Example

```
>>> from kwcoco.demo.toydata_image import *
>>> import kwcoco
>>> dset = demodata_toy_dset(image_size=(300, 300), aux=True, use_cache=False)
>>> # xdoctest: +REQUIRES(--show)
>>> print(ub.repr2(dset.dataset, nl=2))
>>> import kwplot
>>> kwplot.autompl()
```

(continues on next page)


(continued from previous page)

```
>>> dset.show_image(gid=1)
>>> ub.startfile(dset.bundle_dpath)
```

dset.\_tree()

```
>>> from kwcoco.demo.toydata_image import *
>>> import kwcoco
```

cs/.cache/kwcoco/demodata\_bundles/shapes\_5\_gjnxqrhunjrzxt/\_assets/image



```
dset = demodata_toy_dset(image_size=(300, 300), aux=True, use_cache=False) print(dset.imgs[1]) dset._tree()
dset = demodata_toy_dset(image_size=(300, 300), aux=True, use_cache=False,
                        bundle_dpath='test_bundle')
print(dset.imgs[1]) dset._tree()
dset = demodata_toy_dset(
    image_size=(300, 300), aux=True, use_cache=False, dpath='test_cache_dpath')
kwcoco.demo.toydata_image.demodata_toy_img(anchors=None, image_size=(104, 104), categories=None,
                                             n_annot=(0, 50), fg_scale=0.5, bg_scale=0.8,
                                             bg_intensity=0.1, fg_intensity=0.9, gray=True,
                                             centerobj=None, exact=False, newstyle=True, rng=None,
                                             aux=None, **kwargs)
```

Generate a single image with non-overlapping toy objects of available categories.

---

**Todo:**

**DEPRECATE IN FAVOR OF**

random\_single\_video\_dset + render\_toy\_image

**Parameters**

- **anchors** (*ndarray* | *None*) – Nx2 base width / height of boxes
- **gsize** (*Tuple[int, int]*) – width / height of the image
- **categories** (*List[str]* | *None*) – list of category names
- **n\_annot** (*Tuple* | *int*) – controls how many annotations are in the image. if it is a tuple, then it is interpreted as uniform random bounds
- **fg\_scale** (*float*) – standard deviation of foreground intensity
- **bg\_scale** (*float*) – standard deviation of background intensity
- **bg\_intensity** (*float*) – mean of background intensity
- **fg\_intensity** (*float*) – mean of foreground intensity
- **centerobj** (*bool* | *None*) – if ‘pos’, then the first annotation will be in the center of the image, if ‘neg’, then no annotations will be in the center.
- **exact** (*bool*) – if True, ensures that exactly the number of specified annots are generated.
- **newstyle** (*bool*) – use new-syle kwcoco format
- **rng** (*RandomState* | *int* | *None*) – the random state used to seed the process
- **aux** (*bool* | *None*) – if specified builds auxiliary channels
- **\*\*kwargs** – used for old backwards compatible argument names. gsize - alias for image\_size

**CommandLine**

```
xdoctest -m kwcoco.demo.toydata_image demodata_toy_img:0 --profile
xdoctest -m kwcoco.demo.toydata_image demodata_toy_img:1 --show
```

**Example**

```
>>> from kwcoco.demo.toydata_image import * # NOQA
>>> img, anns = demodata_toy_img(image_size=(32, 32), anchors=[[.3, .3]], rng=0)
>>> img['imdata'] = '<ndarray shape={}>'.format(img['imdata'].shape)
>>> print('img = {}'.format(ub.repr2(img)))
>>> print('anns = {}'.format(ub.repr2(anns, nl=2, cbr=True)))
>>> # xdoctest: +IGNORE_WANT
img = {
    'height': 32,
    'imdata': '<ndarray shape=(32, 32, 3)>',
    'width': 32,
}
anns = [{`bbox`: [15, 10, 9, 8],
    'category_name': 'star',
    'keypoints': [],
    'segmentation': {'counts': '[`06j0000020N1000e8', 'size': [32, 32]}},}
```


(continues on next page)

(continued from previous page)

```
{'bbox': [11, 20, 7, 7],
 'category_name': 'star',
 'keypoints': [],
 'segmentation': {'counts': 'g;1m04N0020N102L[=', 'size': [32, 32]},},
{'bbox': [4, 4, 8, 6],
 'category_name': 'superstar',
 'keypoints': [{"keypoint_category': 'left_eye', 'xy': [7.25, 6.8125]}, {"keypoint_category': 'right_eye', 'xy': [8.75, 6.8125]}],
 'segmentation': {'counts': 'U4210j0300001010000MV00ed0', 'size': [32, 32]},},
{'bbox': [3, 20, 6, 7],
 'category_name': 'star',
 'keypoints': [],
 'segmentation': {'counts': 'g31m04N000002L[f0', 'size': [32, 32]},},]
```


## Example

```
>>> # xdoctest: +REQUIRES(--show)
>>> img, anns = demodata_toy_img(image_size=(172, 172), rng=None, aux=True)
>>> print('anns = {}'.format(ub.repr2(anns, nl=1)))
>>> import kwplot
>>> kwplot.autompl()
>>> kwplot.imshow(img['imdata'], pnum=(1, 2, 1), fnum=1)
>>> auxdata = img['auxiliary'][0]['imdata']
>>> kwplot.imshow(auxdata, pnum=(1, 2, 2), fnum=1)
>>> kwplot.show_if_requested()
```



## Example

```
>>> # xdoctest: +REQUIRES(--show)
>>> img, anns = demodata_toy_img(image_size=(172, 172), rng=None, aux=True)
>>> print('anns = {}'.format(ub.repr2(anns, nl=1)))
>>> import kwplot
>>> kwplot.autompl()
>>> kwplot.imshow(img['imdata'], pnum=(1, 2, 1), fnum=1)
>>> auxdata = img['auxiliary'][0]['imdata']
>>> kwplot.imshow(auxdata, pnum=(1, 2, 2), fnum=1)
>>> kwplot.show_if_requested()
```



### 2.1.1.3.1.5 kwcoco.demo.toydata\_video module

Generates “toydata” for demo and testing purposes.

This is the video version of the toydata generator and should be preferred to the loose image version in `toydata_image`.

```
kwcoco.demo.toydata_video.random_video_dset(num_videos=1, num_frames=2, num_tracks=2,
                                             anchors=None, image_size=(600, 600), verbose=3,
                                             render=False, aux=None, multispectral=False,
                                             multisensor=False, rng=None, dpath=None,
                                             max_speed=0.01, channels=None, **kwargs)
```

Create a toy Coco Video Dataset

#### Parameters

- `num_videos` (*int*) – number of videos
- `num_frames` (*int*) – number of images per video
- `num_tracks` (*int*) – number of tracks per video
- `image_size` (*Tuple[int, int]*) – The width and height of the generated images
- `render` (*bool | dict*) – if truthy the toy annotations are synthetically rendered. See [`render\_toy\_image\(\)`](#) for details.
- `rng` (*int | None | RandomState*) – random seed / state
- `dpath` (*str | PathLike | None*) – only used if render is truthy, place to write rendered images.

- **verbose** (*int*) – verbosity mode, default=3
- **aux** (*bool* | *None*) – if True generates dummy auxiliary channels
- **multiplespectral** (*bool*) – similar to aux, but does not have the concept of a “main” image.
- **max\_speed** (*float*) – max speed of movers
- **channels** (*str* | *None*) – experimental new way to get MSI with specific band distributions.
- **\*\*kwargs** – used for old backwards compatible argument names gsize - alias for image\_size


**SeeAlso:**

`random_single_video_dset`

**Example**


```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> dset = random_video_dset(render=True, num_videos=3, num_frames=2,
>>>                               num_tracks=5, image_size=(128, 128))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> dset.show_image(1, doclf=True)
>>> dset.show_image(2, doclf=True)
```

```
>>> from kwcoco.demo.toydata_video import * # NOQA
dset = random_video_dset(render=False, num_videos=3, num_frames=2,
                           num_tracks=10)
dset._tree()
dset.imgs[1]
```



## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> # Test small images
>>> dset = random_video_dset(render=True, num_videos=1, num_frames=1,
>>>                         num_tracks=1, image_size=(2, 2))
>>> ann = dset.annots().peek()
>>> print('ann = {}'.format(ub.urepr(ann, nl=2)))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> dset.show_image(1, doclf=True)
```



```
kwcoco.demo.toydata_video.random_single_video_dset(image_size=(600, 600), num_frames=5,
                                                    num_tracks=3, tid_start=1, gid_start=1,
                                                    video_id=1, anchors=None, rng=None,
                                                    render=False, dpath=None, autobuild=True,
                                                    verbose=3, aux=None, multispectral=False,
                                                    max_speed=0.01, channels=None,
                                                    multisensor=False, **kwargs)
```

Create the video scene layout of object positions.

---

**Note:** Does not render the data unless specified.

---

#### Parameters

- **image\_size** (*Tuple[int, int]*) – size of the images
- **num\_frames** (*int*) – number of frames in this video
- **num\_tracks** (*int*) – number of tracks in this video
- **tid\_start** (*int*) – track-id start index, default=1
- **gid\_start** (*int*) – image-id start index, default=1
- **video\_id** (*int*) – video-id of this video, default=1
- **anchors** (*ndarray | None*) – base anchor sizes of the object boxes we will generate.
- **rng** (*RandomState | None | int*) – random state / seed

- **render** (*bool | dict*) – if truthy, does the rendering according to provided params in the case of dict input.
- **autobuild** (*bool*) – prebuild coco lookup indexes, default=True
- **verbose** (*int*) – verbosity level
- **aux** (*bool | None | List[str]*) – if specified generates auxiliary channels
- **multispectral** (*bool*) – if specified simulates multispectral imagery This is similar to aux, but has no “main” file.
- **max\_speed** (*float*) – max speed of movers
- **channels** (*str | None | kwcoco.ChannelSpec*) – if specified generates multispectral images with dummy channels
- **multisensor** (*bool*) –  
if True, generates demodata from “multiple sensors”, in  
other words, observations may have different “bands”.
- **\*\*kwargs** – used for old backwards compatible argument names gsize - alias for image\_size

---

**Todo:**

- [ ] Need maximum allowed object overlap measure
  - [ ] Need better parameterized path generation
- 

**Example**

```
>>> import numpy as np
>>> from kwcoco.demo.toydata_video import random_single_video_dset
>>> anchors = np.array([ [0.3, 0.3], [0.1, 0.1] ])
>>> dset = random_single_video_dset(render=True, num_frames=5,
>>>                               num_tracks=3, anchors=anchors,
>>>                               max_speed=0.2, rng=91237446)
>>> # xdoctest: +REQUIRES(--show)
>>> # Show the tracks in a single image
>>> import kwplot
>>> import kwimage
>>> #kwplot.autosns()
>>> kwplot.autoplt()
>>> # Group track boxes and centroid locations
>>> paths = []
>>> track_boxes = []
>>> for tid, aids in dset.index.trackid_to_aids.items():
>>>     boxes = dset.annots(aids).boxes.to_cxywh()
>>>     path = boxes.data[:, 0:2]
>>>     paths.append(path)
>>>     track_boxes.append(boxes)
>>> # Plot the tracks over time
>>> ax = kwplot.figure(fnum=1, doclf=1).gca()
>>> colors = kwimage.Color.distinct(len(track_boxes))
>>> for i, boxes in enumerate(track_boxes):
```

(continues on next page)


(continued from previous page)


```

>>> color = colors[i]
>>> path = boxes.data[:, 0:2]
>>> boxes.draw(color=color, centers={'radius': 0.01}, alpha=0.8)
>>> ax.plot(path.T[0], path.T[1], 'x-', color=color)
>>> ax.invert_yaxis()
>>> ax.set_title('Track locations flattened over time')
>>> # Plot the image sequence
>>> fig = kwplot.figure(fnum=2, doclf=1)
>>> gids = list(dset.imgs.keys())
>>> pnums = kwplot.PlotNums(nRows=1, nSubplots=len(gids))
>>> for gid in gids:
>>>     dset.show_image(gid, pnum=pnums(), fnum=2, title=f'Image {gid}', show_aid=0,
>>>     setlim='image')
>>> fig.suptitle('Video Frames')
>>> fig.set_size_inches(15.4, 4.0)
>>> fig.tight_layout()
>>> kwplot.show_if_requested()

```


Track locations flattened over time





## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> anchors = np.array([ [0.2, 0.2], [0.1, 0.1]] )
>>> gsize = np.array([(600, 600)])
>>> print(anchors * gsize)
>>> dset = random_single_video_dset(render=True, num_frames=10,
>>>                               anchors=anchors, num_tracks=10,
>>>                               image_size='random')
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> plt = kwplot.autoplt()
>>> plt.clf()
>>> gids = list(dset.imgs.keys())
>>> pnums = kwplot.PlotNums(nSubplots=len(gids))
>>> for gid in gids:
>>>     dset.show_image(gid, pnum=pnums(), fnum=1, title=f'Image {gid}')
>>> kwplot.show_if_requested()
```



## Example


```
>>> from kwCOCO.demo.toydata_video import * # NOQA
>>> dset = random_single_video_dset(num_frames=10, num_tracks=10, aux=True)
>>> assert 'auxiliary' in dset.imgs[1]
>>> assert dset.imgs[1]['auxiliary'][0]['channels']
>>> assert dset.imgs[1]['auxiliary'][1]['channels']
```

## Example

```
>>> from kwCOCO.demo.toydata_video import * # NOQA
>>> multispectral = True
>>> dset = random_single_video_dset(num_frames=1, num_tracks=1, multispectral=True)
>>> dset._check_json_serializable()
>>> dset.dataset['images']
>>> assert dset.imgs[1]['auxiliary'][1]['channels']
>>> # test that we can render
>>> render_toy_dataset(dset, rng=0, dpath=None, renderkw={})
```

## Example

```
>>> from kwCOCO.demo.toydata_video import * # NOQA
>>> dset = random_single_video_dset(num_frames=4, num_tracks=1, multispectral=True, ↴
    ↵multisensor=True, image_size='random', rng=2338)
>>> dset._check_json_serializable()
>>> assert dset.imgs[1]['auxiliary'][1]['channels']
>>> # Print before and after render
>>> #print('multisensor-images = {}'.format(ub.repr2(dset.dataset['images'], nl=-2)))
>>> #print('multisensor-images = {}'.format(ub.repr2(dset.dataset, nl=-2)))
>>> print(ub.hash_data(dset.dataset))
>>> # test that we can render
>>> render_toy_dataset(dset, rng=0, dpath=None, renderkw={})
>>> #print('multisensor-images = {}'.format(ub.repr2(dset.dataset['images'], nl=-2)))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> from kwCOCO.demo.toydata_video import _draw_video_sequence # NOQA
>>> gids = [1, 2, 3, 4]
>>> final = _draw_video_sequence(dset, gids)
>>> print('dset.fpath = {!r}'.format(dset.fpath))
>>> kwplot.imshow(final)
```



`kwCOCO.demo.toydata_video.render_toy_dataset(dset, rng, dpath=None, renderkw=None, verbose=0)`

Create toydata\_video renderings for a preconstructed coco dataset.

## Parameters

- **dset** (*kwcoco.CocoDataset*) – A dataset that contains special “renderable” annotations. (e.g. the demo shapes). Each image can contain special fields that influence how an image will be rendered.


Currently this process is simple, it just creates a noisy image with the shapes superimposed over where they should exist as indicated by the annotations. In the future this may become more sophisticated.

Each item in *dset.dataset['images']* will be modified to add the “file\_name” field indicating where the rendered data is written.

- **rng** (*int | None | RandomState*) – random state
- **dpath** (*str | PathLike | None*) – The location to write the images to. If unspecified, it is written to the rendered folder inside the kwcoco cache directory.
- **renderkw** (*dict | None*) – See [render\\_toy\\_image\(\)](#) for details. Also takes imwrite keywords args only handled in this function. TODO better docs.

## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> import kwarray
>>> rng = None
>>> rng = kwarray.ensure_rng(rng)
>>> num_tracks = 3
>>> dset = random_video_dset(rng=rng, num_videos=3, num_frames=5,
>>>                           num_tracks=num_tracks, image_size=(128, 128))
>>> dset = render_toy_dataset(dset, rng)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> plt = kwplot.autoplt()
>>> plt.clf()
>>> gids = list(dset.imgs.keys())
>>> pnums = kwplot.PlotNums(nSubplots=len(gids), nRows=num_tracks)
>>> for gid in gids:
>>>     dset.show_image(gid, pnum=pnums(), fnum=1, title=False)
>>> pnums = kwplot.PlotNums(nSubplots=len(gids))
```



`kwCOCO.demo.toydata_video.render_toy_image(dset, gid, rng=None, renderkw=None)`

Modifies dataset inplace, rendering synthetic annotations.

This does not write to disk. Instead this writes to placeholder values in the image dictionary.

#### Parameters

- `dset` (*kwCOCO.CocoDataset*) – coco dataset with renderable annotations / images
- `gid` (*int*) – image to render
- `rng` (*int | None | RandomState*) – random state
- `renderkw` (*dict | None*) – rendering config gray (bool): gray or color images fg\_scale (float): foreground noisiness (gauss std) bg\_scale (float): background noisiness (gauss std) fg\_intensity (float): foreground brightness (gauss mean) bg\_intensity (float): background brightness (gauss mean) newstyle (bool): use new kwCOCO datastructure formats with\_kpts (bool): include keypoint info with\_sseg (bool): include segmentation info

#### Returns

the inplace-modified image dictionary

#### Return type


Dict

## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> image_size=(600, 600)
>>> num_frames=5
>>> verbose=3
>>> rng = None
>>> import kwarray
>>> rng = kwarray.ensure_rng(rng)
>>> aux = 'mx'
>>> dset = random_single_video_dset(
>>>     image_size=image_size, num_frames=num_frames, verbose=verbose, aux=aux, ↴
>>>     rng=rng)
>>> print('dset.dataset = {}'.format(ub.repr2(dset.dataset, nl=2)))
>>> gid = 1
>>> renderkw = {}
>>> render_toy_image(dset, gid, rng, renderkw=renderkw)
>>> img = dset.imgs[gid]
>>> canvas = img['imdata']
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> kwplot.imshow(canvas, doclf=True, pnum=(1, 2, 1))
>>> dets = dset.annots(gid=gid).detections
>>> dets.draw()
```

```
>>> auxdata = img['auxiliary'][0]['imdata']
>>> aux_canvas = false_color(auxdata)
>>> kwplot.imshow(aux_canvas, pnum=(1, 2, 2))
>>> _ = dets.draw()
```

```
>>> # xdoctest: +REQUIRES(--show)
>>> img, anns = demodata_toy_img(image_size=(172, 172), rng=None, aux=True)
>>> print('anns = {}'.format(ub.repr2(anns, nl=1)))
>>> import kwplot
>>> kwplot.autopl()
>>> kwplot.imshow(img['imdata'], pnum=(1, 2, 1), fnum=1)
>>> auxdata = img['auxiliary'][0]['imdata']
>>> kwplot.imshow(auxdata, pnum=(1, 2, 2), fnum=1)
>>> kwplot.show_if_requested()
```



## Example

```
>>> from kwCOCO.demo.toydata_video import * # NOQA
>>> multispectral = True
>>> dset = random_single_video_dset(num_frames=1, num_tracks=1, multispectral=True)
>>> gid = 1
>>> dset.imgs[gid]
>>> rng = kwarray.ensure_rng(0)
>>> renderkw = {'with_sseg': True}
>>> img = render_toy_image(dset, gid, rng=rng, renderkw=renderkw)
```

```
kwCOCO.demo.toydata_video.render_foreground(imdata, chan_to_auxinfo, dset, annots, catpats, with_sseg,
                                              with_kpts, dims, newstyle, gray, rng)
```

Renders demo annotations on top of a demo background

```
kwCOCO.demo.toydata_video.render_background(img, rng, gray, bg_intensity, bg_scale)
```

```
kwCOCO.demo.toydata_video.false_color(twochan)
```

TODO: the function ensure\_false\_color will eventually be ported to kwimage use that instead.

```
kwCOCO.demo.toydata_video.random_multi_object_path(num_objects, num_frames, rng=None,
                                                    max_speed=0.01)
```

```
kwCOCO.demo.toydata_video.random_path(num, degree=1, dimension=2, rng=None, mode='boid')
```

Create a random path using a somem ethod curve.

## Parameters


- **num** (*int*) – number of points in the path
- **degree** (*int*) – degree of curviness of the path, default=1
- **dimension** (*int*) – number of spatial dimensions, default=2
- **mode** (*str*) – can be boid, walk, or bezier
- **rng** (*RandomState | None | int*) – seed, default=None

## References

<https://github.com/dhermes/bezier>

## Example

```
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> num = 10
>>> dimension = 2
>>> degree = 3
>>> rng = None
>>> path = random_path(num, degree, dimension, rng, mode='boid')
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> plt = kwplot.autoplt()
>>> kwplot.multi_plot(xdata=path[:, 0], ydata=path[:, 1], fnum=1, doclf=1, xlim=(0, 1), ylim=(0, 1))
>>> kwplot.show_if_requested()
```



## Example

```
>>> # xdoctest: +REQUIRES(--3d)
>>> # xdoctest: +REQUIRES(module:bezier)
>>> import kwarray
>>> import kwplot
>>> plt = kwplot.autoplt()
>>> #
>>> num= num_frames = 100
>>> rng = kwarray.ensure_rng(0)
>>> #
>>> from kwcoco.demo.toydata_video import * # NOQA
>>> paths = []
>>> paths.append(random_path(num, degree=3, dimension=3, mode='bezier'))
>>> paths.append(random_path(num, degree=2, dimension=3, mode='bezier'))
>>> paths.append(random_path(num, degree=4, dimension=3, mode='bezier'))
>>> #
>>> from mpl_toolkits.mplot3d import Axes3D # NOQA
>>> ax = plt.gca(projection='3d')
>>> ax.cla()
>>> #
>>> for path in paths:
>>>     time = np.arange(len(path))
```

(continues on next page)

(continued from previous page)

```
>>>     ax.plot(time, path.T[0] * 1, path.T[1] * 1, 'o-')
>>> ax.set_xlim(0, num_frames)
>>> ax.set_ylim(-.01, 1.01)
>>> ax.set_zlim(-.01, 1.01)
>>> ax.set_xlabel('x')
>>> ax.set_ylabel('y')
>>> ax.set_zlabel('z')
```


### 2.1.1.3.1.6 kwcoco.demo.toypatterns module

```
class kwcoco.demo.toypatterns.CategoryPatterns(categories=None, fg_scale=0.5, fg_intensity=0.9,
                                                rng=None)
```

Bases: object

#### Example

```
>>> from kwcoco.demo.toypatterns import * # NOQA
>>> self = CategoryPatterns.coerce()
>>> chip = np.zeros((100, 100, 3))
>>> offset = (20, 10)
>>> dims = (160, 140)
>>> info = self.random_category(chip, offset, dims)
>>> print('info = {}'.format(ub.repr2(info, nl=1)))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> kwplot.imshow(info['data'], pnum=(1, 2, 1), fnum=1, title='chip-space')
>>> kpts = kwimage.Points._from_coco(info['keypoints'])
>>> kpts.translate(-np.array(offset)).draw(radius=3)
>>> #####
>>> mask = kwimage.Mask.coerce(info['segmentation'])
>>> kwplot.imshow(mask.to_c_mask().data, pnum=(1, 2, 2), fnum=1, title='img-space')
>>> kpts.draw(radius=3)
>>> kwplot.show_if_requested()
```



**classmethod coerce**(*data=None, \*\*kwargs*)

Construct category patterns from either defaults or only with specific categories. Can accept either an existing category pattern object, a list of known catnames, or mscoco category dictionaries.

### Example

```
>>> data = ['superstar']
>>> self = CategoryPatterns.coerce(data)
```

**index**(*name*)

**get**(*index, default=NoParam*)

**random\_category**(*chip, xy\_offset=None, dims=None, newstyle=True, size=None*)

**Example**

```
>>> from kwcoco.demo.toypatterns import * # NOQA
>>> self = CategoryPatterns.coerce(['superstar'])
>>> chip = np.random.rand(64, 64)
>>> info = self.random_category(chip)
```

`render_category(cname, chip, xy_offset=None, dims=None, newstyle=True, size=None)`

**Example**

```
>>> from kwcoco.demo.toypatterns import * # NOQA
>>> self = CategoryPatterns.coerce(['superstar'])
>>> chip = np.random.rand(64, 64)
>>> info = self.render_category('superstar', chip, newstyle=True)
>>> print('info = {}'.format(ub.repr2(info, nl=-1)))
>>> info = self.render_category('superstar', chip, newstyle=False)
>>> print('info = {}'.format(ub.repr2(info, nl=-1)))
```

**Example**

```
>>> from kwcoco.demo.toypatterns import * # NOQA
>>> self = CategoryPatterns.coerce(['superstar'])
>>> chip = None
>>> dims = (64, 64)
>>> info = self.render_category('superstar', chip, newstyle=True, dims=dims,
>                                size=dims)
>>> print('info = {}'.format(ub.repr2(info, nl=-1)))
```

`kwcoco.demo.toypatterns.star(a, dtype=<class 'numpy.uint8'>)`

Generates a star shaped structuring element.

Much faster than skimage.morphology version

`class kwcoco.demo.toypatterns.Rasters`

Bases: `object`

`static superstar()`

test data patch

`static eff()`

test data patch

### 2.1.1.3.2 Module contents

#### 2.1.1.4 kwcoco.examples package

##### 2.1.1.4.1 Submodules

###### 2.1.1.4.1.1 kwcoco.examples.bench\_large\_hyperspectral module

###### 2.1.1.4.1.2 kwcoco.examples.draw\_gt\_and\_predicted\_boxes module

```
kwcoco.examples.draw_gt_and_predicted_boxes.draw_true_and_pred_boxes(true_fpath, pred_fpath,  
                     gid, viz_fpath)
```

How do you generally visualize gt and predicted bounding boxes together?

#### Example

```
>>> import kwcoco  
>>> import ubelt as ub  
>>> from os.path import join  
>>> from kwcoco.demo.perterb import perterb_coco  
>>> # Create a working directory  
>>> dpath = ub.Path.appdir('kwcoco/examples/draw_true_and_pred_boxes').ensuredir()  
>>> # Lets setup some dummy true data  
>>> true_dset = kwcoco.CocoDataset.demo('shapes2')  
>>> true_dset.fpath = join(dpath, 'true_dset.kwcoco.json')  
>>> true_dset.dump(true_dset.fpath, newlines=True)  
>>> # Lets setup some dummy predicted data  
>>> pred_dset = perterb_coco(true_dset, box_noise=100, rng=421)  
>>> pred_dset.fpath = join(dpath, 'pred_dset.kwcoco.json')  
>>> pred_dset.dump(pred_dset.fpath, newlines=True)  
>>> #  
>>> # We now have our true and predicted data, lets visualize  
>>> true_fpath = true_dset.fpath  
>>> pred_fpath = pred_dset.fpath  
>>> print('dpath = {!r}'.format(dpath))  
>>> print('true_fpath = {!r}'.format(true_fpath))  
>>> print('pred_fpath = {!r}'.format(pred_fpath))  
>>> # Lets choose an image id to visualize and a path to write to  
>>> gid = 1  
>>> viz_fpath = join(dpath, 'viz_{}.jpg'.format(gid))  
>>> # The answer to the question is in the logic of this function  
>>> draw_true_and_pred_boxes(true_fpath, pred_fpath, gid, viz_fpath)
```

### 2.1.1.4.1.3 kwcoco.examples.faq module

These are answers to the questions: How do I?

`kwcoco.examples.faq.get_images_with_videoid()`

Q: How would you recommend querying a kwcoco file to get all of the images associated with a video id?

`kwcoco.examples.faq.get_all_channels_in_dataset()`

Q. After I load a kwcoco.json into a kwcoco\_dset, is there a nice way to query what channels are available for the input imagery? It looks like I can iterate over .imgs and build my own set, but maybe theres a built in way

A. The better way is to use the CocoImage API.

`kwcoco.examples.faq.whats_the_difference_between_Images_and_CocoImage()`

Q. What is the difference between *kwcoco.Images* and *kwcoco.CocoImage*.

It's a little weird because it grew organically, but the "vectorized API" calls like `.images`, `.annots`, `.videos` are methods for handling multiple dictionaries at once. E.g. `dset.images().lookup('width')` returns a list of the width attribute for each dictionary that particular *Images* object is indexing (which by default is all of them, although you can filter).

In contrast the *kwcoco.CocoImage* object is for working with exactly one image. The important thing to note is if you have a CocoImage `coco_img = dset.coco_image(1)` The `coco_img.img` attribute is exactly the underlying dictionary. So you are never too far away from it.

Similarly for the *Images* objects: `dset.images().objs` returns a list of all of the image dictionaries in that set.

### 2.1.1.4.1.4 kwcoco.examples.getting\_started\_existing\_dataset module

`kwcoco.examples.getting_started_existing_dataset.getting_started_existing_dataset()`

If you want to start using the Python API. Just open IPython and try:

`kwcoco.examples.getting_started_existing_dataset.the_core_dataset_backend()`

`kwcoco.examples.getting_started_existing_dataset.demo_vectorize_interface()`

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes2')
>>> #
>>> aids = [1, 2, 3, 4]
>>> annots = dset.annots(aids)
...
>>> print('annots = {!r}'.format(annots))
annots = <Annots(num=4) at ...>
```

```
>>> annots.lookup('bbox')
[[346.5, 335.2, 33.2, 99.4],
 [344.5, 327.7, 48.8, 111.1],
 [548.0, 154.4, 57.2, 62.1],
 [548.7, 151.0, 59.4, 80.5]]
```

```
>>> gids = annots.lookup('image_id')
>>> print('gids = {!r}'.format(gids))
gids = [1, 2, 1, 2]
```

```
>>> images = dset.images(gids)
>>> list(zip(images.lookup('width'), images.lookup('height')))
[(600, 600), (600, 600), (600, 600), (600, 600)]
```

### 2.1.1.4.1.5 kwcoco.examples.loading\_multispectral\_data module

`kwcoco.examples.loading_multispectral_data.demo_load_msi_data()`

### 2.1.1.4.1.6 kwcoco.examples.modification\_example module

`kwcoco.examples.modification_example.dataset_modification_example_via_copy()`

Say you are given a dataset as input and you need to add your own annotation “predictions” to it. You could copy the existing dataset, remove all the annotations, and then add your new annotations.

`kwcoco.examples.modification_example.dataset_modification_example_via_construction()`

Alternatively you can make a new dataset and copy over categories / images as needed

### 2.1.1.4.1.7 kwcoco.examples.simple\_kwcoco\_torch\_dataset module

This example demonstrates how to use kwcoco to write a very simple torch dataset. This assumes the dataset will be single-image RGB inputs. This file is intended to talk the reader through what we are doing and why.

This example aims for clarity over being concise. There are APIs exposed by kwcoco (and its sister module ndsampler) that can perform the same tasks more efficiently and with fewer lines of code.

If you run the doctest, it will produce a visualization that shows the images with boxes drawn on it, running it multiple times will let you see the augmentations. This can be done with the following command:

```
xdoctest -m kwcoco.examples.simple_kwcoco_torch_dataset KW CocoSimpleTorchDataset --show
```

Or just copy the doctest into IPython and run it.

```
class kwcoco.examples.simple_kwcoco_torch_dataset.KW CocoSimpleTorchDataset(coco_dset,
                           input_dims=None,
                           antialias=False,
                           rng=None)
```

Bases: `object`

A simple torch dataloader where each image is considered a single item.

#### Parameters

- **coco\_dset** (`kwcoco.CocoDataset` | `str`) – something coercable to a kwcoco dataset, this could either be a `kwcoco.CocoDataset` object, a path to a kwcoco manifest on disk, or a special toydata code. See `kwcoco.CocoDataset.coerce()` for more details.
- **input\_dims** (`Tuple[int, int]`) – These are the (height, width) dimensions that the image will be resized to.
- **antialias** (`bool, default=False`) – If true, we will antialias before downsampling.
- **rng** (`RandomState` | `int` | `None`) – an existing random number generator or a random seed to produce deterministic augmentations.

## Example

```
>>> # xdoctest: +REQUIRES(module:torch)
>>> from kwcoco.examples.simple_kwococo_torch_dataset import * # NOQA
>>> import kwcoco
>>> coco_dset = kwcoco.CocoDataset.demo('shapes8')
>>> input_dims = (384, 384)
>>> self = torch_dset = KW CocoSimpleTorchDataset(coco_dset, input_dims=input_dims)
>>> index = len(self) // 2
>>> item = self[index]
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.figure(doclf=True, fnum=1)
>>> kwplot.autopl()
>>> canvas = item['inputs']['rgb'].numpy().transpose(1, 2, 0)
>>> # Construct kwimage objects for batch item visualization
>>> dets = kwimage.Detections(
>>>     boxes=kwimage.Boxes(item['labels']['cxywh'], 'cxywh'),
>>>     class_idxs=item['labels']['class_idxs'],
>>>     classes=self.classes,
>>> ).numpy()
>>> # Overlay annotations on the image
>>> canvas = dets.draw_on(canvas)
>>> kwplot.imshow(canvas)
>>> kwplot.show_if_requested()
```

### 2.1.1.4.1.8 kwcoco.examples.vectorized\_interface module

#### kwcoco.examples.vectorized\_interface.demo\_vectorized\_interface()

This demonstrates how to use the kwcoco vectorized interface for images / categories / annotations.

### 2.1.1.4.2 Module contents

#### 2.1.1.5 kwcoco.metrics package

##### 2.1.1.5.1 Submodules

###### 2.1.1.5.1.1 kwcoco.metrics.assignment module

---

##### Todo:

- [ ] **\_fast\_pdist\_priority**: Look at absolute difference in sibling entropy when deciding whether to go up or down in the tree.
- [ ] **medschool applications true-pred matching (applicant proposing) fast algorithm**.
- [ ] **Maybe looping over truth rather than pred is faster? but it makes you have to combine pred score / ious, which is weird.**
- [x] **preallocate ndarray and use hstack to build confusion vectors?**

- doesn't help
  - [ ] relevant classes / classes / classes-of-interest we care about needs to be a first class member of detection metrics.
  - [ ] Add parameter that allows one prediction to “match” to more than one truth object. (example: we have a duck detector problem and all the ducks in a row are annotated as separate object, and we only care about getting the group)
- 

### 2.1.1.5.1.2 kwcoco.metrics.clf\_report module

```
kwcoco.metrics.clf_report.classification_report(y_true, y_pred, target_names=None,  
                                                sample_weight=None, verbose=False,  
                                                remove_unsupported=False, log=None,  
                                                ascii_only=False)
```

Computes a classification report which is a collection of various metrics commonly used to evaluate classification quality. This can handle binary and multiclass settings.

Note that this function does not accept probabilities or scores and must instead act on final decisions. See ovr\_classification\_report for a probability based report function using a one-vs-rest strategy.

This emulates the bm(cm) Matlab script [MatlabBM] written by David Powers that is used for computing bookmaker, markedness, and various other scores and is based on the paper [PowersMetrics].

## References

### Parameters

- **y\_true** (*ndarray*) – true labels for each item
- **y\_pred** (*ndarray*) – predicted labels for each item
- **target\_names** (*List | None*) – mapping from label to category name
- **sample\_weight** (*ndarray | None*) – weight for each item
- **verbose** (*int*) – print if True
- **log** (*callable | None*) – print or logging function
- **remove\_unsupported** (*bool*) – removes categories that have no support. Defaults to False.
- **ascii\_only** (*bool*) – if True dont use unicode characters. if the environ ASCII\_ONLY is present this is forced to True and cannot be undone. Defaults to False.

## Example

```
>>> # xdoctest: +IGNORE_WANT  
>>> # xdoctest: +REQUIRES(module:sklearn)  
>>> # xdoctest: +REQUIRES(module:pandas)  
>>> y_true = [1, 1, 1, 1, 1, 2, 2, 2, 2, 3, 3, 3, 3, 3, 3, 3, 3]  
>>> y_pred = [1, 2, 1, 3, 1, 2, 2, 3, 2, 3, 3, 2, 3, 3, 1, 3]  
>>> target_names = None  
>>> sample_weight = None  
>>> report = classification_report(y_true, y_pred, verbose=0, ascii_only=1)
```

(continues on next page)

(continued from previous page)

```
>>> print(report['confusion'])
pred  1  2  3  r
real
1      3  1  1  5
2      0  4  1  5
3      1  1  6  8
p     4  6  8  18
>>> print(report['metrics'])
metric      precision    recall      fpr  markedness  bookmaker      mcc   support
class
1          0.7500  0.6000  0.0769      0.6071  0.5231  0.5635      5
2          0.6667  0.8000  0.1538      0.5833  0.6462  0.6139      5
3          0.7500  0.7500  0.2000      0.5500  0.5500  0.5500      8
combined   0.7269  0.7222  0.1530      0.5751  0.5761  0.5758     18
```

## Example

```
>>> # xdoctest: +IGNORE_WANT
>>> # xdoctest: +REQUIRES(module:sklearn)
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwcoco.metrics.clf_report import * # NOQA
>>> y_true = [1, 1, 1, 1, 1, 2, 2, 2, 2, 2, 3, 3, 3, 3, 3, 3, 3, 3, 3]
>>> y_pred = [1, 2, 1, 3, 1, 2, 2, 3, 2, 2, 3, 3, 2, 3, 3, 3, 1, 3]
>>> target_names = None
>>> sample_weight = None
>>> logs = []
>>> report = classification_report(y_true, y_pred, verbose=1, ascii_only=True,
->>> log=logs.append)
>>> print('\n'.join(logs))
```

```
kwcoco.metrics.clf_report.ovr_classification_report(mc_y_true, mc_probs, target_names=None,
sample_weight=None, metrics=None,
verbose=0, remove_unsupported=False,
log=None)
```

One-vs-rest classification report

### Parameters

- **mc\_y\_true** (*ndarray*) – multiclass truth labels (integer label format). Shape [N].
- **mc\_probs** (*ndarray*) – multiclass probabilities for each class. Shape [N x C].
- **target\_names** (*Dict[int, str] | None*) – mapping from int label to string name
- **sample\_weight** (*ndarray | None*) – weight for each item. Shape [N].
- **metrics** (*List[str] | None*) – names of metrics to compute

## Example

```
>>> # xdoctest: +IGNORE_WANT
>>> # xdoctest: +REQUIRES(module:sklearn)
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwcoc.metrics.clf_report import * # NOQA
>>> y_true = [1, 1, 1, 1, 2, 2, 2, 2, 2, 0, 0, 0, 0, 0, 0, 0]
>>> y_probs = np.random.rand(len(y_true), max(y_true) + 1)
>>> target_names = None
>>> sample_weight = None
>>> verbose = True
>>> report = ovr_classification_report(y_true, y_probs)
>>> print(report['ave'])
auc      0.6541
ap       0.6824
kappa    0.0963
mcc      0.1002
brier    0.2214
dtype: float64
>>> print(report['ovr'])
     auc      ap      kappa      mcc      brier      support      weight
0 0.6062 0.6161 0.0526 0.0598 0.2608          8  0.4444
1 0.5846 0.6014 0.0000 0.0000 0.2195          5  0.2778
2 0.8000 0.8693 0.2623 0.2652 0.1602          5  0.2778
```

### 2.1.1.5.1.3 kwcoc.metrics.confusion\_measures module

Classes that store accumulated confusion measures (usually derived from confusion vectors).

**For each chosen threshold value:**

- thresholds[i] - the i-th threshold value

The primary data we manipulate are arrays of “confusion” counts, i.e.

- tp\_count[i] - true positives at the i-th threshold
- fp\_count[i] - false positives at the i-th threshold
- fn\_count[i] - false negatives at the i-th threshold
- tn\_count[i] - true negatives at the i-th threshold


**class kwcoc.metrics.confusion\_measures.Measures(*info*)**

Bases: *NiceRepr*, *DictProxy*

Holds accumulated confusion counts, and derived measures

## Example

```
>>> from kwCOCO.metrics.confusion_vectors import BinaryConfusionVectors # NOQA
>>> binvecs = BinaryConfusionVectors.demo(n=100, p_error=0.5)
>>> self = binvecs.measures()
>>> print('self = {!r}'.format(self))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> self.draw(doclf=True)
>>> self.draw(key='pr', pnum=(1, 2, 1))
>>> self.draw(key='roc', pnum=(1, 2, 2))
>>> kwplot.show_if_requested()
```



**property catname**  
**reconstruct()**  
**classmethod from\_json(state)**  
**summary()**  
**maximized\_thresholds()**

Returns thresholds that maximize metrics.

```
counts()  
draw(key=None, prefix='', **kw)
```


### Example

```
>>> # xdoctest: +REQUIRES(module:kwplot)  
>>> # xdoctest: +REQUIRES(module:pandas)  
>>> from kwcoco.metrics.confusion_vectors import ConfusionVectors # NOQA  
>>> cfsn_vecs = ConfusionVectors.demo()  
>>> ovr_cfsn = cfsn_vecs.binarize_ovr(keyby='name')  
>>> self = ovr_cfsn.measures()['perclass']  
>>> self.draw('mcc', doclf=True, fnum=1)  
>>> self.draw('pr', doclf=1, fnum=2)  
>>> self.draw('roc', doclf=1, fnum=3)
```

```
summary_plot(fnum=1, title='', subplots='auto')
```

### Example

```
>>> from kwcoco.metrics.confusion_measures import * # NOQA  
>>> from kwcoco.metrics.confusion_vectors import ConfusionVectors # NOQA  
>>> cfsn_vecs = ConfusionVectors.demo(n=3, p_error=0.5)  
>>> binvecs = cfsn_vecs.binarize_classless()  
>>> self = binvecs.measures()  
>>> # xdoctest: +REQUIRES(--show)  
>>> import kwplot  
>>> kwplot.autopl()  
>>> self.summary_plot()  
>>> kwplot.show_if_requested()
```

**classmethod demo(\*\*kwargs)**

Create a demo Measures object for testing / demos

**Parameters**

**\*\*kwargs** – passed to `BinaryConfusionVectors.demo()`. some valid keys are: n, rng, p\_rue, p\_error, p\_miss.

**classmethod combine(tocombine, precision=None, growth=None, thresh\_bins=None)**

Combine binary confusion metrics

**Parameters**


- **tocombine** (`List[Measures]`) – a list of measures to combine into one
- **precision** (`int | None`) – If specified rounds thresholds to this precision which can prevent a RAM explosion when combining a large number of measures. However, this is a lossy operation and will impact the underlying scores. NOTE: use `growth` instead.
- **growth** (`int | None`) – if specified this limits how much the resulting measures are allowed to grow by. If `None`, growth is unlimited. Otherwise, if `growth` is ‘`max`’, the growth is limited to the maximum length of an input. We might make this more numerical in the future.
- **thresh\_bins** (`int | None`) – Force this many threshold bins.

**Returns**

`kwcocodoc.metrics.confusion_measures.Measures`

## Example

```
>>> from kwcoc.metrics.confusion_measures import * # NOQA
>>> measures1 = Measures.demo(n=15)
>>> measures2 = measures1
>>> tocombine = [measures1, measures2]
>>> new_measures = Measures.combine(tocombine)
>>> new_measures.reconstruct()
>>> print('new_measures = {!r}'.format(new_measures))
>>> print('measures1 = {!r}'.format(measures1))
>>> print('measures2 = {!r}'.format(measures2))
>>> print(ub.repr2(measures1.__json__(), nl=1, sort=0))
>>> print(ub.repr2(measures2.__json__(), nl=1, sort=0))
>>> print(ub.repr2(new_measures.__json__(), nl=1, sort=0))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> kwplot.figure(fnum=1)
>>> new_measures.summary_plot()
>>> measures1.summary_plot()
>>> measures1.draw('roc')
>>> measures2.draw('roc')
>>> new_measures.draw('roc')
```



## Example

```
>>> # Demonstrate issues that can arise from choosing a precision
>>> # that is too low when combining metrics. Breakpoints
>>> # between different metrics can get muddled, but choosing a
>>> # precision that is too high can overwhelm memory.
>>> from kwcocoo.metrics.confusion_measures import * # NOQA
>>> base = ub.map_vals(np.asarray, {
>>>     'tp_count': [1, 1, 2, 2, 2, 3],
>>>     'fp_count': [0, 1, 1, 2, 3, 4, 5],
>>>     'fn_count': [1, 1, 0, 0, 0, 0],
>>>     'tn_count': [5, 4, 4, 3, 2, 1, 0],
>>>     'thresholds': [.0, .0, .0, .0, .0, .0, .0],
>>> })
>>> # Make tiny offsets to thresholds
>>> rng = kwarray.ensure_rng(0)
>>> n = len(base['thresholds'])
>>> offsets = [
>>>     sorted(rng.rand(n) * 10 ** -rng.randint(4, 7))[::-1]
>>>     for _ in range(20)
>>> ]
>>> tocombine = []
>>> for offset in offsets:
>>>     base_n = base.copy()
>>>     base_n['thresholds'] += offset
>>>     measures_n = Measures(base_n).reconstruct()
>>>     tocombine.append(measures_n)
>>> for precision in [6, 5, 2]:
>>>     combo = Measures.combine(tocombine, precision=precision).reconstruct()
>>>     print('precision = {!r}'.format(precision))
>>>     print('combo = {}'.format(ub.repr2(combo, nl=1)))
>>>     print('num_thresholds = {}'.format(len(combo['thresholds'])))
>>> for growth in [None, 'max', 'log', 'root', 'half']:
>>>     combo = Measures.combine(tocombine, growth=growth).reconstruct()
>>>     print('growth = {!r}'.format(growth))
>>>     print('combo = {}'.format(ub.repr2(combo, nl=1)))
>>>     print('num_thresholds = {}'.format(len(combo['thresholds'])))
>>> #print(combo.counts().pandas()
```

## Example

```
>>> # Test case: combining a single measures should leave it unchanged
>>> from kwcocoo.metrics.confusion_measures import * # NOQA
>>> measures = Measures.demo(n=40, p_true=0.2, p_error=0.4, p_miss=0.6)
>>> df1 = measures.counts().pandas().fillna(0)
>>> print(df1)
>>> tocombine = [measures]
>>> combo = Measures.combine(tocombine)
>>> df2 = combo.counts().pandas().fillna(0)
>>> print(df2)
>>> assert np.allclose(df1, df2)
```

```
>>> combo = Measures.combine(tocombine, thresh_bins=2)
>>> df3 = combo.counts().pandas().fillna(0)
>>> print(df3)
```

```
>>> # I am NOT sure if this is correct or not
>>> thresh_bins = 20
>>> combo = Measures.combine(tocombine, thresh_bins=thresh_bins)
>>> df4 = combo.counts().pandas().fillna(0)
>>> print(df4)
```

```
>>> combo = Measures.combine(tocombine, thresh_bins=np.linspace(0, 1, 20))
>>> df4 = combo.counts().pandas().fillna(0)
>>> print(df4)
```

```
assert np.allclose(combo['thresholds'], measures['thresholds']) assert np.allclose(combo['fp_count'], measures['fp_count']) assert np.allclose(combo['tp_count'], measures['tp_count']) assert np.allclose(combo['tp_count'], measures['tp_count'])

globals().update(xdev.get_func_kwargs(Measures.combine))
```

## Example

```
>>> # Test degenerate case
>>> from kwcoc.metrics.confusion_measures import * # NOQA
>>> tocombine = [
>>>     {'fn_count': [0.0], 'fp_count': [359980.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [7747.0]},
>>>     {'fn_count': [0.0], 'fp_count': [360849.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [424.0]},
>>>     {'fn_count': [0.0], 'fp_count': [367003.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [991.0]},
>>>     {'fn_count': [0.0], 'fp_count': [367976.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [1017.0]},
>>>     {'fn_count': [0.0], 'fp_count': [676338.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [7067.0]},
>>>     {'fn_count': [0.0], 'fp_count': [676348.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [7406.0]},
>>>     {'fn_count': [0.0], 'fp_count': [676626.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [7858.0]},
>>>     {'fn_count': [0.0], 'fp_count': [676693.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [10969.0]},
>>>     {'fn_count': [0.0], 'fp_count': [677269.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [11188.0]},
>>>     {'fn_count': [0.0], 'fp_count': [677331.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [11734.0]},
>>>     {'fn_count': [0.0], 'fp_count': [677395.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [11556.0]},
>>>     {'fn_count': [0.0], 'fp_count': [677418.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [11621.0]},
>>>     {'fn_count': [0.0], 'fp_count': [677422.0], 'thresholds': [0.0], 'tn_
->count': [0.0], 'tp_count': [11424.0]},
>>>     {'fn_count': [0.0], 'fp_count': [677648.0], 'thresholds': [0.0], 'tn_
```

(continues on next page)

(continued from previous page)

```

    'fn_count': [0.0], 'fp_count': [9804.0]}, 
    {'fn_count': [0.0], 'fp_count': [677826.0], 'thresholds': [0.0], 'tn_
    count': [0.0], 'tp_count': [2470.0]}, 
    {'fn_count': [0.0], 'fp_count': [677834.0], 'thresholds': [0.0], 'tn_
    count': [0.0], 'tp_count': [2470.0]}, 
    {'fn_count': [0.0], 'fp_count': [677835.0], 'thresholds': [0.0], 'tn_
    count': [0.0], 'tp_count': [2470.0]}, 
    {'fn_count': [11123.0, 0.0], 'fp_count': [0.0, 676754.0], 'thresholds': [
    [0.0002442002442002442, 0.0], 'tn_count': [676754.0, 0.0], 'tp_count': [2.0,
    11125.0]}, 
    {'fn_count': [7738.0, 0.0], 'fp_count': [0.0, 676466.0], 'thresholds': [
    [0.0002442002442002442, 0.0], 'tn_count': [676466.0, 0.0], 'tp_count': [0.0,
    7738.0]}, 
    {'fn_count': [8653.0, 0.0], 'fp_count': [0.0, 676341.0], 'thresholds': [
    [0.0002442002442002442, 0.0], 'tn_count': [676341.0, 0.0], 'tp_count': [0.0,
    8653.0]}, 
    ]
    thresh_bins = np.linspace(0, 1, 4)
    combo = Measures.combine(tocombine, thresh_bins=thresh_bins).reconstruct()
    print('tocombine = {}'.format(ub.repr2(tocombine, nl=2)))
    print('thresh_bins = {!r}'.format(thresh_bins))
    print(ub.repr2(combo.__json__(), nl=1))
    for thresh_bins in [4096, 1]:
        combo = Measures.combine(tocombine, thresh_bins=thresh_bins).
        reconstruct()
        print('thresh_bins = {!r}'.format(thresh_bins))
        print('combo = {}'.format(ub.repr2(combo, nl=1)))
        print('num_thresholds = {}'.format(len(combo['thresholds'])))
    for precision in [6, 5, 2]:
        combo = Measures.combine(tocombine, precision=precision).reconstruct()
        print('precision = {!r}'.format(precision))
        print('combo = {}'.format(ub.repr2(combo, nl=1)))
        print('num_thresholds = {}'.format(len(combo['thresholds'])))
    for growth in [None, 'max', 'log', 'root', 'half']:
        combo = Measures.combine(tocombine, growth=growth).reconstruct()
        print('growth = {!r}'.format(growth))
        print('combo = {}'.format(ub.repr2(combo, nl=1)))
        print('num_thresholds = {}'.format(len(combo['thresholds'])))

```

`kwcocoo.metrics.confusion_measures.reversible_diff(arr, assume_sorted=1, reverse=False)`

Does a reversible array difference operation.

This will be used to find positions where accumulation happened in confusion count array.

`class kwcocoo.metrics.confusion_measures.PerClass_Measures(cx_to_info)`

Bases: `NiceRepr, DictProxy`

`summary()`

`classmethod from_json(state)`

`draw(key='mcc', prefix='', **kw)`

## Example

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> from kwcoc.metrics.confusion_vectors import ConfusionVectors # NOQA
>>> cfsn_vecs = ConfusionVectors.demo()
>>> ovr_cfsn = cfsn_vecs.binarize_ovr(keyby='name')
>>> self = ovr_cfsn.measures()['perclass']
>>> self.draw('mcc', doclf=True, fnum=1)
>>> self.draw('pr', doclf=1, fnum=2)
>>> self.draw('roc', doclf=1, fnum=3)
```


```
draw_roc(prefix='', **kw)
draw_pr(prefix='', **kw)
summary_plot(fnum=1, title='', subplots='auto')
```

## CommandLine

```
python ~/code/kwcoco/kwcoco/metrics/confusion_measures.py PerClass_Measures.
->summary_plot --show
```

## Example

```
>>> from kwcoc.metrics.confusion_measures import * # NOQA
>>> from kwcoc.metrics.detect_metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo()
>>>     n_fp=(0, 1), n_fn=(0, 3), nimgs=32, nboxes=(0, 32),
>>>     classes=3, rng=0, newstyle=1, box_noise=0.7, cls_noise=0.2, score_
>>> noise=0.3, with_probs=False)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> ovr_cfsn = cfsn_vecs.binarize_ovr(keyby='name', ignore_classes=['vector',
>>> 'raster'])
>>> self = ovr_cfsn.measures()['perclass']
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> import seaborn as sns
>>> sns.set()
>>> self.summary_plot(title='demo summary_plot ovr', subplots=['pr', 'roc'])
>>> kwplot.show_if_requested()
>>> self.summary_plot(title='demo summary_plot ovr', subplots=['mcc', 'acc'],
>>> fnum=2)
```



```
class kwcoco.metrics.confusion_measures.MeasureCombiner(precision=None, growth=None,
                                                        thresh_bins=None)
```

Bases: object

Helper to iteravely combine binary measures generated by some process

### Example

```
>>> from kwcoco.metrics.confusion_measures import * # NOQA
>>> from kwcoco.metrics.confusion_vectors import BinaryConfusionVectors
>>> rng = kwarray.ensure_rng(0)
>>> bin_combiner = MeasureCombiner(growth='max')
>>> for _ in range(80):
>>>     bin_cfsn_vecs = BinaryConfusionVectors.demo(n=rng.randint(40, 50), rng=rng,
>>>         p_true=0.2, p_error=0.4, p_miss=0.6)
>>>     bin_measures = bin_cfsn_vecs.measures()
>>>     bin_combiner.submit(bin_measures)
>>> combined = bin_combiner.finalize()
>>> print('combined = {!r}'.format(combined))
```

**property queue\_size**

**submit(other)**

**combine()**

**finalize()**

```
class kwcoco.metrics.confusion_measures.OneVersusRestMeasureCombiner(precision=None,
                                                                      growth=None,
                                                                      thresh_bins=None)
```

Bases: object

Helper to iteravely combine ovr measures generated by some process

### Example

```
>>> from kwcoco.metrics.confusion_measures import * # NOQA
>>> from kwcoco.metrics.confusion_vectors import OneVsRestConfusionVectors
>>> rng = kwarray.ensure_rng(0)
>>> ovr_combiner = OneVersusRestMeasureCombiner(growth='max')
>>> for _ in range(80):
>>>     ovr_cfsn_vecs = OneVsRestConfusionVectors.demo()
>>>     ovr_measures = ovr_cfsn_vecs.measures()
>>>     ovr_combiner.submit(ovr_measures)
>>> combined = ovr_combiner.finalize()
>>> print('combined = {!r}'.format(combined))
```

**submit(other)**

**combine()**

**finalize()**

## kwCOCO.metrics.confusion\_measures.populate\_info(info)

Given raw accumulated confusion counts, populated secondary measures like AP, AUC, F1, MCC, etc..

### 2.1.1.5.1.4 kwCOCO.metrics.confusion\_vectors module

Classes that store raw confusion vectors, which can be accumulated into confusion measures.

`class kwCOCO.metrics.confusion_vectors.ConfusionVectors(data, classes, probs=None)`

Bases: `NiceRepr`

Stores information used to construct a confusion matrix. This includes corresponding vectors of predicted labels, true labels, sample weights, etc...

#### Variables

- `data` (`kwarray.DataFrameArray`) – should at least have keys `true`, `pred`, `weight`
- `classes` (`Sequence` / `CategoryTree`) – list of category names or category graph
- `probs` (`ndarray` / `None`) – probabilities for each class


#### Example

```
>>> # xdoctest: IGNORE_WANT
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwCOCO.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo()
>>> nimgs=10, nboxes=(0, 10), n_fp=(0, 1), classes=3
>>> cfsn_vecs = dmet.confusion_vectors()
>>> print(cfsn_vecs.data._pandas())
   pred  true    score    weight      iou     txs     pxs     gid
0      2      2  10.0000  1.0000  1.0000      0      4      0
1      2      2  7.5025  1.0000  1.0000      1      3      0
2      1      1  5.0050  1.0000  1.0000      2      2      0
3      3     -1  2.5075  1.0000 -1.0000     -1      1      0
4      2     -1  0.0100  1.0000 -1.0000     -1      0      0
5     -1      2  0.0000  1.0000 -1.0000      3     -1      0
6     -1      2  0.0000  1.0000 -1.0000      4     -1      0
7      2      2  10.0000  1.0000  1.0000      0      5      1
8      2      2  8.0020  1.0000  1.0000      1      4      1
9      1      1  6.0040  1.0000  1.0000      2      3      1
...
62     -1      2  0.0000  1.0000 -1.0000      7     -1      7
63     -1      3  0.0000  1.0000 -1.0000      8     -1      7
64     -1      1  0.0000  1.0000 -1.0000      9     -1      7
65      1     -1  10.0000  1.0000 -1.0000     -1      0      8
66      1      1  0.0100  1.0000  1.0000      0      1      8
67      3     -1  10.0000  1.0000 -1.0000     -1      3      9
68      2      2  6.6700  1.0000  1.0000      0      2      9
69      2      2  3.3400  1.0000  1.0000      1      1      9
70      3     -1  0.0100  1.0000 -1.0000     -1      0      9
71     -1      2  0.0000  1.0000 -1.0000      2     -1      9
```

```

>>> # xdoctest: +REQUIRES(--show)
>>> # xdoctest: +REQUIRES(module:pandas)
>>> import kwplot
>>> kwplot.autopl()
>>> from kwcoco.metrics.confusion_vectors import ConfusionVectors
>>> cfsn_vecs = ConfusionVectors.demo(
>>>     nimgs=128, nboxes=(0, 10), n_fp=(0, 3), n_fn=(0, 3), classes=3)
>>> cx_to_binvecs = cfsn_vecs.binarize_ovr()
>>> measures = cx_to_binvecs.measures()['perclass']
>>> print('measures = {!r}'.format(measures))
measures = <PerClass_Measures{
    'cat_1': <Measures({'ap': 0.227, 'auc': 0.507, 'catname': cat_1, 'max_f1': f1=0.
        ↵45@0.47, 'nsupport': 788.000})>,
    'cat_2': <Measures({'ap': 0.288, 'auc': 0.572, 'catname': cat_2, 'max_f1': f1=0.
        ↵51@0.43, 'nsupport': 788.000})>,
    'cat_3': <Measures({'ap': 0.225, 'auc': 0.484, 'catname': cat_3, 'max_f1': f1=0.
        ↵46@0.40, 'nsupport': 788.000})>,
} at 0x7facf77bdf0>
>>> kwplot.figure(fnum=1, doclf=True)
>>> measures.draw(key='pr', fnum=1, pnum=(1, 3, 1))
>>> measures.draw(key='roc', fnum=1, pnum=(1, 3, 2))
>>> measures.draw(key='mcc', fnum=1, pnum=(1, 3, 3))
...

```



```
classmethod from_json(state)
```

---

```
classmethod demo(**kw)
```

**Parameters**  
`**kwargs` – See `kwcocoo.metrics.DetectionMetrics.demo()`

**Returns**  
`ConfusionVectors`

### Example

```
>>> cfsn_vecs = ConfusionVectors.demo()  
>>> print('cfsn_vecs = {!r}'.format(cfsn_vecs))  
>>> cx_to_binvecs = cfsn_vecs.binarize_ovr()  
>>> print('cx_to_binvecs = {!r}'.format(cx_to_binvecs))
```

---

```
classmethod from_arrays(true, pred=None, score=None, weight=None, probs=None, classes=None)
```

Construct confusion vector data structure from component arrays

### Example

```
>>> # xdoctest: +REQUIRES(module:pandas)
>>> import kwarray
>>> classes = ['person', 'vehicle', 'object']
>>> rng = kwarray.ensure_rng(0)
>>> true = (rng.rand(10) * len(classes)).astype(int)
>>> probs = rng.rand(len(true), len(classes))
>>> cfsn_vecs = ConfusionVectors.from_arrays(true=true, probs=probs, ↴
-> classes=classes)
>>> cfsn_vecs.confusion_matrix()
pred      person    vehicle    object
real
person        0        0        0
vehicle       2        4        1
object        2        1        0
```

---

```
confusion_matrix(compress=False)
```

Builds a confusion matrix from the confusion vectors.

**Parameters**  
`compress (bool, default=False)` – if True removes rows / columns with no entries

**Returns**

`cm`  
[the labeled confusion matrix]

(Note: we should write a efficient replacement for  
this use case. #remove\_pandas)

**Return type**  
`pd.DataFrame`

## CommandLine

```
xdoctest -m kwcoco.metrics.confusion_vectors ConfusionVectors.confusion_matrix
```

## Example

```
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwcoco.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 10), n_fp=(0, 1), n_fn=(0, 1), classes=3, cls_
>>> _noise=.2)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> cm = cfsn_vecs.confusion_matrix()

...
>>> print(cm.to_string(float_format=lambda x: '%.2f' % x))
pred      background  cat_1  cat_2  cat_3
real
background      0.00   1.00   2.00   3.00
cat_1          3.00  12.00   0.00   0.00
cat_2          3.00   0.00  14.00   0.00
cat_3          2.00   0.00   0.00  17.00
```

### coarsen(cx)

Creates a coarsened set of vectors

#### Returns

ConfusionVectors

### binarize\_classless(negative\_classes=None)

Creates a binary representation useful for measuring the performance of detectors. It is assumed that scores of “positive” classes should be high and “negative” classes should be low.

#### Parameters

**negative\_classes** (*List[str | int] | None*) – list of negative class names or idxs, by default chooses any class with a true class index of -1. These classes should ideally have low scores.

#### Returns

BinaryConfusionVectors

---

**Note:** The “classlessness” of this depends on the `compat="all"` argument being used when constructing confusion vectors, otherwise it becomes something like a macro-average because the class information was used in deciding which true and predicted boxes were allowed to match.

---

## Example

```
>>> from kwCOCO.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
    nimgs=10, nboxes=(0, 10), n_fp=(0, 1), n_fn=(0, 1), classes=3)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> class_idxs = list(dmet.classes.node_to_idx.values())
>>> binvecs = cfsn_vecs.binarize_classless()
```

**binarize\_ovr**(*mode=1*, *keyby='name'*, *ignore\_classes={'ignore'}*, *approx=False*)

Transforms cfsn\_vecs into one-vs-rest BinaryConfusionVectors for each category.

### Parameters

- **mode** (*int, default=1*) – 0 for hierarchy aware or 1 for voc like. MODE 0 IS PROBABLY BROKEN
- **keyby** (*int | str*) – can be cx or name
- **ignore\_classes** (*Set[str]*) – category names to ignore
- **approx** (*bool, default=False*) – if True try and approximate missing scores otherwise assume they are irrecoverable and use -inf

### Returns

which behaves like

Dict[int, BinaryConfusionVectors]: cx\_to\_binvecs

### Return type

*OneVsRestConfusionVectors*

## Example

```
>>> from kwCOCO.metrics.confusion_vectors import * # NOQA
>>> cfsn_vecs = ConfusionVectors.demo()
>>> print('cfsn_vecs = {!r}'.format(cfsn_vecs))
>>> catname_to_binvecs = cfsn_vecs.binarize_ovr(keyby='name')
>>> print('catname_to_binvecs = {!r}'.format(catname_to_binvecs))
```

cfsn\_vecs.data.pandas() catname\_to\_binvecs.cx\_to\_binvecs['class\_1'].data.pandas()

---

### Note:

---

**classification\_report**(*verbose=0*)

Build a classification report with various metrics.

## Example

```
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwcoc.metrics.confusion_vectors import * # NOQA
>>> cfsn_vecs = ConfusionVectors.demo()
>>> report = cfsn_vecs.classification_report(verbose=1)
```

**class** kwcoc.metrics.confusion\_vectors.**OneVsRestConfusionVectors**(*cx\_to\_binvecs*, *classes*)

Bases: `NiceRepr`

Container for multiple one-vs-rest binary confusion vectors

### Variables

- `cx_to_binvecs` –
- `classes` –

## Example

```
>>> from kwcoc.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 10), n_fp=(0, 1), classes=3)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> self = cfsn_vecs.binarize_ovr(keyby='name')
>>> print('self = {!r}'.format(self))
```

**classmethod demo()**

### Parameters

`**kwargs` – See `kwcoc.metrics.DetectionMetrics.demo()`

### Returns

ConfusionVectors

**keys()**

**measures**(*stabalize\_thresh*=7, *fp\_cutoff*=None, *monotonic\_ppv*=True, *ap\_method*='pycocotools')

Creates binary confusion measures for every one-versus-rest category.

### Parameters

- `stabalize_thresh` (*int*) – if fewer than this many data points inserts dummy stabilization data so curves can still be drawn. Default to 7.
- `fp_cutoff` (*int* | *None*) – maximum number of false positives in the truncated roc curves. The default None is equivalent to `float('inf')`
- `monotonic_ppv` (*bool*) – if True ensures that precision is always increasing as recall decreases. This is done in pycocotools scoring, but I'm not sure its a good idea. Default to True.

### SeeAlso:

`BinaryConfusionVectors.measures()`

## Example

```
>>> self = OneVsRestConfusionVectors.demo()
>>> thresh_result = self.measures()['perclass']
```

`ovr_classification_report()`

`class kwcoco.metrics.confusion_vectors.BinaryConfusionVectors(data, cx=None, classes=None)`

Bases: `NiceRepr`

Stores information about a binary classification problem. This is always with respect to a specific class, which is given by `cx` and `classes`.

The `data DataFrameArray` must contain

`is_true` - if the row is an instance of class `classes[cx]` `pred_score` - the predicted probability of class `classes[cx]`, and `weight` - sample weight of the example

## Example

```
>>> from kwcoco.metrics.confusion_vectors import * # NOQA
>>> self = BinaryConfusionVectors.demo(n=10)
>>> print('self = {!r}'.format(self))
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

```
>>> self = BinaryConfusionVectors.demo(n=0)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

```
>>> self = BinaryConfusionVectors.demo(n=1)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

```
>>> self = BinaryConfusionVectors.demo(n=2)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

`classmethod demo(n=10, p_true=0.5, p_error=0.2, p_miss=0.0, rng=None)`

Create random data for tests

### Parameters


- `n (int)` – number of rows
- `p_true (float)` – fraction of real positive cases
- `p_error (float)` – probability of making a recoverable mistake
- `p_miss (float)` – probability of making a unrecoverable mistake
- `rng (int | RandomState | None)` – random seed / state

### Returns

`BinaryConfusionVectors`

## Example

```
>>> from kwCOCO.metrics.confusion_vectors import * # NOQA
>>> cfsn = BinaryConfusionVectors.demo(n=1000, p_error=0.1, p_miss=0.1)
>>> measures = cfsn.measures()
>>> print('measures = {}'.format(ub.repr2(measures, nl=1)))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> kwplot.figure(fnum=1, pnum=(1, 2, 1))
>>> measures.draw('pr')
>>> kwplot.figure(fnum=1, pnum=(1, 2, 2))
>>> measures.draw('roc')
```



**property catname**

**measures**(*stabilize\_thresh*=7, *fp\_cutoff*=None, *monotonic\_ppv*=True, *ap\_method*='pycocotools')

Get statistics (F1, G1, MCC) versus thresholds

### Parameters

- **stabilize\_thresh** (*int*, *default*=7) – if fewer than this many data points inserts dummy stabilization data so curves can still be drawn.
- **fp\_cutoff** (*int* | *None*) – maximum number of false positives in the truncated roc curves. The default of *None* is equivalent to `float('inf')`
- **monotonic\_ppv** (*bool*) – if *True* ensures that precision is always increasing as recall decreases. This is done in pycocotools scoring, but I'm not sure its a good idea.

## Example

```
>>> from kwCOCO.metrics.confusion_vectors import * # NOQA
>>> self = BinaryConfusionVectors.demo(n=0)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
>>> self = BinaryConfusionVectors.demo(n=1, p_true=0.5, p_error=0.5)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
>>> self = BinaryConfusionVectors.demo(n=3, p_true=0.5, p_error=0.5)
>>> print('measures = {}'.format(ub.repr2(self.measures())))

>>> self = BinaryConfusionVectors.demo(n=100, p_true=0.5, p_error=0.5, p_miss=0.
    ↪3)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
>>> print('measures = {}'.format(ub.repr2(ub.odict(self.measures()))))
```

## References

[https://en.wikipedia.org/wiki/Confusion\\_matrix](https://en.wikipedia.org/wiki/Confusion_matrix) [https://en.wikipedia.org/wiki/Precision\\_and\\_recall](https://en.wikipedia.org/wiki/Precision_and_recall) [https://en.wikipedia.org/wiki/Matthews\\_correlation\\_coefficient](https://en.wikipedia.org/wiki/Matthews_correlation_coefficient)

`draw_distribution()`

### 2.1.1.5.1.5 kwCOCO.metrics.detect\_metrics module

`class kwCOCO.metrics.detect_metrics.DetectionMetrics(classes=None)`

Bases: `NiceRepr`

Object that computes associations between detections and can convert them into sklearn-compatible representations for scoring.

#### Variables

- `gid_to_true_dets` (`Dict`) – maps image ids to truth
- `gid_to_pred_dets` (`Dict`) – maps image ids to predictions
- `classes` (`kwCOCO.CategoryTree`) – category coder

## Example

```
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=100, nboxes=(0, 3), n_fp=(0, 1), classes=8, score_noise=0.9, ↴
>>>     hacked=False)
>>> print(dmet.score_kwCOCO(bias=0, compat='mutex', prioritize='iou')['mAP'])
...
>>> # NOTE: IN GENERAL NETHARN AND VOC ARE NOT THE SAME
>>> print(dmet.score_voc(bias=0)['mAP'])
0.8582...
>>> #print(dmet.score_coco()['mAP'])
```

`clear()`

**enrich\_confusion\_vectors(*cfsn\_vecs*)**

Adds annotation id information into confusion vectors computed via this detection metrics object.

TODO: should likely use this at the end of the function that builds the confusion vectors.

**classmethod from\_coco(*true\_coco*, *pred\_coco*, *gids=None*, *verbose=0*)**

Create detection metrics from two coco files representing the truth and predictions.

**Parameters**

- **true\_coco** (*kwCOCO.CocoDataset*)
- **pred\_coco** (*kwCOCO.CocoDataset*)

**Example**

```
>>> import kwCOCO
>>> from kwCOCO.demo.perterb import perterb_coco
>>> true_coco = kwCOCO.CocoDataset.demo('shapes')
>>> perterbkw = dict(box_noise=0.5, cls_noise=0.5, score_noise=0.5)
>>> pred_coco = perterb_coco(true_coco, **perterbkw)
>>> self = DetectionMetrics.from_coco(true_coco, pred_coco)
>>> self.score_voc()
```

**add\_predictions(*pred\_dets*, *imgname=None*, *gid=None*)**

Register/Add predicted detections for an image

**Parameters**

- **pred\_dets** (*kwimage.Detections*) – predicted detections
- **imgname** (*str | None*) – a unique string to identify the image
- **gid** (*int | None*) – the integer image id if known

**add\_truth(*true\_dets*, *imgname=None*, *gid=None*)**

Register/Add groundtruth detections for an image

**Parameters**

- **true\_dets** (*kwimage.Detections*) – groundtruth
- **imgname** (*str | None*) – a unique string to identify the image
- **gid** (*int | None*) – the integer image id if known

**true\_detections(*gid*)**

gets Detections representation for groundtruth in an image

**pred\_detections(*gid*)**

gets Detections representation for predictions in an image

**confusion\_vectors(*iou\_thresh=0.5*, *bias=0*, *gids=None*, *compat='mutex'*, *prioritize='iou'*,  
*ignore\_classes='ignore'*, *background\_class=NoParam*, *verbose='auto'*, *workers=0*,  
*track\_probs='try'*, *max\_dets=None*)**

Assigns predicted boxes to the true boxes so we can transform the detection problem into a classification problem for scoring.

**Parameters**

- **iou\_thresh** (*float | List[float]*) – bounding box overlap iou threshold required for assignment if a list, then return type is a dict. Defaults to 0.5
- **bias** (*float*) – for computing bounding box overlap, either 1 or 0 Defaults to 0.
- **gids** (*List[int] | None*) – which subset of images ids to compute confusion metrics on. If not specified all images are used. Defaults to None.
- **compat** (*str*) – can be ('ancestors' | 'mutex' | 'all'). determines which pred boxes are allowed to match which true boxes. If 'mutex', then pred boxes can only match true boxes of the same class. If 'ancestors', then pred boxes can match true boxes that match or have a coarser label. If 'all', then any pred can match any true, regardless of its category label. Defaults to all.
- **prioritize** (*str*) – can be ('iou' | 'class' | 'correct') determines which box to assign to if multiple true boxes overlap a predicted box. if prioritize is iou, then the true box with maximum iou (above iou\_thresh) will be chosen. If prioritize is class, then it will prefer matching a compatible class above a higher iou. If prioritize is correct, then ancestors of the true class are preferred over descendants of the true class, over unrelated classes. Default to 'iou'
- **ignore\_classes** (*set | str*) – class names indicating ignore regions. Default={ 'ignore' }
- **background\_class** (*str | NoParamType*) – Name of the background class. If unspecified we try to determine it with heuristics. A value of None means there is no background class.
- **verbose** (*int | str*) – verbosity flag. Default to 'auto'. In auto mode, verbose=1 if len(gids) > 1000.
- **workers** (*int*) – number of parallel assignment processes. Defaults to 0
- **track\_probs** (*str*) – can be 'try', 'force', or False. if truthy, we assume probabilities for multiple classes are available. default='try'

**Returns**

ConfusionVectors | Dict[float, ConfusionVectors]

**Example**

```
>>> dmet = DetectionMetrics.demo(nimgs=30, classes=3,
>>>                               nboxes=10, n_fp=3, box_noise=10,
>>>                               with_probs=False)
>>> iou_to_cfsn = dmet.confusion_vectors(iou_thresh=[0.3, 0.5, 0.9])
>>> for t, cfsn in iou_to_cfsn.items():
>>>     print('t = {!r}'.format(t))
...     print(cfsn.binarize_ovr().measures())
...     print(cfsn.binarize_classless().measures())
```

**score\_kwant**(*iou\_thresh*=0.5)

Scores the detections using kwant

**score\_kwcoco**(*iou\_thresh*=0.5, *bias*=0, *gids*=None, *compat*'all', *prioritize*'iou')

our scoring method

**score\_voc**(*iou\_thresh*=0.5, *bias*=1, *method*'voc2012', *gids*=None, *ignore\_classes*'ignore')

score using voc method

## Example

```
>>> dmet = DetectionMetrics.demo()  
>>> nimgs=100, nboxes=(0, 3), n_fp=(0, 1), classes=8,  
>>> score_noise=.5  
>>> print(dmet.score_voc()['mAP'])  
0.9399...
```

**score\_pycocotools**(*with\_evaler=False*, *with\_confusion=False*, *verbose=0*, *iou\_thresholds=None*)  
score using ms-coco method

**Returns**

dictionary with pct info

**Return type**

Dict

## Example

```
>>> # xdoctest: +REQUIRES(module:pycocotools)  
>>> from kwcoco.metrics.detect_metrics import *  
>>> dmet = DetectionMetrics.demo()  
>>> nimgs=10, nboxes=(0, 3), n_fn=(0, 1), n_fp=(0, 1), classes=8, with_  
-probs=False  
>>> pct_info = dmet.score_pycocotools(verbose=1,  
>>>                               with_evaler=True,  
>>>                               with_confusion=True,  
>>>                               iou_thresholds=[0.5, 0.9])  
>>> evaler = pct_info['evaler']  
>>> iou_to_cfsn_vecs = pct_info['iou_to_cfsn_vecs']  
>>> for iou_thresh in iou_to_cfsn_vecs.keys():  
>>>     print('iou_thresh = {!r}'.format(iou_thresh))  
>>>     cfsn_vecs = iou_to_cfsn_vecs[iou_thresh]  
>>>     ovr_measures = cfsn_vecs.binarize_ovr().measures()  
>>>     print('ovr_measures = {}'.format(ub.repr2(ovr_measures, nl=1,  
-precision=4)))
```

---

**Note:** by default pycocotools computes average precision as the literal average of computed precisions at 101 uniformly spaced recall thresholds.

pycocoutils seems to only allow predictions with the same category as the truth to match those truth objects. This should be the same as calling dmet.confusion\_vectors with compat = mutex

pycocoutils does not take into account the fact that each box often has a score for each category.

pycocoutils will be incorrect if any annotation has an id of 0

a major difference in the way kwcoco scores versus pycocoutils is the calculation of AP. The assignment between truth and predicted detections produces similar enough results. Given our confusion vectors we use the scikit-learn definition of AP, whereas pycocoutils seems to compute precision and recall — more or less correctly — but then it resamples the precision at various specified recall thresholds (in the *accumulate* function, specifically how *pr* is resampled into the *q* array). This can lead to a large difference in reported scores.

pycocoutils also smooths out the precision such that it is monotonic decreasing, which might not be the best idea.

pycocotools area ranges are inclusive on both ends, that means the “small” and “medium” truth selections do overlap somewhat.

---

`score_coco(with_evaler=False, with_confusion=False, verbose=0, iou_thresholds=None)`

score using ms-coco method

**Returns**

dictionary with pct info

**Return type**

Dict

## Example

```
>>> # xdoctest: +REQUIRES(module:pycocotools)
>>> from kwcoco.metrics.detect_metrics import *
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 3), n_fn=(0, 1), n_fp=(0, 1), classes=8, with_
>>>     _probs=False)
>>> pct_info = dmet.score_pycocotools(verbose=1,
>>>                                     with_evaler=True,
>>>                                     with_confusion=True,
>>>                                     iou_thresholds=[0.5, 0.9])
>>> evaler = pct_info['evaler']
>>> iou_to_cfsn_vecs = pct_info['iou_to_cfsn_vecs']
>>> for iou_thresh in iou_to_cfsn_vecs.keys():
>>>     print('iou_thresh = {!r}'.format(iou_thresh))
>>>     cfsn_vecs = iou_to_cfsn_vecs[iou_thresh]
>>>     ovr_measures = cfsn_vecs.binarize_ovr().measures()
>>>     print('ovr_measures = {}'.format(ub.repr2(ovr_measures, nl=1,_
>>>     precision=4)))
```

---

**Note:** by default pycocotools computes average precision as the literal average of computed precisions at 101 uniformly spaced recall thresholds.

pycocoutils seems to only allow predictions with the same category as the truth to match those truth objects. This should be the same as calling `dmet.confusion_vectors` with `compat = mutex`

pycocoutils does not take into account the fact that each box often has a score for each category.

pycocoutils will be incorrect if any annotation has an id of 0

a major difference in the way kwcoco scores versus pycocoutils is the calculation of AP. The assignment between truth and predicted detections produces similar enough results. Given our confusion vectors we use the scikit-learn definition of AP, whereas pycocoutils seems to compute precision and recall — more or less correctly — but then it resamples the precision at various specified recall thresholds (in the `accumulate` function, specifically how `pr` is resampled into the `q` array). This can lead to a large difference in reported scores.

pycocoutils also smooths out the precision such that it is monotonic decreasing, which might not be the best idea.

pycocotools area ranges are inclusive on both ends, that means the “small” and “medium” truth selections do overlap somewhat.

---

**classmethod demo(\*\*kwargs)**

Creates random true boxes and predicted boxes that have some noisy offset from the truth.

**Kwargs:****classes (int):**

class list or the number of foreground classes. Defaults to 1.

nimgs (int): number of images in the coco datasets. Defaults to 1.

nboxes (int): boxes per image. Defaults to 1.

n\_fp (int): number of false positives. Defaults to 0.

**n\_fn (int):**

number of false negatives. Defaults to 0.

**box\_noise (float):**

std of a normal distribution used to perterb both box location and box size. Defaults to 0.

**cls\_noise (float):**

probability that a class label will change. Must be within 0 and 1. Defaults to 0.

**anchors (ndarray):**

used to create random boxes. Defaults to None.

**null\_pred (bool):**

if True, predicted classes are returned as null, which means only localization scoring is suitable. Defaults to 0.

**with\_probs (bool):**

if True, includes per-class probabilities with predictions Defaults to 1.

**CommandLine**

```
xdoctest -m kwcoco.metrics.detect_metrics DetectionMetrics.demo:2 --show
```

**Example**

```
>>> kwargs = {}
>>> # Seed the RNG
>>> kwargs['rng'] = 0
>>> # Size parameters determine how big the data is
>>> kwargs['nimgs'] = 5
>>> kwargs['nboxes'] = 7
>>> kwargs['classes'] = 11
>>> # Noise parameters perterb predictions further from the truth
>>> kwargs['n_fp'] = 3
>>> kwargs['box_noise'] = 0.1
>>> kwargs['cls_noise'] = 0.5
>>> dmet = DetectionMetrics.demo(**kwargs)
>>> print('dmet.classes = {}'.format(dmet.classes))
```


(continues on next page)

(continued from previous page)

```
dmet.classes = <CategoryTree(nNodes=12, maxDepth=3, maxBreadth=4...)>
>>> # Can grab kwimage.Detection object for any image
>>> print(dmet.true_detections(gid=0))
<Detections(4)>
>>> print(dmet.pred_detections(gid=0))
<Detections(7)>
```

## Example

```
>>> # Test case with null predicted categories
>>> dmet = DetectionMetrics.demo(nimgs=30, null_pred=1, classes=3,
>>>                               nboxes=10, n_fp=3, box_noise=0.1,
>>>                               with_probs=False)
>>> dmet.gid_to_pred_dets[0].data
>>> dmet.gid_to_true_dets[0].data
>>> cfsn_vecs = dmet.confusion_vectors()
>>> binvecs_ovr = cfsn_vecs.binarize_ovr()
>>> binvecs_per = cfsn_vecs.binarize_classless()
>>> measures_per = binvecs_per.measures()
>>> measures_ovr = binvecs_ovr.measures()
>>> print('measures_per = {!r}'.format(measures_per))
>>> print('measures_ovr = {!r}'.format(measures_ovr))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> measures_ovr['perclass'].draw(key='pr', fnum=2)
```




### Example


```
>>> from kwCOCO.metrics.confusion_vectors import * # NOQA
>>> from kwCOCO.metrics.detect_metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     n_fp=(0, 1), n_fn=(0, 1), nimgs=32, nboxes=(0, 16),
>>>     classes=3, rng=0, newstyle=1, box_noise=0.5, cls_noise=0.0, score_
>>> _noise=0.3, with_probs=False)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> summary = dmet.summarize(plot=True, title='DetectionMetrics summary demo', u
>>> _with_ovr=True, with_bin=False)
>>> summary['bin_measures']
>>> kwplot.show_if_requested()
```

```
summarize(out_dpath=None, plot=False, title='', with_bin='auto', with_ovr='auto')
```

## Example

```
>>> from kwcoco.metrics.confusion_vectors import * # NOQA
>>> from kwcoco.metrics.detect_metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     n_fp=(0, 128), n_fn=(0, 4), nimgs=512, nboxes=(0, 32),
>>>     classes=3, rng=0)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autmpl()
>>> dmet.summarize(plot=True, title='DetectionMetrics summary demo')
>>> kwplot.show_if_requested()
```





```
kwcoco.metrics.detect_metrics.pycocotools_confusion_vectors(dmet, evaler, iou_thresh=0.5,
                                                               verbose=0)
```

### Example

```
>>> # xdoctest: +REQUIRES(module:pycocotools)
>>> from kwcoco.metrics.detect_metrics import *
>>> dmet = DetectionMetrics.demo()
>>>     nimgs=10, nboxes=(0, 3), n_fn=(0, 1), n_fp=(0, 1), classes=8, with_
+probs=False)
>>> coco_scores = dmet.score_pycocotools(with_evaler=True)
>>> evaler = coco_scores['evaler']
>>> cfsn_vecs = pycocotools_confusion_vectors(dmet, evaler, verbose=1)
```

```
kwcoco.metrics.detect_metrics.eval_detections_cli(**kw)
```

DEPRECATED USE *kwcoco eval* instead

## CommandLine

```
xdoc test -m ~/code/kwCOCO/kwCOCO/metrics/detect_metrics.py eval_detections_cli
```

```
kwCOCO.metrics.detect_metrics.pct_summarize2(self)
```

### 2.1.1.5.1.6 kwCOCO.metrics.drawing module

```
kwCOCO.metrics.drawing.draw_perclass_roc(cx_to_info, classes=None, prefix='', fnum=1, fp_axis='count', **kw)
```

#### Parameters

- **cx\_to\_info** (*kwCOCO.metrics.confusion\_measures.PerClass\_Measures | Dict*)
- **fp\_axis** (*str*) – can be count or rate

```
kwCOCO.metrics.drawing.demo_format_options()
```

```
kwCOCO.metrics.drawing.concise_si_display(val, eps=1e-08, precision=2, si_thresh=4)
```

Display numbers in scientific notation if above a threshold

#### Parameters

- **eps** (*float*) – threshold to be formatted as an integer if other integer conditions hold.
- **precision** (*int*) – maximum significant digits (might print less)
- **si\_thresh** (*int*) – If the number is less than  $10^{\{si\_thresh\}}$ , then it will be printed as an integer if it is within *eps* of an integer.

## References

<https://docs.python.org/2/library/stdtypes.html#string-formatting-operations>

## Example

```
>>> grid = {
>>>     'sign': [1, -1],
>>>     'exp': [1, -1],
>>>     'big_part': [0, 32132e3, 4000000032],
>>>     'med_part': [0, 0.5, 0.9432, 0.000043, 0.01, 1, 2],
>>>     'small_part': [0, 1321e-3, 43242e-11],
>>> }
>>> for kw in ub.named_product(grid):
>>>     sign = kw.pop('sign')
>>>     exp = kw.pop('exp')
>>>     raw = (sum(map(float, kw.values())))
>>>     val = sign * raw ** exp if raw != 0 else sign * raw
>>>     print('{:>20} - {}'.format(concise_si_display(val), val))
>>> from kwCOCO.metrics.drawing import * # NOQA
>>> print(concise_si_display(40000000432432))
>>> print(concise_si_display(473243280432890))
>>> print(concise_si_display(473243284289))
```

(continues on next page)

(continued from previous page)

```
>>> print(concise_si_display(473243289))
>>> print(concise_si_display(4739))
>>> print(concise_si_display(473))
>>> print(concise_si_display(0.432432))
>>> print(concise_si_display(0.132432))
>>> print(concise_si_display(1.0000043))
>>> print(concise_si_display(01.0000000000000000000000000000043))
```


```
kwcoco.metrics.drawing.draw_perclass_prcurve(cx_to_info, classes=None, prefix='', fnum=1, **kw)
```

#### Parameters

`cx_to_info` (`kwcoco.metrics.confusion_measures.PerClass_Measures` | `Dict`)

#### Example

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> from kwcoco.metrics.drawing import * # NOQA
>>> from kwcoco.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=3, nboxes=(0, 10), n_fp=(0, 3), n_fn=(0, 2), classes=3, score_noise=0.
>>>     ↵1, box_noise=0.1, with_probs=False)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> print(cfsn_vecs.data.pandas())
>>> classes = cfsn_vecs.classes
>>> cx_to_info = cfsn_vecs.binarize_ovr().measures()['perclass']
>>> print('cx_to_info = {}'.format(ub.repr2(cx_to_info, nl=1)))
>>> import kwplot
>>> kwplot.autompl()
>>> draw_perclass_prcurve(cx_to_info, classes)
>>> # xdoctest: +REQUIRES(--show)
>>> kwplot.show_if_requested()
```



```
kwCOCO.metrics.drawing.draw_perclass_thresholds(cx_to_info, key='mcc', classes=None, prefix='',
                                                fnum=1, **kw)
```

#### Parameters

`cx_to_info` (`kwCOCO.metrics.confusion_measures.PerClass_Measures` | `Dict`)


---

**Note:** Each category is inspected independently of one another, there is no notion of confusion.

---

#### Example

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> from kwCOCO.metrics.drawing import * # NOQA
>>> from kwCOCO.metrics import ConfusionVectors
>>> cfsn_vecs = ConfusionVectors.demo()
>>> classes = cfsn_vecs.classes
>>> ovr_cfsn = cfsn_vecs.binarize_ovr(keyby='name')
>>> cx_to_info = ovr_cfsn.measures()['perclass']
>>> import kwplot
>>> kwplot.autopl()l()
>>> key = 'mcc'
>>> draw_perclass_thresholds(cx_to_info, key, classes)
>>> # xdoctest: +REQUIRES(--show)
>>> kwplot.show_if_requested()
```



```
kwCOCO.metrics.drawing.draw_roc(info, prefix='', fnum=1, **kw)
```

#### Parameters

info (Measures | Dict)

---

**Note:** There needs to be enough negative examples for using ROC to make any sense!

---


#### Example

```
>>> # xdoctest: +REQUIRES(module:kwplot, module:seaborn)
>>> from kwCOCO.metrics.drawing import * # NOQA
>>> from kwCOCO.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(nimgs=30, null_pred=1, classes=3,
>>>                         nboxes=10, n_fp=10, box_noise=0.3,
>>>                         with_probs=False)
>>> dmet.true_detections(0).data
>>> cfsn_vecs = dmet.confusion_vectors(compat='mutex', prioritize='iou', bias=0)
>>> print(cfsn_vecs.data._pandas().sort_values('score'))
>>> classes = cfsn_vecs.classes
>>> info = ub.peek(cfsn_vecs.binarize_ovr().measures()['perclass'].values())
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
```

(continues on next page)

(continued from previous page)

```
>>> kwplot.autompl()
>>> draw_roc(info)
>>> kwplot.show_if_requested()
```



`kwcoco.metrics.drawing.draw_prcurve(info, prefix='', fnum=1, **kw)`

Draws a single pr curve.

#### Parameters

`info (Measures | Dict)`

#### Example


```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> from kwcoco.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 10), n_fp=(0, 1), classes=3)
>>> cfsn_vecs = dmet.confusion_vectors()

>>> classes = cfsn_vecs.classes
>>> info = cfsn_vecs.binarize_classless().measures()
>>> import kwplot
>>> kwplot.autompl()
>>> draw_prcurve(info)
```

(continues on next page)

(continued from previous page)

```
>>> # xdoctest: +REQUIRES(--show)
>>> kwplot.show_if_requested()
```



```
kwcoco.metrics.drawing.draw_threshold_curves(info, keys=None, prefix='', fnum=1, **kw)
```

#### Parameters


- **info** (*Measures* | *Dict*)
- **keys** (*None* | *List[str]*) – the metrics to view over thresholds

## CommandLine

```
xdoctest -m kwcoco.metrics.drawing draw_threshold_curves --show
```

## Example

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> from kwcoco.metrics.drawing import * # NOQA
>>> from kwcoco.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo()
>>> nimgs=10, nboxes=(0, 10), n_fp=(0, 1), classes=3
>>> cfsn_vecs = dmet.confusion_vectors()
>>> info = cfsn_vecs.binarize_classless().measures()
>>> keys = None
>>> import kwplot
>>> kwplot.autopl()
>>> keys = {'g1', 'f1', 'acc', 'mcc', 'tpr'}
>>> draw_threshold_curves(info, keys)
>>> # xdoctest: +REQUIRES(--show)
>>> kwplot.show_if_requested()
```



`kwcoco.metrics.drawing.deterministic_colors(keys, preset_colors)`

### 2.1.1.5.1.7 kwcoco.metrics.functional module

`kwcoco.metrics.functional.fast_confusion_matrix(y_true, y_pred, n_labels, sample_weight=None)`

faster version of sklearn confusion matrix that avoids the expensive checks and label rectification

#### Parameters

- **y\_true** (*ndarray*) – ground truth class label for each sample
- **y\_pred** (*ndarray*) – predicted class label for each sample
- **n\_labels** (*int*) – number of labels
- **sample\_weight** (*ndarray | None*) – weight of each sample Extended typing *ndarray[Any, int | Float]*

#### Returns

matrix where rows represent real and cols represent pred and the value at each cell is the total amount of weight Extended typing *ndarray[Shape['\*', '\*'], Int64 | Float64]*

#### Return type

*ndarray*

#### Example

```
>>> y_true = np.array([0, 0, 0, 0, 1, 1, 1, 0, 0, 1])
>>> y_pred = np.array([0, 0, 0, 0, 0, 0, 0, 1, 1, 1])
>>> fast_confusion_matrix(y_true, y_pred, 2)
array([[4, 2],
       [3, 1]])
>>> fast_confusion_matrix(y_true, y_pred, 2).ravel()
array([4, 2, 3, 1])
```

### 2.1.1.5.1.8 kwcoco.metrics.sklearn\_alts module

Faster pure-python versions of sklearn functions that avoid expensive checks and label rectifications. It is assumed that all labels are consecutive non-negative integers.

`kwcoco.metrics.sklearn_alts.confusion_matrix(y_true, y_pred, n_labels=None, labels=None, sample_weight=None)`

faster version of sklearn confusion matrix that avoids the expensive checks and label rectification

Runs in about 0.7ms

#### Returns

matrix where rows represent real and cols represent pred

#### Return type

*ndarray*

## Example

```
>>> y_true = np.array([0, 0, 0, 0, 1, 1, 1, 0, 1])
>>> y_pred = np.array([0, 0, 0, 0, 0, 0, 1, 1, 1])
>>> confusion_matrix(y_true, y_pred, 2)
array([[4, 2],
       [3, 1]])
>>> confusion_matrix(y_true, y_pred, 2).ravel()
array([4, 2, 3, 1])
```

## Benchmark

```
>>> # xdoctest: +SKIP
>>> import ubelt as ub
>>> y_true = np.random.randint(0, 2, 10000)
>>> y_pred = np.random.randint(0, 2, 10000)
>>> n = 1000
>>> for timer in ub.Timerit(n, bestof=10, label='py-time'):
>>>     sample_weight = [1] * len(y_true)
>>>     confusion_matrix(y_true, y_pred, 2, sample_weight=sample_weight)
>>> for timer in ub.Timerit(n, bestof=10, label='np-time'):
>>>     sample_weight = np.ones(len(y_true), dtype=int)
>>>     confusion_matrix(y_true, y_pred, 2, sample_weight=sample_weight)
```

`kwcoco.metrics.sklearn_alts.global_accuracy_from_confusion(cfsn)`

`kwcoco.metrics.sklearn_alts.class_accuracy_from_confusion(cfsn)`

### 2.1.1.5.1.9 kwcoco.metrics.util module

### 2.1.1.5.1.10 kwcoco.metrics.voc\_metrics module

`class kwcoco.metrics.voc_metrics.VOC_Metrics(classes=None)`

Bases: `NiceRepr`

API to compute object detection scores using Pascal VOC evaluation method.

To use, add true and predicted detections for each image and then run the `VOC_Metrics.score()` function.

#### Variables

- `recs` (`Dict[int, List[dict]]`) – true boxes for each image. maps image ids to a list of records within that image. Each record is a tlbr bbox, a difficult flag, and a class name.
- `cx_to_lines` (`Dict[int, List]`) – VOC formatted prediction predictions. mapping from class index to all predictions for that category. Each “line” is a list of [`<imgid>`, `<score>`, `<tl_x>`, `<tl_y>`, `<br_x>`, `<br_y>`].
- `classes` (`None` / `List[str]` / `kwcoco.CategoryTree`) – class names

`add_truth(true_dets, gid)`


`add_predictions(pred_dets, gid)`

```
score(iou_thresh=0.5, bias=1, method='voc2012')
```

Compute VOC scores for every category

### Example

```
>>> from kwCOCO.metrics.detect_metrics import DetectionMetrics
>>> from kwCOCO.metrics.voc_metrics import * # NOQA
>>> dmet = DetectionMetrics.demo()
>>> nimgs=1, nboxes=(0, 100), n_fp=(0, 30), n_fn=(0, 30), classes=2, score_
->>> noise=0.9
>>> self = VOC_Metrics(classes=dmet.classes)
>>> self.add_truth(dmet.true_detections(0), 0)
>>> self.add_predictions(dmet.pred_detections(0), 0)
>>> voc_scores = self.score()
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()l()
>>> kwplot.figure(fnum=1, doclf=True)
>>> voc_scores['perclass'].draw()
```



```
kwplot.figure(fnum=2)      dmet.true_detections(0).draw(color='green',      labels=None)
dmet.pred_detections(0).draw(color='blue',    labels=None)  kwplot.autopl().gca().set_xlim(0, 100)
kwplot.autopl().gca().set_ylim(0, 100)
```

### 2.1.1.5.2 Module contents

`mkinit kwcocoo.metrics -w --relative`

**class** `kwcocoo.metrics.BinaryConfusionVectors(data, cx=None, classes=None)`

Bases: `NiceRepr`

Stores information about a binary classification problem. This is always with respect to a specific class, which is given by `cx` and `classes`.

The `data DataFrameArray` must contain

`is_true` - if the row is an instance of class `classes[cx]` `pred_score` - the predicted probability of class `classes[cx]`, and `weight` - sample weight of the example

#### Example

```
>>> from kwcocoo.metrics.confusion_vectors import * # NOQA
>>> self = BinaryConfusionVectors.demo(n=10)
>>> print('self = {!r}'.format(self))
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

```
>>> self = BinaryConfusionVectors.demo(n=0)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

```
>>> self = BinaryConfusionVectors.demo(n=1)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

```
>>> self = BinaryConfusionVectors.demo(n=2)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
```

**classmethod** `demo(n=10, p_true=0.5, p_error=0.2, p_miss=0.0, rng=None)`

Create random data for tests

#### Parameters


- `n (int)` – number of rows
- `p_true (float)` – fraction of real positive cases
- `p_error (float)` – probability of making a recoverable mistake
- `p_miss (float)` – probability of making a unrecoverable mistake
- `rng (int | RandomState | None)` – random seed / state

#### Returns

`BinaryConfusionVectors`

## Example

```
>>> from kwCOCO.metrics.confusion_vectors import * # NOQA
>>> cfsn = BinaryConfusionVectors.demo(n=1000, p_error=0.1, p_miss=0.1)
>>> measures = cfsn.measures()
>>> print('measures = {}'.format(ub.repr2(measures, nl=1)))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> kwplot.figure(fnum=1, pnum=(1, 2, 1))
>>> measures.draw('pr')
>>> kwplot.figure(fnum=1, pnum=(1, 2, 2))
>>> measures.draw('roc')
```



**property catname**

**measures**(*stabilize\_thresh*=7, *fp\_cutoff*=None, *monotonic\_ppv*=True, *ap\_method*='pycocotools')

Get statistics (F1, G1, MCC) versus thresholds

### Parameters

- **stabilize\_thresh** (*int*, *default*=7) – if fewer than this many data points inserts dummy stabilization data so curves can still be drawn.
- **fp\_cutoff** (*int* | *None*) – maximum number of false positives in the truncated roc curves. The default of *None* is equivalent to `float('inf')`.
- **monotonic\_ppv** (*bool*) – if *True* ensures that precision is always increasing as recall decreases. This is done in pycocotools scoring, but I'm not sure its a good idea.

## Example

```
>>> from kwcoco.metrics.confusion_vectors import * # NOQA
>>> self = BinaryConfusionVectors.demo(n=0)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
>>> self = BinaryConfusionVectors.demo(n=1, p_true=0.5, p_error=0.5)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
>>> self = BinaryConfusionVectors.demo(n=3, p_true=0.5, p_error=0.5)
>>> print('measures = {}'.format(ub.repr2(self.measures())))

>>> self = BinaryConfusionVectors.demo(n=100, p_true=0.5, p_error=0.5, p_miss=0.
    ↪3)
>>> print('measures = {}'.format(ub.repr2(self.measures())))
>>> print('measures = {}'.format(ub.repr2(ub.odict(self.measures()))))
```

## References

[https://en.wikipedia.org/wiki/Confusion\\_matrix](https://en.wikipedia.org/wiki/Confusion_matrix) [https://en.wikipedia.org/wiki/Precision\\_and\\_recall](https://en.wikipedia.org/wiki/Precision_and_recall) [https://en.wikipedia.org/wiki/Matthews\\_correlation\\_coefficient](https://en.wikipedia.org/wiki/Matthews_correlation_coefficient)

### draw\_distribution()

**class kwcoco.metrics.ConfusionVectors(*data, classes, probs=None*)**

Bases: `NiceRepr`

Stores information used to construct a confusion matrix. This includes corresponding vectors of predicted labels, true labels, sample weights, etc...

### Variables

- **data** (`kwarray.DataFrameArray`) – should at least have keys true, pred, weight
- **classes** (`Sequence / CategoryTree`) – list of category names or category graph
- **probs** (`ndarray / None`) – probabilities for each class

## Example

```
>>> # xdoctest: IGNORE_WANT
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwcoco.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 10), n_fp=(0, 1), classes=3)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> print(cfsn_vecs.data._pandas())
   pred  true   score  weight      iou    txs    pxs    gid
0      2      2  10.0000  1.0000  1.0000      0      4      0
1      2      2   7.5025  1.0000  1.0000      1      3      0
2      1      1   5.0050  1.0000  1.0000      2      2      0
3      3     -1   2.5075  1.0000 -1.0000     -1      1      0
4      2     -1   0.0100  1.0000 -1.0000     -1      0      0
5     -1      2   0.0000  1.0000 -1.0000      3     -1      0
6     -1      2   0.0000  1.0000 -1.0000      4     -1      0
```


(continues on next page)

(continued from previous page)

7	2	2	10.0000	1.0000	1.0000	0	5	1
8	2	2	8.0020	1.0000	1.0000	1	4	1
9	1	1	6.0040	1.0000	1.0000	2	3	1
..	..	..	..	..	..	..	..	..
62	-1	2	0.0000	1.0000	-1.0000	7	-1	7
63	-1	3	0.0000	1.0000	-1.0000	8	-1	7
64	-1	1	0.0000	1.0000	-1.0000	9	-1	7
65	1	-1	10.0000	1.0000	-1.0000	-1	0	8
66	1	1	0.0100	1.0000	1.0000	0	1	8
67	3	-1	10.0000	1.0000	-1.0000	-1	3	9
68	2	2	6.6700	1.0000	1.0000	0	2	9
69	2	2	3.3400	1.0000	1.0000	1	1	9
70	3	-1	0.0100	1.0000	-1.0000	-1	0	9
71	-1	2	0.0000	1.0000	-1.0000	2	-1	9

```
>>> # xdoctest: +REQUIRES(--show)
>>> # xdoctest: +REQUIRES(module:pandas)
>>> import kwplot
>>> kwplot.autopl()
>>> from kwcoco.metrics.confusion_vectors import ConfusionVectors
>>> cfsn_vecs = ConfusionVectors.demo()
>>> nimgs=128, nboxes=(0, 10), n_fp=(0, 3), n_fn=(0, 3), classes=3)
>>> cx_to_binvecs = cfsn_vecs.binarize_ovr()
>>> measures = cx_to_binvecs.measures()['perclass']
>>> print('measures = {!r}'.format(measures))
measures = <PerClass_Measures{
    'cat_1': <Measures({'ap': 0.227, 'auc': 0.507, 'catname': cat_1, 'max_f1': f1=0.
        ↪45@0.47, 'nsupport': 788.000})>,
    'cat_2': <Measures({'ap': 0.288, 'auc': 0.572, 'catname': cat_2, 'max_f1': f1=0.
        ↪51@0.43, 'nsupport': 788.000})>,
    'cat_3': <Measures({'ap': 0.225, 'auc': 0.484, 'catname': cat_3, 'max_f1': f1=0.
        ↪46@0.40, 'nsupport': 788.000})>,
}) at 0x7facf77bdf0>
>>> kwplot.figure(fnum=1, doclf=True)
>>> measures.draw(key='pr', fnum=1, pnum=(1, 3, 1))
>>> measures.draw(key='roc', fnum=1, pnum=(1, 3, 2))
>>> measures.draw(key='mcc', fnum=1, pnum=(1, 3, 3))
...

```



**classmethod from\_json(state)**

**classmethod demo(\*\*kw)**

#### Parameters

\*\*kwargs – See [kwCOCO.metrics.DetectionMetrics.demo\(\)](#)

#### Returns

ConfusionVectors

#### Example

```
>>> cfsn_vecs = ConfusionVectors.demo()
>>> print('cfsn_vecs = {!r}'.format(cfsn_vecs))
>>> cx_to_binvecs = cfsn_vecs.binarize_ovr()
>>> print('cx_to_binvecs = {!r}'.format(cx_to_binvecs))
```

**classmethod from\_arrays(true, pred=None, score=None, weight=None, probs=None, classes=None)**

Construct confusion vector data structure from component arrays

## Example

```
>>> # xdoctest: +REQUIRES(module:pandas)
>>> import kwarray
>>> classes = ['person', 'vehicle', 'object']
>>> rng = kwarray.ensure_rng(0)
>>> true = (rng.rand(10) * len(classes)).astype(int)
>>> probs = rng.rand(len(true), len(classes))
>>> cfsn_vecs = ConfusionVectors.from_arrays(true=true, probs=probs, u
   ~classes=classes)
>>> cfsn_vecs.confusion_matrix()
pred      person    vehicle    object
real
person        0        0        0
vehicle       2        4        1
object        2        1        0
```

### confusion\_matrix(compress=False)

Builds a confusion matrix from the confusion vectors.

#### Parameters

**compress** (bool, default=False) – if True removes rows / columns with no entries

#### Returns

##### cm

[the labeled confusion matrix]

(Note: we should write a efficient replacement for  
this use case. #remove\_pandas)

#### Return type

pd.DataFrame

## CommandLine

```
xdoctest -m kwcoc.metrics.confusion_vectors ConfusionVectors.confusion_matrix
```

## Example

```
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwcoc.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 10), n_fp=(0, 1), n_fn=(0, 1), classes=3, cls_
   ~noise=.2)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> cm = cfsn_vecs.confusion_matrix()
...
>>> print(cm.to_string(float_format=lambda x: '%.2f' % x))
pred      background    cat_1    cat_2    cat_3
real
background        0.00    1.00    2.00    3.00
cat_1            3.00   12.00    0.00    0.00
```

(continues on next page)

(continued from previous page)

cat_2	3.00	0.00	14.00	0.00
cat_3	2.00	0.00	0.00	17.00

**coarsen(cx)**

Creates a coarsened set of vectors

**Returns**

ConfusionVectors

**binarize\_classless(negative\_classes=None)**

Creates a binary representation useful for measuring the performance of detectors. It is assumed that scores of “positive” classes should be high and “negative” classes should be low.

**Parameters**

- **negative\_classes** (*List[str | int] | None*) – list of negative class names or idxs, by default chooses any class with a true class index of -1. These classes should ideally have low scores.

**Returns**

BinaryConfusionVectors

**Note:** The “classlessness” of this depends on the compat=”all” argument being used when constructing confusion vectors, otherwise it becomes something like a macro-average because the class information was used in deciding which true and predicted boxes were allowed to match.

**Example**

```
>>> from kwcoco.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo()
>>> nimgs=10, nboxes=(0, 10), n_fp=(0, 1), n_fn=(0, 1), classes=3
>>> cfsn_vecs = dmet.confusion_vectors()
>>> class_idxs = list(dmet.classes.node_to_idx.values())
>>> binvecs = cfsn_vecs.binarize_classless()
```

**binarize\_ovr(mode=1, keyby='name', ignore\_classes={'ignore'}, approx=False)**

Transforms cfsn\_vecs into one-vs-rest BinaryConfusionVectors for each category.

**Parameters**

- **mode** (*int, default=1*) – 0 for hierarchy aware or 1 for voc like. MODE 0 IS PROBABLY BROKEN
- **keyby** (*int | str*) – can be cx or name
- **ignore\_classes** (*Set[str]*) – category names to ignore
- **approx** (*bool, default=False*) – if True try and approximate missing scores otherwise assume they are irrecoverable and use -inf

**Returns****which behaves like**

Dict[int, BinaryConfusionVectors]: cx\_to\_binvecs

**Return type***OneVsRestConfusionVectors*

## Example

```
>>> from kwcoco.metrics.confusion_vectors import * # NOQA
>>> cfsn_vecs = ConfusionVectors.demo()
>>> print('cfsn_vecs = {!r}'.format(cfsn_vecs))
>>> catname_to_binvecs = cfsn_vecs.binarize_ovr(keyby='name')
>>> print('catname_to_binvecs = {!r}'.format(catname_to_binvecs))
```

```
cfsn_vecs.data.pandas() catname_to_binvecs.cx_to_binvecs['class_1'].data.pandas()
```

---

### Note:

---

**classification\_report(***verbose=0*)

Build a classification report with various metrics.

## Example

```
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwcoco.metrics.confusion_vectors import * # NOQA
>>> cfsn_vecs = ConfusionVectors.demo()
>>> report = cfsn_vecs.classification_report(verbose=1)
```

**class kwcoco.metrics.DetectionMetrics(***classes=None*)

Bases: `NiceRepr`

Object that computes associations between detections and can convert them into sklearn-compatible representations for scoring.

### Variables

- **gid\_to\_true\_dets** (*Dict*) – maps image ids to truth
- **gid\_to\_pred\_dets** (*Dict*) – maps image ids to predictions
- **classes** (`kwcoco.CategoryTree`) – category coder

## Example

```
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=100, nboxes=(0, 3), n_fp=(0, 1), classes=8, score_noise=0.9, ↴
>>>     hacked=False)
>>> print(dmet.score_kwCOCO(bias=0, compat='mutex', prioritize='iou')['mAP'])
...
>>> # NOTE: IN GENERAL NETHARN AND VOC ARE NOT THE SAME
>>> print(dmet.score_voc(bias=0)['mAP'])
0.8582...
>>> #print(dmet.score_coco()['mAP'])
```

`clear()`

**enrich\_confusion\_vectors(*cfsn\_vecs*)**

Adds annotation id information into confusion vectors computed via this detection metrics object.

TODO: should likely use this at the end of the function that builds the confusion vectors.

**classmethod from\_coco(*true\_coco*, *pred\_coco*, *gids=None*, *verbose=0*)**

Create detection metrics from two coco files representing the truth and predictions.

**Parameters**

- **true\_coco** (*kwCOCO.CocoDataset*)
- **pred\_coco** (*kwCOCO.CocoDataset*)

**Example**

```
>>> import kwCOCO
>>> from kwCOCO.demo.perterb import perterb_coco
>>> true_coco = kwCOCO.CocoDataset.demo('shapes')
>>> perterbkw = dict(box_noise=0.5, cls_noise=0.5, score_noise=0.5)
>>> pred_coco = perterb_coco(true_coco, **perterbkw)
>>> self = DetectionMetrics.from_coco(true_coco, pred_coco)
>>> self.score_voc()
```

**add\_predictions(*pred\_dets*, *imgname=None*, *gid=None*)**

Register/Add predicted detections for an image

**Parameters**

- **pred\_dets** (*kwimage.Detections*) – predicted detections
- **imgname** (*str | None*) – a unique string to identify the image
- **gid** (*int | None*) – the integer image id if known

**add\_truth(*true\_dets*, *imgname=None*, *gid=None*)**

Register/Add groundtruth detections for an image

**Parameters**

- **true\_dets** (*kwimage.Detections*) – groundtruth
- **imgname** (*str | None*) – a unique string to identify the image
- **gid** (*int | None*) – the integer image id if known

**true\_detections(*gid*)**

gets Detections representation for groundtruth in an image

**pred\_detections(*gid*)**

gets Detections representation for predictions in an image

**confusion\_vectors(*iou\_thresh=0.5*, *bias=0*, *gids=None*, *compat='mutex'*, *prioritize='iou'*,  
*ignore\_classes='ignore'*, *background\_class=NoParam*, *verbose='auto'*, *workers=0*,  
*track\_probs='try'*, *max\_dets=None*)**

Assigns predicted boxes to the true boxes so we can transform the detection problem into a classification problem for scoring.

**Parameters**

- **iou\_thresh** (*float | List[float]*) – bounding box overlap iou threshold required for assignment if a list, then return type is a dict. Defaults to 0.5
- **bias** (*float*) – for computing bounding box overlap, either 1 or 0 Defaults to 0.
- **gids** (*List[int] | None*) – which subset of images ids to compute confusion metrics on. If not specified all images are used. Defaults to None.
- **compat** (*str*) – can be ('ancestors' | 'mutex' | 'all'). determines which pred boxes are allowed to match which true boxes. If 'mutex', then pred boxes can only match true boxes of the same class. If 'ancestors', then pred boxes can match true boxes that match or have a coarser label. If 'all', then any pred can match any true, regardless of its category label. Defaults to all.
- **prioritize** (*str*) – can be ('iou' | 'class' | 'correct') determines which box to assign to if multiple true boxes overlap a predicted box. if prioritize is iou, then the true box with maximum iou (above iou\_thresh) will be chosen. If prioritize is class, then it will prefer matching a compatible class above a higher iou. If prioritize is correct, then ancestors of the true class are preferred over descendants of the true class, over unrelated classes. Default to 'iou'
- **ignore\_classes** (*set | str*) – class names indicating ignore regions. Default={ 'ignore' }
- **background\_class** (*str | NoParamType*) – Name of the background class. If unspecified we try to determine it with heuristics. A value of None means there is no background class.
- **verbose** (*int | str*) – verbosity flag. Default to 'auto'. In auto mode, verbose=1 if len(gids) > 1000.
- **workers** (*int*) – number of parallel assignment processes. Defaults to 0
- **track\_probs** (*str*) – can be 'try', 'force', or False. if truthy, we assume probabilities for multiple classes are available. default='try'

**Returns**

ConfusionVectors | Dict[float, ConfusionVectors]

**Example**

```
>>> dmet = DetectionMetrics.demo(nimgs=30, classes=3,
>>>                               nboxes=10, n_fp=3, box_noise=10,
>>>                               with_probs=False)
>>> iou_to_cfsn = dmet.confusion_vectors(iou_thresh=[0.3, 0.5, 0.9])
>>> for t, cfsn in iou_to_cfsn.items():
>>>     print('t = {!r}'.format(t))
...     print(cfsn.binarize_ovr().measures())
...     print(cfsn.binarize_classless().measures())
```

**score\_kwant**(*iou\_thresh*=0.5)

Scores the detections using kwant

**score\_kwcoco**(*iou\_thresh*=0.5, *bias*=0, *gids*=None, *compat*'all', *prioritize*'iou')

our scoring method

**score\_voc**(*iou\_thresh*=0.5, *bias*=1, *method*'voc2012', *gids*=None, *ignore\_classes*'ignore')

score using voc method

**Example**

```
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=100, nboxes=(0, 3), n_fp=(0, 1), classes=8,
>>>     score_noise=.5)
>>> print(dmet.score_voc()['mAP'])
0.9399...
```

**score\_pycocotools**(*with\_evaler=False*, *with\_confusion=False*, *verbose=0*, *iou\_thresholds=None*)  
score using ms-coco method

**Returns**

dictionary with pct info

**Return type**

Dict

**Example**

```
>>> # xdoctest: +REQUIRES(module:pycocotools)
>>> from kwcoco.metrics.detect_metrics import *
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 3), n_fn=(0, 1), n_fp=(0, 1), classes=8, with_
>>>     probs=False)
>>> pct_info = dmet.score_pycocotools(verbose=1,
>>>                                     with_evaler=True,
>>>                                     with_confusion=True,
>>>                                     iou_thresholds=[0.5, 0.9])
>>> evaler = pct_info['evaler']
>>> iou_to_cfsn_vecs = pct_info['iou_to_cfsn_vecs']
>>> for iou_thresh in iou_to_cfsn_vecs.keys():
>>>     print('iou_thresh = {!r}'.format(iou_thresh))
>>>     cfsn_vecs = iou_to_cfsn_vecs[iou_thresh]
>>>     ovr_measures = cfsn_vecs.binarize_ovr().measures()
>>>     print('ovr_measures = {}'.format(ub.repr2(ovr_measures, nl=1,_
>>>     precision=4)))
```

---

**Note:** by default pycocotools computes average precision as the literal average of computed precisions at 101 uniformly spaced recall thresholds.

pycocoutils seems to only allow predictions with the same category as the truth to match those truth objects. This should be the same as calling dmet.confusion\_vectors with compat = mutex

pycocoutils does not take into account the fact that each box often has a score for each category.

pycocoutils will be incorrect if any annotation has an id of 0

a major difference in the way kwcoco scores versus pycocoutils is the calculation of AP. The assignment between truth and predicted detections produces similar enough results. Given our confusion vectors we use the scikit-learn definition of AP, whereas pycocoutils seems to compute precision and recall — more or less correctly — but then it resamples the precision at various specified recall thresholds (in the *accumulate* function, specifically how *pr* is resampled into the *q* array). This can lead to a large difference in reported scores.

pycocoutils also smooths out the precision such that it is monotonic decreasing, which might not be the best idea.

pycocotools area ranges are inclusive on both ends, that means the “small” and “medium” truth selections do overlap somewhat.

---

`score_coco(with_evaler=False, with_confusion=False, verbose=0, iou_thresholds=None)`

score using ms-coco method

**Returns**

dictionary with pct info

**Return type**

Dict

**Example**

```
>>> # xdoctest: +REQUIRES(module:pycocotools)
>>> from kwcocod.metrics.detect_metrics import *
>>> dmet = DetectionMetrics.demo(
>>>     nimgs=10, nboxes=(0, 3), n_fn=(0, 1), n_fp=(0, 1), classes=8, with_
>>>     _probs=False)
>>> pct_info = dmet.score_pycocotools(verbose=1,
>>>                                     with_evaler=True,
>>>                                     with_confusion=True,
>>>                                     iou_thresholds=[0.5, 0.9])
>>> evaler = pct_info['evaler']
>>> iou_to_cfsn_vecs = pct_info['iou_to_cfsn_vecs']
>>> for iou_thresh in iou_to_cfsn_vecs.keys():
>>>     print('iou_thresh = {!r}'.format(iou_thresh))
>>>     cfsn_vecs = iou_to_cfsn_vecs[iou_thresh]
>>>     ovr_measures = cfsn_vecs.binarize_ovr().measures()
>>>     print('ovr_measures = {}'.format(ub.repr2(ovr_measures, nl=1,_
>>>     precision=4)))
```

---

**Note:** by default pycocotools computes average precision as the literal average of computed precisions at 101 uniformly spaced recall thresholds.

pycocoutils seems to only allow predictions with the same category as the truth to match those truth objects. This should be the same as calling `dmet.confusion_vectors` with `compat = mutex`

pycocoutils does not take into account the fact that each box often has a score for each category.

pycocoutils will be incorrect if any annotation has an id of 0

a major difference in the way kwcocod scores versus pycocoutils is the calculation of AP. The assignment between truth and predicted detections produces similar enough results. Given our confusion vectors we use the scikit-learn definition of AP, whereas pycocoutils seems to compute precision and recall — more or less correctly — but then it resamples the precision at various specified recall thresholds (in the `accumulate` function, specifically how `pr` is resampled into the `q` array). This can lead to a large difference in reported scores.

pycocoutils also smooths out the precision such that it is monotonic decreasing, which might not be the best idea.

---

pycocotools area ranges are inclusive on both ends, that means the “small” and “medium” truth selections do overlap somewhat.

---

**classmethod demo(\*\*kwargs)**

Creates random true boxes and predicted boxes that have some noisy offset from the truth.

**Kwargs:**
**classes (int):**

class list or the number of foreground classes. Defaults to 1.

nimgs (int): number of images in the coco datasets. Defaults to 1.

nboxes (int): boxes per image. Defaults to 1.

n\_fp (int): number of false positives. Defaults to 0.

**n\_fn (int):**

number of false negatives. Defaults to 0.

**box\_noise (float):**

std of a normal distribution used to perterb both box location and box size. Defaults to 0.

**cls\_noise (float):**

probability that a class label will change. Must be within 0 and 1. Defaults to 0.

**anchors (ndarray):**

used to create random boxes. Defaults to None.

**null\_pred (bool):**

if True, predicted classes are returned as null, which means only localization scoring is suitable. Defaults to 0.

**with\_probs (bool):**

if True, includes per-class probabilities with predictions Defaults to 1.

## CommandLine

```
xdoctest -m kwcoco.metrics.detect_metrics DetectionMetrics.demo:2 --show
```

## Example

```
>>> kwargs = {}
>>> # Seed the RNG
>>> kwargs['rng'] = 0
>>> # Size parameters determine how big the data is
>>> kwargs['nimgs'] = 5
>>> kwargs['nboxes'] = 7
>>> kwargs['classes'] = 11
>>> # Noise parameters perterb predictions further from the truth
>>> kwargs['n_fp'] = 3
>>> kwargs['box_noise'] = 0.1
>>> kwargs['cls_noise'] = 0.5
>>> dmet = DetectionMetrics.demo(**kwargs)
>>> print('dmet.classes = {}'.format(dmet.classes))
```


(continues on next page)

(continued from previous page)

```
dmet.classes = <CategoryTree(nNodes=12, maxDepth=3, maxBreadth=4...)>
>>> # Can grab kwimage.Detection object for any image
>>> print(dmet.true_detections(gid=0))
<Detections(4)>
>>> print(dmet.pred_detections(gid=0))
<Detections(7)>
```

## Example

```
>>> # Test case with null predicted categories
>>> dmet = DetectionMetrics.demo(nimgs=30, null_pred=1, classes=3,
>>>                               nboxes=10, n_fp=3, box_noise=0.1,
>>>                               with_probs=False)
>>> dmet.gid_to_pred_dets[0].data
>>> dmet.gid_to_true_dets[0].data
>>> cfsn_vecs = dmet.confusion_vectors()
>>> binvecs_ovr = cfsn_vecs.binarize_ovr()
>>> binvecs_per = cfsn_vecs.binarize_classless()
>>> measures_per = binvecs_per.measures()
>>> measures_ovr = binvecs_ovr.measures()
>>> print('measures_per = {!r}'.format(measures_per))
>>> print('measures_ovr = {!r}'.format(measures_ovr))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> measures_ovr['perclass'].draw(key='pr', fnum=2)
```




### Example


```
>>> from kwcoco.metrics.confusion_vectors import * # NOQA
>>> from kwcoco.metrics.detect_metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     n_fp=(0, 1), n_fn=(0, 1), nimgs=32, nboxes=(0, 16),
>>>     classes=3, rng=0, newstyle=1, box_noise=0.5, cls_noise=0.0, score_
>>> _noise=0.3, with_probs=False)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> summary = dmet.summarize(plot=True, title='DetectionMetrics summary demo', u
>>> _with_ovr=True, with_bin=False)
>>> summary['bin_measures']
>>> kwplot.show_if_requested()
```

`summarize(out_dpath=None, plot=False, title='', with_bin='auto', with_ovr='auto')`

## Example

```
>>> from kwcoco.metrics.confusion_vectors import * # NOQA
>>> from kwcoco.metrics.detect_metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     n_fp=(0, 128), n_fn=(0, 4), nimgs=512, nboxes=(0, 32),
>>>     classes=3, rng=0)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autmpl()
>>> dmet.summarize(plot=True, title='DetectionMetrics summary demo')
>>> kwplot.show_if_requested()
```






```
class kwCOCO.metrics.Measures(info)
```

Bases: *NiceRepr*, *DictProxy*

Holds accumulated confusion counts, and derived measures

### Example

```
>>> from kwCOCO.metrics.confusion_vectors import BinaryConfusionVectors # NOQA
>>> binvecs = BinaryConfusionVectors.demo(n=100, p_error=0.5)
>>> self = binvecs.measures()
>>> print('self = {!r}'.format(self))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> self.draw(doclf=True)
>>> self.draw(key='pr', pnum=(1, 2, 1))
>>> self.draw(key='roc', pnum=(1, 2, 2))
>>> kwplot.show_if_requested()
```



```
property catname
reconstruct()
classmethod from_json(state)
summary()
maximized_thresholds()
    Returns thresholds that maximize metrics.
counts()
draw(key=None, prefix='', **kw)
```

### Example

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> # xdoctest: +REQUIRES(module:pandas)
>>> from kwCOCO.metrics.confusion_vectors import ConfusionVectors # NOQA
>>> cfsn_vecs = ConfusionVectors.demo()
>>> ovr_cfsn = cfsn_vecs.binarize_ovr(keyby='name')
>>> self = ovr_cfsn.measures()['perclass']
>>> self.draw('mcc', doclf=True, fnum=1)
```

(continues on next page)


(continued from previous page)

```
>>> self.draw('pr', doclf=1, fnum=2)
>>> self.draw('roc', doclf=1, fnum=3)

summary_plot(fnum=1, title='', subplots='auto')
```

### Example

```
>>> from kwCOCO.metrics.confusion_measures import * # NOQA
>>> from kwCOCO.metrics.confusion_vectors import ConfusionVectors # NOQA
>>> cfsn_vecs = ConfusionVectors.demo(n=3, p_error=0.5)
>>> binvecs = cfsn_vecs.binarize_classless()
>>> self = binvecs.measures()
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autoplotted()
>>> self.summary_plot()
>>> kwplot.show_if_requested()
```



**classmethod demo(\*\*kwargs)**

Create a demo Measures object for testing / demos

#### Parameters

\*\*kwargs – passed to `BinaryConfusionVectors.demo()`. some valid keys are: n, rng, p\_rue, p\_error, p\_miss.

```
classmethod combine(tocombine, precision=None, growth=None, thresh_bins=None)
```

Combine binary confusion metrics

#### Parameters


- **tocombine** (*List[Measures]*) – a list of measures to combine into one
- **precision** (*int | None*) – If specified rounds thresholds to this precision which can prevent a RAM explosion when combining a large number of measures. However, this is a lossy operation and will impact the underlying scores. NOTE: use **growth** instead.
- **growth** (*int | None*) – if specified this limits how much the resulting measures are allowed to grow by. If *None*, growth is unlimited. Otherwise, if growth is ‘max’, the growth is limited to the maximum length of an input. We might make this more numerical in the future.
- **thresh\_bins** (*int | None*) – Force this many threshold bins.

#### Returns

`kwcoc.metrics.confusion_measures.Measures`

### Example

```
>>> from kwcoc.metrics.confusion_measures import * # NOQA
>>> measures1 = Measures.demo(n=15)
>>> measures2 = measures1
>>> tocombine = [measures1, measures2]
>>> new_measures = Measures.combine(tocombine)
>>> new_measures.reconstruct()
>>> print('new_measures = {!r}'.format(new_measures))
>>> print('measures1 = {!r}'.format(measures1))
>>> print('measures2 = {!r}'.format(measures2))
>>> print(ub.repr2(measures1.__json__(), nl=1, sort=0))
>>> print(ub.repr2(measures2.__json__(), nl=1, sort=0))
>>> print(ub.repr2(new_measures.__json__(), nl=1, sort=0))
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> kwplot.figure(fnum=1)
>>> new_measures.summary_plot()
>>> measures1.summary_plot()
>>> measures1.draw('roc')
>>> measures2.draw('roc')
>>> new_measures.draw('roc')
```



## Example

```
>>> # Demonstrate issues that can arise from choosing a precision
>>> # that is too low when combining metrics. Breakpoints
>>> # between different metrics can get muddled, but choosing a
>>> # precision that is too high can overwhelm memory.
>>> from kwCOCO.metrics.confusion_measures import * # NOQA
>>> base = ub.map_vals(np.asarray, {
>>>     'tp_count': [ 1, 1, 2, 2, 2, 3],
>>>     'fp_count': [ 0, 1, 1, 2, 3, 4, 5],
>>>     'fn_count': [ 1, 1, 0, 0, 0, 0],
>>>     'tn_count': [ 5, 4, 4, 3, 2, 1, 0],
>>>     'thresholds': [.0, .0, .0, .0, .0, .0, .0],
>>> })
>>> # Make tiny offsets to thresholds
>>> rng = kwarray.ensure_rng(0)
>>> n = len(base['thresholds'])
>>> offsets = [
>>>     sorted(rng.rand(n) * 10 ** -rng.randint(4, 7))[::-1]
>>>     for _ in range(20)
>>> ]
>>> tocombine = []
>>> for offset in offsets:
>>>     base_n = base.copy()
>>>     base_n['thresholds'] += offset
```

(continues on next page)

(continued from previous page)

```
>>>     measures_n = Measures(base_n).reconstruct()
>>>     tocombine.append(measures_n)
>>> for precision in [6, 5, 2]:
>>>     combo = Measures.combine(tocombine, precision=precision).reconstruct()
>>>     print('precision = {!r}'.format(precision))
>>>     print('combo = {}'.format(ub.repr2(combo, nl=1)))
>>>     print('num_thresholds = {}'.format(len(combo['thresholds'])))
>>> for growth in [None, 'max', 'log', 'root', 'half']:
>>>     combo = Measures.combine(tocombine, growth=growth).reconstruct()
>>>     print('growth = {!r}'.format(growth))
>>>     print('combo = {}'.format(ub.repr2(combo, nl=1)))
>>>     print('num_thresholds = {}'.format(len(combo['thresholds'])))
>>> #print(combo.counts().pandas())
```

## Example

```
>>> # Test case: combining a single measures should leave it unchanged
>>> from kwcoc.metrics.confusion_measures import * # NOQA
>>> measures = Measures.demo(n=40, p_true=0.2, p_error=0.4, p_miss=0.6)
>>> df1 = measures.counts().pandas().fillna(0)
>>> print(df1)
>>> tocombine = [measures]
>>> combo = Measures.combine(tocombine)
>>> df2 = combo.counts().pandas().fillna(0)
>>> print(df2)
>>> assert np.allclose(df1, df2)
```

```
>>> combo = Measures.combine(tocombine, thresh_bins=2)
>>> df3 = combo.counts().pandas().fillna(0)
>>> print(df3)
```

```
>>> # I am NOT sure if this is correct or not
>>> thresh_bins = 20
>>> combo = Measures.combine(tocombine, thresh_bins=thresh_bins)
>>> df4 = combo.counts().pandas().fillna(0)
>>> print(df4)
```

```
>>> combo = Measures.combine(tocombine, thresh_bins=np.linspace(0, 1, 20))
>>> df4 = combo.counts().pandas().fillna(0)
>>> print(df4)
```

```
assert np.allclose(combo['thresholds'], measures['thresholds']) assert np.allclose(combo['fp_count'], measures['fp_count']) assert np.allclose(combo['tp_count'], measures['tp_count']) assert np.allclose(combo['tp_count'], measures['tp_count'])

globals().update(xdev.get_func_kwargs(Measures.combine))
```

## Example

```
>>> # Test degenerate case
>>> from kwcocoo.metrics.confusion_measures import * # NOQA
>>> tocombine = [
>>>     {'fn_count': [0.0], 'fp_count': [359980.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [7747.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [360849.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [424.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [367003.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [991.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [367976.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [1017.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [676338.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [7067.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [676348.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [7406.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [676626.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [7858.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [676693.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [10969.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677269.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [11188.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677331.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [11734.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677395.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [11556.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677418.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [11621.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677422.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [11424.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677648.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [9804.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677826.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [2470.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677834.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [2470.0]}, 
>>>     {'fn_count': [0.0], 'fp_count': [677835.0], 'thresholds': [0.0], 'tn_
>>> _count': [0.0], 'tp_count': [2470.0]}, 
>>>     {'fn_count': [11123.0, 0.0], 'fp_count': [0.0, 676754.0], 'thresholds': [_
>>> [0.0002442002442002442, 0.0], 'tn_count': [676754.0, 0.0], 'tp_count': [2.0,_
>>> 11125.0]}, 
>>>     {'fn_count': [7738.0, 0.0], 'fp_count': [0.0, 676466.0], 'thresholds': [_
>>> [0.0002442002442002442, 0.0], 'tn_count': [676466.0, 0.0], 'tp_count': [0.0,_
>>> 7738.0]}, 
>>>     {'fn_count': [8653.0, 0.0], 'fp_count': [0.0, 676341.0], 'thresholds': [_
>>> [0.0002442002442002442, 0.0], 'tn_count': [676341.0, 0.0], 'tp_count': [0.0,_
>>> 8653.0]}, 
>>> ]
>>> thresh_bins = np.linspace(0, 1, 4)
>>> combo = Measures.combine(tocombine, thresh_bins=thresh_bins).reconstruct()
>>> print('tocombine = {}'.format(ub.repr2(tocombine, nl=2)))
>>> print('thresh_bins = {!r}'.format(thresh_bins))
```

(continues on next page)

(continued from previous page)

```
>>> print(ub.repr2(combo.__json__(nl=1)))
>>> for thresh_bins in [4096, 1]:
>>>     combo = Measures.combine(tocombine, thresh_bins=tthresh_bins).
>>>     reconstruct()
>>>     print('thresh_bins = {!r}'.format(thresh_bins))
>>>     print('combo = {}'.format(ub.repr2(combo, nl=1)))
>>>     print('num_thresholds = {}'.format(len(combo['thresholds'])))
>>> for precision in [6, 5, 2]:
>>>     combo = Measures.combine(tocombine, precision=precision).reconstruct()
>>>     print('precision = {!r}'.format(precision))
>>>     print('combo = {}'.format(ub.repr2(combo, nl=1)))
>>>     print('num_thresholds = {}'.format(len(combo['thresholds'])))
>>> for growth in [None, 'max', 'log', 'root', 'half']:
>>>     combo = Measures.combine(tocombine, growth=growth).reconstruct()
>>>     print('growth = {!r}'.format(growth))
>>>     print('combo = {}'.format(ub.repr2(combo, nl=1)))
>>>     print('num_thresholds = {}'.format(len(combo['thresholds'])))
```

**class kwcoc.metrics.OneVsRestConfusionVectors(cx\_to\_binvecs, classes)**Bases: `NiceRepr`

Container for multiple one-vs-rest binary confusion vectors

**Variables**

- `cx_to_binvecs` –
- `classes` –

**Example**

```
>>> from kwcoc.metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo()
>>> nimgs=10, nboxes=(0, 10), n_fp=(0, 1), classes=3
>>> cfsn_vecs = dmet.confusion_vectors()
>>> self = cfsn_vecs.binarize_ovr(keyby='name')
>>> print('self = {!r}'.format(self))
```

**classmethod demo()****Parameters**`**kwargs` – See `kwcoc.metrics.DetectionMetrics.demo()`**Returns**

ConfusionVectors

**keys()****measures**(`stabalize_thresh=7, fp_cutoff=None, monotonic_ppv=True, ap_method='pycocotools'`)

Creates binary confusion measures for every one-versus-rest category.

**Parameters**

- `stabilize_thresh` (`int`) – if fewer than this many data points inserts dummy stabilization data so curves can still be drawn. Default to 7.

- **fp\_cutoff** (*int | None*) – maximum number of false positives in the truncated roc curves. The default `None` is equivalent to `float('inf')`
- **monotonic\_ppv** (*bool*) – if `True` ensures that precision is always increasing as recall decreases. This is done in pycocotools scoring, but I'm not sure its a good idea. Default to `True`.

**SeeAlso:**

`BinaryConfusionVectors.measures()`

**Example**

```
>>> self = OneVsRestConfusionVectors.demo()
>>> thresh_result = self.measures()['perclass']
```

`ovr_classification_report()`

```
class kwcocoo.metrics.PerClass_Measures(cx_to_info)
Bases: NiceRepr, DictProxy

summary()

classmethod from_json(state)

draw(key='mcc', prefix='', **kw)
```

**Example**

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> from kwcocoo.metrics.confusion_vectors import ConfusionVectors # NOQA
>>> cfsn_vecs = ConfusionVectors.demo()
>>> ovr_cfsn = cfsn_vecs.binarize_ovr(keyby='name')
>>> self = ovr_cfsn.measures()['perclass']
>>> self.draw('mcc', doclf=True, fnum=1)
>>> self.draw('pr', doclf=1, fnum=2)
>>> self.draw('roc', doclf=1, fnum=3)
```

`draw_roc(prefix='', **kw)`

`draw_pr(prefix='', **kw)`


`summary_plot(fnum=1, title='', subplots='auto')`


**CommandLine**

```
python ~/code/kwcoco/kwcoco/metrics/confusion_measures.py PerClass_Measures.
    -> summary_plot --show
```

## Example

```
>>> from kwcoc.metrics.confusion_measures import * # NOQA
>>> from kwcoc.metrics.detect_metrics import DetectionMetrics
>>> dmet = DetectionMetrics.demo(
>>>     n_fp=(0, 1), n_fn=(0, 3), nimgs=32, nboxes=(0, 32),
>>>     classes=3, rng=0, newstyle=1, box_noise=0.7, cls_noise=0.2, score_
>>> _noise=0.3, with_probs=False)
>>> cfsn_vecs = dmet.confusion_vectors()
>>> ovr_cfsn = cfsn_vecs.binarize_ovr(keyby='name', ignore_classes=['vector',
>>> 'raster'])
>>> self = ovr_cfsn.measures()['perclass']
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> import seaborn as sns
>>> sns.set()
>>> self.summary_plot(title='demo summary_plot ovr', subplots=['pr', 'roc'])
>>> kwplot.show_if_requested()
>>> self.summary_plot(title='demo summary_plot ovr', subplots=['mcc', 'acc'],
>>> fnum=2)
```





```
kwCOCO.metrics.eval_detections_cli(**kw)
```

DEPRECATED USE `kwCOCO eval` instead

### CommandLine

```
xdotest -m ~/code/kwCOCO/kwCOCO/metrics/detect_metrics.py eval_detections_cli
```

## 2.1.1.6 kwCOCO.util package

### 2.1.1.6.1 Subpackages

#### 2.1.1.6.1.1 kwCOCO.util.delayed\_ops package

##### 2.1.1.6.1.2 Module contents

Functionality has been ported to `delayed_image`

```
class kwCOCO.util.delayed_ops.DelayedArray(subdata=None)
```

Bases: `DelayedUnaryOperation`

A generic NDArray.

**property shape**

Returns: None | Tuple[int | None, ...]

```
class kwcoco.util.delayed_ops.DelayedAsXarray(subdata=None, dsize=None, channels=None)
```

Bases: *DelayedImage*

Casts the data to an xarray object in the finalize step

**Example:**

```
>>> # xdoctest: +REQUIRES(module:xarray)
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> # without channels
>>> base = DelayedLoad.demo(dsize=(16, 16)).prepare()
>>> self = base.as_xarray()
>>> final = self._validate().finalize()
>>> assert len(final.coords) == 0
>>> assert final.dims == ('y', 'x', 'c')
>>> # with channels
>>> base = DelayedLoad.demo(dsize=(16, 16), channels='r|g|b').prepare()
>>> self = base.as_xarray()
>>> final = self._validate().finalize()
>>> assert final.coords.indexes['c'].tolist() == ['r', 'g', 'b']
>>> assert final.dims == ('y', 'x', 'c')
```

**optimize()**

**Returns**

*DelayedImage*

```
class kwcoco.util.delayed_ops.DelayedChannelConcat(parts, dsize=None)
```

Bases: *ImageOpsMixin*, *DelayedConcat*

Stacks multiple arrays together.

**Example**

```
>>> from delayed_image import * # NOQA
>>> from delayed_image.delayed_leafs import DelayedLoad
>>> dsize = (307, 311)
>>> c1 = DelayedNans(dsize=dsize, channels='foo')
>>> c2 = DelayedLoad.demo('astro', dsize=dsize, channels='R|G|B').prepare()
>>> cat = DelayedChannelConcat([c1, c2])
>>> warped_cat = cat.warp({'scale': 1.07}, dsize=(328, 332))
>>> warped_cat._validate()
>>> warped_cat.finalize()
```

## Example

```
>>> # Test case that failed in initial implementation
>>> # Due to incorrectly pushing channel selection under the concat
>>> from delayed_image import * # NOQA
>>> import kwimage
>>> fpath = kwimage.grab_test_image_fpath()
>>> base1 = DelayedLoad(fpath, channels='r|g|b').prepare()
>>> base2 = DelayedLoad(fpath, channels='x|y|z').prepare().scale(2)
>>> base3 = DelayedLoad(fpath, channels='i|j|k').prepare().scale(2)
>>> bands = [base2, base1[:, :, 0].scale(2).evaluate(),
>>>           base1[:, :, 1].evaluate().scale(2),
>>>           base1[:, :, 2].evaluate().scale(2), base3]
>>> delayed = DelayedChannelConcat(bands)
>>> delayed = delayed.warp({'scale': 2})
>>> delayed = delayed[0:100, 0:55, [0, 2, 4]]
>>> delayed.write_network_text()
>>> delayed.optimize()
```

### **property channels**

Returns: None | FusedChannelSpec

### **property shape**

Returns: Tuple[int | None, int | None, int | None]

### **optimize()**

#### **Returns**

DelayedImage

### **take\_channels(channels)**

This method returns a subset of the vision data with only the specified bands / channels.

#### **Parameters**

**channels** (*List[int] | slice | channel\_spec.FusedChannelSpec*) – List of integers indexes, a slice, or a channel spec, which is typically a pipe (|) delimited list of channel codes. See ChannelSpec for more details.

#### **Returns**

a delayed vision operation that only operates on the following channels.

#### **Return type**

DelayedArray

## Example

```
>>> # xdoctest: +REQUIRES(module:kwcoco)
>>> from delayed_image.delayed_nodes import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> self = delayed = dset.coco_image(1).delay()
>>> channels = 'B11|B8|B1|B10'
>>> new = self.take_channels(channels)
```

## Example

```
>>> # xdoctest: +REQUIRES(module:kwcoco)
>>> # Complex case
>>> import kwcoco
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image.delayed_leafs import DelayedLoad
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> delayed = dset.coco_image(1).delay()
>>> astro = DelayedLoad.demo('astro', channels='r|g|b').prepare()
>>> aligned = astro.warp(kwimage.Affine.scale(600 / 512), dszie='auto')
>>> self = combo = DelayedChannelConcat(delayed.parts + [aligned])
>>> channels = 'B1|r|B8|g'
>>> new = self.take_channels(channels)
>>> new_cropped = new.crop((slice(10, 200), slice(12, 350)))
>>> new_opt = new_cropped.optimize()
>>> datas = new_opt.finalize()
>>> if 1:
>>>     new_cropped.write_network_text(with_labels='name')
>>>     new_opt.write_network_text(with_labels='name')
>>> vizable = kwimage.normalize_intensity(datas, axis=2)
>>> self._validate()
>>> new._validate()
>>> new_cropped._validate()
>>> new_opt._validate()
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> stacked = kwimage.stack_images(vizable.transpose(2, 0, 1))
>>> kwplot.imshow(stacked)
```



## Example

```
>>> # xdoctest: +REQUIRES(module:kwcoco)
>>> # Test case where requested channel does not exist
>>> import kwcoco
>>> from delayed_image.delayed_nodes import * # NOQA
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral', use_cache=1, verbose=100)
>>> self = delayed = dset.coco_image(1).delay()
>>> channels = 'B1|foobar|bazbiz|B8'
>>> new = self.take_channels(channels)
>>> new_cropped = new.crop((slice(10, 200), slice(12, 350)))
>>> fused = new_cropped.finalize()
>>> assert fused.shape == (190, 338, 4)
>>> assert np.all(np.isnan(fused[..., 1:3]))
>>> assert not np.any(np.isnan(fused[..., 0]))
>>> assert not np.any(np.isnan(fused[..., 3]))
```

### property num\_overviews

Returns: int

### as\_xarray()

#### Returns

DelayedAsXarray

**undo\_warps**(*remove=None*, *retain=None*, *squash\_nans=False*, *return\_warps=False*)

Attempts to “undo” warping for each concatenated channel and returns a list of delayed operations that are cropped to the right regions.

Typically you will retrain offset, theta, and shear to remove scale. This ensures the data is spatially aligned up to a scale factor.

**Parameters**

- **remove** (*List[str]*) – if specified, list components of the warping to remove. Can include: “offset”, “scale”, “shearx”, “theta”. Typically set this to [“scale”].
- **retain** (*List[str]*) – if specified, list components of the warping to retain. Can include: “offset”, “scale”, “shearx”, “theta”. Mutually exclusive with “remove”. If neither remove or retain is specified, retain is set to [].
- **squash\_nans** (*bool*) – if True, pure nan channels are squashed into a 1x1 array as they do not correspond to a real source.
- **return\_warps** (*bool*) – if True, return the transforms we applied. I.e. the transform from the `self` to the returned `parts`. This is useful when you need to warp objects in the original space into the jagged space.

**Returns**

The `List[DelayedImage]` are the `parts` i.e. the new images with the warping undone. The `List[Affine]`: is the transforms from `self` to each item in `parts`

**Return type**

`List[DelayedImage]` | `Tuple[List[DelayedImage]]` | `List[Affine]`

**Example**

```
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image.delayed_leafs import DelayedLoad
>>> from delayed_image.delayed_leafs import DelayedNans
>>> import ubelt as ub
>>> import kwimage
>>> import kwarray
>>> import numpy as np
>>> # Demo case where we have different channels at different resolutions
>>> base = DelayedLoad.demo(channels='r|g|b').prepare().dequantize({'quant_max': 255})
>>> bandR = base[:, :, 0].scale(100 / 512)[:, :-50].evaluate()
>>> bandG = base[:, :, 1].scale(300 / 512).warp({'theta': np.pi / 8, 'about': (150, 150)}).evaluate()
>>> bandB = base[:, :, 2].scale(600 / 512)[:150, :].evaluate()
>>> bandN = DelayedNans((600, 600), channels='N')
>>> # Make a concatenation of images of different underlying native resolutions
>>> delayed_vidspace = DelayedChannelConcat([
>>>     bandR.scale(6, dsize=(600, 600)).optimize(),
>>>     bandG.warp({'theta': -np.pi / 8, 'about': (150, 150)}).scale(2, dsize=(600, 600)).optimize(),
>>>     bandB.scale(1, dsize=(600, 600)).optimize(),
>>>     bandN,
>>> ]).warp({'scale': 0.7}).optimize()
>>> vidspace_box = kwimage.Boxes([[100, 10, 270, 160]], 'ltrb')
```


(continues on next page)

(continued from previous page)

```

>>> vidspace_poly = vidspace_box.to_polygons()[0]
>>> vidspace_slice = vidspace_box.to_slices()[0]
>>> self = delayed_vidspace[vidspace_slice].optimize()
>>> print('--- Aligned --- ')
>>> self.write_network_text()
>>> squash_nans = True
>>> undone_all_parts, tfs1 = self.undo_warp(squash_nans=squash_nans, return_
>>> ~warps=True)
>>> undone_scale_parts, tfs2 = self.undo_warp(remove=['scale'], squash_
>>> _nans=squash_nans, return_warp=True)
>>> stackable_aligned = self.finalize().transpose(2, 0, 1)
>>> stackable undone_all = []
>>> stackable undone_scale = []
>>> print('--- Undone All --- ')
>>> for undone in undone_all_parts:
...     undone.write_network_text()
...     stackable undone_all.append(undone.finalize())
>>> print('--- Undone Scale --- ')
>>> for undone in undone_scale_parts:
...     undone.write_network_text()
...     stackable undone_scale.append(undone.finalize())
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> canvas0 = kwimage.stack_images(stackable_aligned, axis=1)
>>> canvas1 = kwimage.stack_images(stackable undone_all, axis=1)
>>> canvas2 = kwimage.stack_images(stackable undone_scale, axis=1)
>>> canvas0 = kwimage.draw_header_text(canvas0, 'Rescaled Aligned Channels')
>>> canvas1 = kwimage.draw_header_text(canvas1, 'Unwarped Channels')
>>> canvas2 = kwimage.draw_header_text(canvas2, 'Unscaled Channels')
>>> canvas = kwimage.stack_images([canvas0, canvas1, canvas2], axis=0)
>>> canvas = kwimage.fill_nans_with_checkers(canvas)
>>> kwplot.imshow(canvas)

```



```
class kwcoco.util.delayed_ops.DelayedConcat(parts, axis)
```

Bases: *DelayedNaryOperation*

Stacks multiple arrays together.

**property shape**

Returns: None | Tuple[int | None, ...]

```
class kwcoco.util.delayed_ops.DelayedCrop(subdata, space_slice=None, chan_idxs=None)
```

Bases: *DelayedImage*

Crops an image along integer pixel coordinates.

## Example

```
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> base = DelayedLoad.demo(dsize=(16, 16)).prepare()
>>> # Test Fuse Crops Space Only
>>> crop1 = base[4:12, 0:16]
>>> self = crop1[2:6, 0:8]
>>> opt = self._opt_fuse_crops()
>>> self.write_network_text()
>>> opt.write_network_text()
>>> #
>>> # Test Channel Select Via Index
```

(continues on next page)

(continued from previous page)

```
>>> self = base[:, :, [0]]
>>> self.write_network_text()
>>> final = self._finalize()
>>> assert final.shape == (16, 16, 1)
>>> assert base[:, :, [0, 1]].finalize().shape == (16, 16, 2)
>>> assert base[:, :, [2, 0, 1]].finalize().shape == (16, 16, 3)
```

## Example

```
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> base = DelayedLoad.demo(dsize=(16, 16)).prepare()
>>> # Test Discontiguous Channel Select Via Index
>>> self = base[:, :, [0, 2]]
>>> self.write_network_text()
>>> final = self._finalize()
>>> assert final.shape == (16, 16, 2)
```

**optimize()****Returns**

DelayedImage

## Example

```
>>> # Test optimize nans
>>> from delayed_image import DelayedNans
>>> import kwimage
>>> base = DelayedNans(dsize=(100, 100), channels='a|b|c')
>>> self = base[0:10, 0:5]
>>> # Should simply return a new nan generator
>>> new = self.optimize()
>>> self.write_network_text()
>>> new.write_network_text()
>>> assert len(new.as_graph().nodes) == 1
```

**class kwcoco.util.delayed\_ops.DelayedDequantize(subdata, quantization)**Bases: *DelayedImage*

Rescales image intensities from int to floats.

The output is usually between 0 and 1. This also handles transforming nodata into nan values.

**optimize()****Returns**

DelayedImage

## Example

```
>>> # Test a case that caused an error in development
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> fpath = kwimage.grab_test_image_fpath()
>>> base = DelayedLoad(fpath, channels='r|g|b').prepare()
>>> quantization = {'quant_max': 255, 'nodata': 0}
>>> self = base.get_overview(1).dequantize(quantization)
>>> self.write_network_text()
>>> opt = self.optimize()
```

**class** kwcoco.util.delayed\_ops.DelayedFrameStack(*parts*)

Bases: *DelayedStack*

Stacks multiple arrays together.

**class** kwcoco.util.delayed\_ops.DelayedIdentity(*data*, *channels=None*, *dsize=None*)

Bases: *DelayedImageLeaf*

Returns an ndarray as-is

## Example

```
self = DelayedNans((10, 10), channel_spec.FusedChannelSpec.coerce('rgb')) region_slices = (slice(5, 10),
slice(1, 12)) delayed = self.crop(region_slices)
```

## Example

```
>>> from delayed_image import * # NOQA
>>> arr = kwimage.checkerboard()
>>> self = DelayedIdentity(arr, channels='gray')
>>> warp = self.warp({'scale': 1.07})
>>> warp.optimize().finalize()
```

**class** kwcoco.util.delayed\_ops.DelayedImage(*subdata=None*, *dsize=None*, *channels=None*)

Bases: *ImageOpsMixin*, *DelayedArray*

For the case where an array represents a 2D image with multiple channels

**property** *shape*

Returns: None | Tuple[int | None, int | None, int | None]

**property** *num\_channels*

Returns: None | int

**property** *dsize*

Returns: None | Tuple[int | None, int | None]

**property** *channels*

Returns: None | FusedChannelSpec

**property** *num\_overviews*

Returns: int

**take\_channels(channels)**

This method returns a subset of the vision data with only the specified bands / channels.

**Parameters**

**channels** (*List[int] | slice | channel\_spec.FusedChannelSpec*) – List of integers indexes, a slice, or a channel spec, which is typically a pipe (|) delimited list of channel codes. See ChannelSpec for more details.

**Returns**

a new delayed load with a fused take channel operation

**Return type**

*DelayedCrop*

---

**Note:** The channel subset must exist here or it will raise an error. A better implementation (via symbolic) might be able to do better

---

**Example**

```
>>> #
>>> # Test Channel Select Via Code
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> self = DelayedLoad.demo(dsize=(16, 16), channels='r|g|b').prepare()
>>> channels = 'r|b'
>>> new = self.take_channels(channels).validate()
>>> new2 = new[:, :, [1, 0]].validate()
>>> new3 = new2[:, :, [1]].validate()
```

**Example**

```
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> self = DelayedLoad.demo('astro').prepare()
>>> channels = [2, 0]
>>> new = self.take_channels(channels)
>>> new3 = new.take_channels([1, 0])
>>> new._validate()
>>> new3._validate()
```

```
>>> final1 = self.finalize()
>>> final2 = new.finalize()
>>> final3 = new3.finalize()
>>> assert np.all(final1[..., 2] == final2[..., 0])
>>> assert np.all(final1[..., 0] == final2[..., 1])
>>> assert final2.shape[2] == 2
```

```
>>> assert np.all(final1[..., 2] == final3[..., 1])
>>> assert np.all(final1[..., 0] == final3[..., 0])
>>> assert final3.shape[2] == 2
```

## Example

```
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> self = DelayedLoad.demo(dsize=(16, 16), channels='r|g|b').prepare()
>>> # Case where a channel doesn't exist
>>> channels = 'r|b|magic'
>>> new = self.take_channels(channels)
>>> assert len(new.parts) == 2
>>> new._validate()
```

### get\_transform\_from\_leaf()

Returns the transformation that would align data with the leaf

### evaluate()

Evaluate this node and return the data as an identity.

#### Returns

DelayedIdentity

### undo\_warp(remove=None, retain=None, squash\_nans=False, return\_warp=False)

Attempts to “undo” warping for each concatenated channel and returns a list of delayed operations that are cropped to the right regions.

Typically you will retrain offset, theta, and shear to remove scale. This ensures the data is spatially aligned up to a scale factor.

#### Parameters

- **remove** (*List[str]*) – if specified, list components of the warping to remove. Can include: “offset”, “scale”, “shearx”, “theta”. Typically set this to [“scale”].
- **retain** (*List[str]*) – if specified, list components of the warping to retain. Can include: “offset”, “scale”, “shearx”, “theta”. Mutually exclusive with “remove”. If neither remove or retain is specified, retain is set to [].
- **squash\_nans** (*bool*) – if True, pure nan channels are squashed into a 1x1 array as they do not correspond to a real source.
- **return\_warp** (*bool*) – if True, return the transform we applied. This is useful when you need to warp objects in the original space into the jagged space.

#### SeeAlso:

DelayedChannelConcat.undo\_warps

## Example

```
>>> # Test similar to undo_warps, but on each channel separately
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image.delayed_leafs import DelayedLoad
>>> from delayed_image.delayed_leafs import DelayedNans
>>> import ubelt as ub
>>> import kwimage
>>> import kwarray
>>> import numpy as np
>>> # Demo case where we have different channels at different resolutions
```

(continues on next page)

(continued from previous page)

```

>>> base = DelayedLoad.demo(channels='r|g|b').prepare().dequantize({'quant_max': 255})
>>> bandR = base[:, :, 0].scale(100 / 512)[:, :-50].evaluate()
>>> bandG = base[:, :, 1].scale(300 / 512).warp({'theta': np.pi / 8, 'about': (150, 150)}).evaluate()
>>> bandB = base[:, :, 2].scale(600 / 512)[:150, :].evaluate()
>>> bandN = DelayedNans((600, 600), channels='N')
>>> B0 = bandR.scale(6, dsize=(600, 600)).optimize()
>>> B1 = bandG.warp({'theta': -np.pi / 8, 'about': (150, 150)}).scale(2, dsize=(600, 600)).optimize()
>>> B2 = bandB.scale(1, dsize=(600, 600)).optimize()
>>> vidspace_box = kwimage.Boxes([-10, -10, 270, 160], 'ltrb').scale(1 / .7).quantize()
>>> vidspace_poly = vidspace_box.to_polygons()[0]
>>> vidspace_slice = vidspace_box.to_slices()[0]
>>> # Test with the padded crop
>>> self0 = B0.crop(vidspace_slice, wrap=0, clip=0, pad=10).optimize()
>>> self1 = B1.crop(vidspace_slice, wrap=0, clip=0, pad=10).optimize()
>>> self2 = B2.crop(vidspace_slice, wrap=0, clip=0, pad=10).optimize()
>>> parts = [self0, self1, self2]
>>> # Run the undo on each channel
>>> undone_scale_parts = [d.undo_warp(remove=['scale']) for d in parts]
>>> print('--- Aligned --- ')
>>> stackable_aligned = []
>>> for d in parts:
>>>     d.write_network_text()
>>>     stackable_aligned.append(d.finalize())
>>> print('--- Undone Scale --- ')
>>> stackable undone_scale = []
>>> for undone in undone_scale_parts:
>>>     undone.write_network_text()
>>>     stackable undone_scale.append(undone.finalize())
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> canvas0 = kwimage.stack_images(stackable_aligned, axis=1, pad=5, bg_value='kw_darkgray')
>>> canvas2 = kwimage.stack_images(stackable undone_scale, axis=1, pad=5, bg_value='kw_darkgray')
>>> canvas0 = kwimage.draw_header_text(canvas0, 'Rescaled Channels')
>>> canvas2 = kwimage.draw_header_text(canvas2, 'Native Scale Channels')
>>> canvas = kwimage.stack_images([canvas0, canvas2], axis=0, bg_value='kw_darkgray')
>>> canvas = kwimage.fill_nans_with_checkers(canvas)
>>> kwplot.imshow(canvas)

```



```
class kwcoco.util.delayed_ops.DelayedImageLeaf(subdata=None, dsize=None, channels=None)
```

Bases: *DelayedImage*

**get\_transform\_from\_leaf()**

Returns the transformation that would align data with the leaf

**Returns**

kwimage.Affine

**optimize()**

```
class kwcoco.util.delayed_ops.DelayedLoad(fpath, channels=None, dsize=None, nodata_method=None)
```

Bases: *DelayedImageLeaf*

Points to an image on disk to be loaded.

This is the starting point for most delayed operations. Disk IO is avoided until the `finalize` operation is called. Calling `prepare` can read image headers if metadata like the image width, height, and number of channels is not provided, but most operations can be performed while these are still unknown.

If a gdal backend is available, and the underlying image is in the appropriate formate (e.g. COG), `finalize` will return a lazy reference that enables fast overviews and crops. For image formats that do not allow for tiling / overviews, then there is no way to avoid reading entire image as an ndarray.

**Example**

```
>>> from delayed_image import * # NOQA
>>> self = DelayedLoad.demo(dsize=(16, 16)).prepare()
>>> data1 = self.finalize()
```

**Example**

```
>>> # xdoctest: +REQUIRES(module:osgeo)
>>> # Demo code to develop support for overviews
>>> from delayed_image import * # NOQA
>>> import kwimage
>>> import ubelt as ub
>>> fpath = kwimage.grab_test_image_fpath(overviews=3)
>>> self = DelayedLoad(fpath, channels='r|g|b').prepare()
>>> print(f'self={self}')
>>> print('self.meta = {}'.format(ub.repr2(self.meta, nl=1)))
>>> quantization = {
>>>     'quant_max': 255,
>>>     'nodata': 0,
>>> }
>>> node0 = self
>>> node1 = node0.get_overview(2)
>>> node2 = node1[13:900, 11:700]
>>> node3 = node2.dequantize(quantization)
>>> node4 = node3.warp({'scale': 0.05})
>>> #
>>> data0 = node0._validate().finalize()
>>> data1 = node1._validate().finalize()
>>> data2 = node2._validate().finalize()
>>> data3 = node3._validate().finalize()
>>> data4 = node4._validate().finalize()
>>> node4.write_network_text()
```


**Example**

```
>>> # xdoctest: +REQUIRES(module:osgeo)
>>> # Test delayed ops with int16 and nodata values
>>> from delayed_image import * # NOQA
>>> import kwimage
>>> from delayed_image.helpers import quantize_float01
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('delayed_image/tests/test_delay_nodata').ensuredir()
>>> fpath = dpath / 'data.tif'
>>> data = kwimage.ensure_float01(kwimage.grab_test_image())
>>> poly = kwimage.Polygon(rng=321032).scale(data.shape[0])
>>> poly.fill(data, np.nan)
>>> data_uint16, quantization = quantize_float01(data)
>>> nodata = quantization['nodata']
>>> kwimage.imwrite(fpath, data_uint16, nodata=nodata, backend='gdal', overviews=3)
```

(continues on next page)

(continued from previous page)

```
>>> # Test loading the data
>>> self = DelayedLoad(fpPath, channels='r|g|b', nodata_method='float').prepare()
>>> node0 = self
>>> node1 = node0.dequantize(quantization)
>>> node2 = node1.warp({'scale': 0.51}, interpolation='lanczos')
>>> node3 = node2[13:900, 11:700]
>>> node4 = node3.warp({'scale': 0.9}, interpolation='lanczos')
>>> node4.write_network_text()
>>> node5 = node4.optimize()
>>> node5.write_network_text()
>>> node6 = node5.warp({'scale': 8}, interpolation='lanczos').optimize()
>>> node6.write_network_text()
>>> #
>>> data0 = node0._validate().finalize()
>>> data1 = node1._validate().finalize()
>>> data2 = node2._validate().finalize()
>>> data3 = node3._validate().finalize()
>>> data4 = node4._validate().finalize()
>>> data5 = node5._validate().finalize()
>>> data6 = node6._validate().finalize()
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> stack1 = kwimage.stack_images([data1, data2, data3, data4, data5])
>>> stack2 = kwimage.stack_images([stack1, data6], axis=1)
>>> kwplot.imshow(stack2)
```

**property fpath**

**classmethod demo**(key='astro', channels=None, dsize=None, nodata\_method=None, overviews=None)

Creates a demo DelayedLoad node that points to a file generated by `kwimage.grab_test_image_fpath()`.

If metadata like dsize and channels are not provided, then the `prepare()` can be used to auto-populate them at the cost of the disk IO to read image headers.

**Parameters**

- **key** (*str*) – which test image to grab. Valid choices are: astro - an astronaut carl - Carl Sagan paraview - ParaView logo stars - picture of stars in the sky
- **channels** (*str*) – if specified, these channels will be stored in the delayed load metadata. Note: these are not auto-populated. Usually the key corresponds to 3-channel data,
- **dsize** (*None* | *Tuple[int, int]*) – if specified, we will return a variant of the data with the specific dsize
- **nodata\_method** (*str* | *None*) – How to handle nodata values in the file itself. Can be “auto”, “float”, or “ma”.
- **overviews** (*None* | *int*) – if specified, will return a variant of the data with overviews

**Returns**

DelayedLoad

## Example

```
>>> from delayed_image.delayed_leafs import * # NOQA
>>> import delayed_image
>>> delayed = delayed_image.DelayedLoad.demo()
>>> print(f'delayed={delayed}')
>>> delayed.prepare()
>>> print(f'delayed={delayed}')
>>> delayed = DelayedLoad.demo(channels='r|g|b', nodata_method='float')
>>> print(f'delayed={delayed}')
>>> delayed.prepare()
>>> print(f'delayed={delayed}')
>>> delayed.finalize()
```

### prepare()

If metadata is missing, perform minimal IO operations in order to prepopulate metadata that could help us better optimize the operation tree.

#### Returns

DelayedLoad

**class** kwcoco.util.delayed\_ops.DelayedNans(*dsize=None, channels=None*)

Bases: *DelayedImageLeaf*

Constructs nan channels as needed

## Example

```
self = DelayedNans((10, 10), channel_spec.FusedChannelSpec.coerce('rgb')) region_slices = (slice(5, 10), slice(1, 12)) delayed = self.crop(region_slices)
```

## Example

```
>>> from delayed_image import * # NOQA
>>> dsize = (307, 311)
>>> c1 = DelayedNans(dsize=dsize, channels='foo')
>>> c2 = DelayedLoad.demo('astro', dsize=dsize, channels='R|G|B').prepare()
>>> cat = DelayedChannelConcat([c1, c2])
>>> warped_cat = cat.warp({'scale': 1.07}, dsize=(328, 332))._validate()
>>> warped_cat._validate().optimize().finalize()
```

**class** kwcoco.util.delayed\_ops.DelayedNaryOperation(*parts*)

Bases: *DelayedOperation*

For operations that have multiple input arrays

### children()

#### Yields

*Any*

**class** kwcoco.util.delayed\_ops.DelayedOperation

Bases: *NiceRepr*

**nesting()****Returns**

Dict[str, dict]

**as\_graph(fields='auto')**

Builds the underlying graph structure as a networkx graph with human readable labels.

**Parameters****fields (str | List[str])** – Add the specified fields as labels. If ‘auto’ then does something “reasonable”. If ‘all’ then shows everything. TODO: only implemented for “auto” and “all”, implement general field selection (PR Wanted).**Returns**

networkx.DiGraph

**print\_graph(fields='auto', with\_labels=True, rich='auto')**

Alias for write\_network\_text

**write\_network\_text(fields='auto', with\_labels=True, rich='auto')****property shape**

Returns: None | Tuple[int | None, ...]

**children()****Yields**

Any

**prepare()**

If metadata is missing, perform minimal IO operations in order to prepopulate metadata that could help us better optimize the operation tree.

**Returns**

DelayedOperation2

**finalize(prepare=True, optimize=True, \*\*kwargs)**

Evaluate the operation tree in full.

**Parameters**

- **prepare (bool)** – ensure prepare is called to ensure metadata exists if possible before optimizing. Defaults to True.
- **optimize (bool)** – ensure the graph is optimized before loading. Default to True.
- **\*\*kwargs** – for backwards compatibility, these will allow for in-place modification of select nested parameters.

**Returns**

ArrayLike

## Notes

Do not overload this method. Overload `DelayedOperation2._finalize()` instead.

### `optimize()`

#### Returns

`DelayedOperation2`

```
class kwcoco.util.delayed_ops.DelayedOverview(subdata, overview)
```

Bases: `DelayedImage`

Downsamples an image by a factor of two.

If the underlying image being loaded has precomputed overviews it simply loads these instead of downsampling the original image, which is more efficient.

## Example

```
>>> # xdoctest: +REQUIRES(module:osgeo)
>>> # Make a complex chain of operations and optimize it
>>> from delayed_image import * # NOQA
>>> import kwimage
>>> fpath = kwimage.grab_test_image_fpath(overviews=3)
>>> dimg = DelayedLoad(fpath, channels='r|g|b').prepare()
>>> dimg = dimg.get_overview(1)
>>> dimg = dimg.get_overview(1)
>>> dimg = dimg.get_overview(1)
>>> dopt = dimg.optimize()
>>> if 1:
>>>     import networkx as nx
>>>     dimg.write_network_text()
>>>     dopt.write_network_text()
>>>     print(ub.repr2(dopt.nesting(), nl=-1, sort=0))
>>> final0 = dimg._finalize()[:]
>>> final1 = dopt._finalize()[:]
>>> assert final0.shape == final1.shape
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autompl()
>>> kwplot.imshow(final0, pnum=(1, 2, 1), fnum=1, title='raw')
>>> kwplot.imshow(final1, pnum=(1, 2, 2), fnum=1, title='optimized')
```



**property num\_overviews**

Returns: int

**optimize()**

**Returns**

DelayedImage

**class kwcoco.util.delayed\_ops.DelayedStack(parts, axis)**

Bases: *DelayedNaryOperation*

Stacks multiple arrays together.

**property shape**

Returns: None | Tuple[int | None, ...]

**class kwcoco.util.delayed\_ops.DelayedUnaryOperation(subdata)**

Bases: *DelayedOperation*

For operations that have a single input array

**children()**

**Yields**

Any

**class kwcoco.util.delayed\_ops.DelayedWarp(subdata, transform, dszie='auto', antialias=True, interpolation='linear', border\_value='auto', noop\_eps=0)**

Bases: *DelayedImage*

Applies an affine transform to an image.

### Example

```
>>> from delayed_image.delayed_nodes import * # NOQA
>>> from delayed_image import DelayedLoad
>>> self = DelayedLoad.demo(dsize=(16, 16)).prepare()
>>> warp1 = self.warp({'scale': 3})
>>> warp2 = warp1.warp({'theta': 0.1})
>>> warp3 = warp2._opt_fuse_warps()
>>> warp3._validate()
>>> print(ub.repr2(warp2.nesting(), nl=-1, sort=0))
>>> print(ub.repr2(warp3.nesting(), nl=-1, sort=0))
```

#### property transform

Returns: kwimage.Affine

#### optimize()

##### Returns

DelayedImage

### Example

```
>>> # Demo optimization that removes a noop warp
>>> from delayed_image import DelayedLoad
>>> import kwimage
>>> base = DelayedLoad.demo(channels='r|g|b').prepare()
>>> self = base.warp(kwimage.Affine.eye())
>>> new = self.optimize()
>>> assert len(self.as_graph().nodes) == 2
>>> assert len(new.as_graph().nodes) == 1
```

### Example

```
>>> # Test optimize nans
>>> from delayed_image import DelayedNans
>>> import kwimage
>>> base = DelayedNans(dsize=(100, 100), channels='a|b|c')
>>> self = base.warp(kwimage.Affine.scale(0.1))
>>> # Should simply return a new nan generator
>>> new = self.optimize()
>>> assert len(new.as_graph().nodes) == 1
```

## Example

```
>>> # Test optimize nans
>>> from delayed_image import DelayedLoad
>>> import kwimage
>>> base = DelayedLoad.demo(channels='r|g|b').prepare()
>>> transform = kwimage.Affine.scale(1.0 + 1e-7)
>>> self = base.warp(transform, dsize=base.dsize)
>>> # An optimize will not remove a warp if there is any
>>> # doubt if it is the identity.
>>> new = self.optimize()
>>> assert len(self.as_graph().nodes) == 2
>>> assert len(new.as_graph().nodes) == 2
>>> # But we can specify a threshold where it will
>>> self._set_nested_params(noop_eps=1e-6)
>>> new = self.optimize()
>>> assert len(self.as_graph().nodes) == 2
>>> assert len(new.as_graph().nodes) == 1
```

**class** kwcoco.util.delayed\_ops.ImageOpsMixin  
Bases: `object`

**crop**(`space_slice=None, chan_idxs=None, clip=True, wrap=True, pad=0`)  
Crops an image along integer pixel coordinates.

### Parameters

- `space_slice` (`Tuple[slice, slice]`) – y-slice and x-slice.
- `chan_idxs` (`List[int]`) – indexes of bands to take
- `clip` (`bool`) – if True, the slice is interpreted normally, where it won't go past the image extent, otherwise slicing into negative regions or past the image bounds will result in padding. Defaults to True.
- `wrap` (`bool`) – if True, negative indexes “wrap around”, otherwise they are treated as is. Defaults to True.
- `pad` (`int | List[Tuple[int, int]]`) – if specified, applies extra padding

### Returns

`DelayedImage`

## Example

```
>>> from delayed_image import DelayedLoad
>>> import kwimage
>>> self = DelayedLoad.demo().prepare()
>>> self = self.dequantize({'quant_max': 255})
>>> self = self.warp({'scale': 1 / 2})
>>> pad = 0
>>> h, w = space_dims = self.dsize[::-1]
>>> grid = list(ub.named_product({
>>>     'left': [0, -64], 'right': [0, 64],
>>>     'top': [0, -64], 'bot': [0, 64],}))
```

(continues on next page)

(continued from previous page)

```
>>> grid += [
>>>     {'left': 64, 'right': -64, 'top': 0, 'bot': 0},
>>>     {'left': 64, 'right': 64, 'top': 0, 'bot': 0},
>>>     {'left': 0, 'right': 0, 'top': 64, 'bot': -64},
>>>     {'left': 64, 'right': -64, 'top': 64, 'bot': -64},
>>> ]
>>> crops = []
>>> for pads in grid:
>>>     space_slice = (slice(pads['top'], h + pads['bot']),
>>>                     slice(pads['left'], w + pads['right']))
>>>     delayed = self.crop(space_slice)
>>>     crop = delayed.finalize()
>>>     yyxx = kwimage.Boxes.from_slice(space_slice, wrap=False, clip=0).
>>>         toformat('_yyxx').data[0]
>>>     title = '[{:}:{:}, {:}:{:}]'.format(*yyxx)
>>>     crop_canvas = kwimage.draw_header_text(crop, title, fit=True, bg_color=
>>>         'kw_darkgray')
>>>     crops.append(crop_canvas)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> canvas = kwimage.stack_images_grid(crops, pad=16, bg_value='kw_darkgreen')
>>> canvas = kwimage.fill_nans_with_checkers(canvas)
>>> kwplot.imshow(canvas, title='Normal Slicing: Cropped Images With_
>>> Wrap+Clipped Slices', doclf=1, fnum=1)
>>> kwplot.show_if_requested()
```

## Normal Slicing: Cropped Images With Wrap+Clipped Slices



### Example

```
>>> # Demo the case with pads / no-clips / no-wraps
>>> from delayed_image import DelayedLoad
>>> import kwimage
>>> self = DelayedLoad.demo().prepare()
>>> self = self.dequantize({'quant_max': 255})
>>> self = self.warp({'scale': 1 / 2})
>>> pad = [(64, 128), (32, 96)]
>>> pad = [(0, 20), (0, 0)]
>>> pad = 0
>>> pad = 8
>>> h, w = space_dims = self.dszie[::-1]
>>> grid = list(ub.named_product({
>>>     'left': [0, -64], 'right': [0, 64],
>>>     'top': [0, -64], 'bot': [0, 64],}))
>>> grid += [
>>>     {'left': 64, 'right': -64, 'top': 0, 'bot': 0},
>>>     {'left': 64, 'right': 64, 'top': 0, 'bot': 0},
>>>     {'left': 0, 'right': 0, 'top': 64, 'bot': -64},
>>>     {'left': 64, 'right': -64, 'top': 64, 'bot': -64},
>>> ]
>>> crops = []
>>> for pads in grid:
>>>     space_slice = (slice(pads['top']), h + pads['bot']),

```

(continues on next page)

(continued from previous page)

```

>>>         slice(pads['left'], w + pads['right']))
>>>     delayed = self._padded_crop(space_slice, pad=pad)
>>>     crop = delayed.finalize(optimize=1)
>>>     yyxx = kwimage.Boxes.from_slice(space_slice, wrap=False, clip=0).
>>>     toformat('_yyxx').data[0]
>>>     title = '[{}:{} , {}:{} ]'.format(*yyxx)
>>>     if pad:
>>>         title += f'{chr(10)} pad={pad}'
>>>     crop_canvas = kwimage.draw_header_text(crop, title, fit=True, bg_color=
>>>         'kw_darkgray')
>>>     crops.append(crop_canvas)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> canvas = kwimage.stack_images_grid(crops, pad=16, bg_value='kw_darkgreen',_
>>>         resize='smaller')
>>> canvas = kwimage.fill_nans_with_checkers(canvas)
>>> kwplot.imshow(canvas, title='Negative Slicing: Cropped Images With_
>>>         clip=False wrap=False', doclf=1, fnum=2)
>>> kwplot.show_if_requested()

```

Negative Slicing: Cropped Images With clip=False wrap=False

**warp**(*transform*, *dsize*='auto', \*\**warp\_kwargs*)Applies an affine transformation to the image. See [DelayedWarp](#).**Parameters**

- **transform** (*ndarray | dict | kwimage.Affine*) – a coercable affine matrix. See [kwimage.Affine](#) for details on what can be coerced.
- **dsize** (*Tuple[int, int] | str*) – The width / height of the output canvas. If ‘auto’, dsize is computed such that the positive coordinates of the warped image will fit in the new canvas. In this case, any pixel that maps to a negative coordinate will be clipped. This has the property that the input transformation is not modified.
- **antialias** (*bool*) – if True determines if the transform is downsampling and applies antialiasing via gaussian blur. Defaults to False
- **interpolation** (*str*) – interpolation code or cv2 integer. Interpolation codes are linear, nearest, cubic, lancsoz, and area. Defaults to “linear”.
- **border\_value** (*int | float | str*) – if auto will be nan for float and 0 for int.
- **noop\_eps** (*float*) – This is the tolerance for optimizing a warp away. If the transform has all of its decomposed parameters (i.e. scale, rotation, translation, shear) less than this value, the warp node can be optimized away. Defaults to 0.

**Returns**

DelayedImage

**scale**(*scale*, *dsize='auto'*, *\*\*warp\_kwargs*)

An alias for self.warp({“scale”: scale}, ...)

**resize**(*dsize*, *\*\*warp\_kwargs*)

Resize an image to a specific width/height by scaling it.

**dequantize**(*quantization*)

Rescales image intensities from int to floats.

**Parameters****quantization** (*Dict[str, Any]*) – see [delayed\\_image.helpers.dequantize\(\)](#)**Returns**

DelayedDequantize

**get\_overview**(*overview*)

Downsamples an image by a factor of two.

**Parameters****overview** (*int*) – the overview to use (assuming it exists)**Returns**

DelayedOverview

**as\_xarray**()**Returns**

DelayedAsXarray

**get\_transform\_from**(*src*)

Find a transform from a given node (src) to this node (self / dst).

Given two delayed images src and dst that share a common leaf, find the transform from src to dst.

**Parameters****src** (*DelayedOperation*) – the other view to get a transform to. This must share a leaf with self (which is the dst).**Returns**

The transform that warps the space of src to the space of self.

**Return type**

kwimage.Affine

**Example**

```
>>> from delayed_image import * # NOQA
>>> from delayed_image.delayed_leafs import DelayedLoad
>>> base = DelayedLoad.demo().prepare()
>>> src = base.scale(2)
>>> dst = src.warp({'scale': 4, 'offset': (3, 5)})
>>> transform = dst.get_transform_from(src)
>>> tf = transform.decompose()
>>> assert tf['scale'] == (4, 4)
>>> assert tf['offset'] == (3, 5)
```

**Example**

```
>>> from delayed_image import demo
>>> self = demo.non_aligned_leafs()
>>> leaf = list(self._leaf_paths())[0][0]
>>> tf1 = self.get_transform_from(leaf)
>>> tf2 = leaf.get_transform_from(self)
>>> np.allclose(np.linalg.inv(tf2), tf1)
```

## 2.1.1.6.2 Submodules

### 2.1.1.6.2.1 kwcoco.util.dict\_like module

**class kwcoco.util.dict\_like.DictLike**

Bases: `NiceRepr`

An inherited class must specify the `getitem`, `setitem`, and `keys` methods.

A class is dictionary like if it has:

`__iter__`, `__len__`, `__contains__`, `__getitem__`, `items`, `keys`, `values`, `get`,

and if it should be writable it should have: `__delitem__`, `__setitem__`, `update`,

And perhaps: `copy`,

`__iter__`, `__len__`, `__contains__`, `__getitem__`, `items`, `keys`, `values`, `get`,

and if it should be writable it should have: `__delitem__`, `__setitem__`, `update`,

And perhaps: `copy`,

**getitem(key)**

**Parameters**

`key (Any)` – a key

**Returns**

a value

**Return type**  
Any

**setitem**(*key*, *value*)

**Parameters**

- **key** (*Any*)
- **value** (*Any*)

**delitem**(*key*)

**Parameters**  
**key** (*Any*)

**keys**()

**Yields**  
*Any* – a key

**items**()

**Yields**  
*Tuple[Any, Any]* – a key value pair

**values**()

**Yields**  
*Any* – a value

**copy**()

**Return type**  
Dict

**to\_dict**()

**Return type**  
Dict

**asdict**()

**Return type**  
Dict

**update**(*other*)

**get**(*key*, *default=None*)

**Parameters**

- **key** (*Any*)
- **default** (*Any*)

**Return type**  
Any

**class** kwcoco.util.dict\_like.DictProxy

Bases: [DictLike](#)

Allows an object to proxy the behavior of a dict attribute

**keys**()

### 2.1.1.6.2.2 kwcoco.util.jsonschema\_elements module

Functional interface into defining jsonschema structures.

See mixin classes for details.

#### Example

```
>>> from kwcoco.util.jsonschema_elements import * # NOQA
>>> elem = SchemaElements()
>>> for base in SchemaElements.__bases__:
>>>     print('\n\n====\nbase = {!r}'.format(base))
>>>     attrs = [key for key in dir(base) if not key.startswith('_')]
>>>     for key in attrs:
>>>         value = getattr(elem, key)
>>>         print(' {} = {}'.format(key, value))
```

```
class kwcoco.util.jsonschema_elements.Element(base, options={}, _magic=None)
```

Bases: dict

A dictionary used to define an element of a JSON Schema.

The exact keys/values for the element will depend on the type of element being described. The *SchemaElements* defines exactly what these are for the core elements. (e.g. OBJECT, INTEGER, NULL, ARRAY, ANYOF)

#### Example

```
>>> from kwcoco.coco_schema import * # NOQA
>>> self = Element(base={'type': 'demo'}, options={'opt1': 'opt2'})
>>> new = self(opt1=3)
>>> print('self = {}'.format(ub.repr2(self, nl=1, sort=1)))
>>> print('new = {}'.format(ub.repr2(new, nl=1, sort=1)))
>>> print('new2 = {}'.format(ub.repr2(new(), nl=1, sort=1)))
>>> print('new3 = {}'.format(ub.repr2(new(title='myvar'), nl=1, sort=1)))
>>> print('new4 = {}'.format(ub.repr2(new(title='myvar')(examples=['']), nl=1, sort=1)))
>>> print('new5 = {}'.format(ub.repr2(new(badattr=True), nl=1, sort=1)))
self = {
    'type': 'demo',
}
new = {
    'opt1': 3,
    'type': 'demo',
}
new2 = {
    'opt1': 3,
    'type': 'demo',
}
new3 = {
    'opt1': 3,
    'title': 'myvar',
    'type': 'demo',
}
```

(continues on next page)

(continued from previous page)

```

}
new4 = {
    'examples': [''],
    'opt1': 3,
    'title': 'myvar',
    'type': 'demo',
}
new5 = {
    'opt1': 3,
    'type': 'demo',
}

```

**validate(*instance=NoParam*)**

If *instance* is given, validates that that dictionary conforms to this schema. Otherwise validates that this is a valid schema element.

**Parameters**

**instance** (*dict*) – a dictionary to validate

**class kwcoco.util.jsonschema\_elements.ScalarElements**

Bases: `object`

Single-valued elements

**property NULL**

[//json-schema.org/understanding-json-schema/reference/null.html](https://json-schema.org/understanding-json-schema/reference/null.html)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/null.html)

**property BOOLEAN**

[//json-schema.org/understanding-json-schema/reference/null.html](https://json-schema.org/understanding-json-schema/reference/null.html)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/null.html)

**property STRING**

[//json-schema.org/understanding-json-schema/reference/string.html](https://json-schema.org/understanding-json-schema/reference/string.html)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/string.html)

**property NUMBER**

[//json-schema.org/understanding-json-schema/reference/numeric.html#number](https://json-schema.org/understanding-json-schema/reference/numeric.html#number)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/numeric.html#number)

**property INTEGER**

[//json-schema.org/understanding-json-schema/reference/numeric.html#integer](https://json-schema.org/understanding-json-schema/reference/numeric.html#integer)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/numeric.html#integer)

**class kwcoco.util.jsonschema\_elements.QuantifierElements**

Bases: `object`

Quantifier types

<https://json-schema.org/understanding-json-schema/reference/combining.html#allof>

### Example

```
>>> from kwococo.util.jsonschema_elements import * # NOQA
>>> elem.ANYOF(elem.STRING, elem.NUMBER).validate()
>>> elem.ONEOF(elem.STRING, elem.NUMBER).validate()
>>> elem.NOT(elem.NULL).validate()
>>> elem.NOT(elem.ANY).validate()
>>> elem.ANY.validate()
```

**property ANY**

**ALLOF(\*TYPES)**

**ANYOF(\*TYPES)**

**ONEOF(\*TYPES)**

**NOT(TYPE)**

**class kwococo.util.jsonschema\_elements.ContainerElements**

Bases: `object`

Types that contain other types

### Example

```
>>> from kwococo.util.jsonschema_elements import * # NOQA
>>> print(elem.ARRAY().validate())
>>> print(elem.OBJECT().validate())
>>> print(elem.OBJECT().validate())
{'type': 'array', 'items': []}
{'type': 'object', 'properties': {}}
{'type': 'object', 'properties': {}}
```

**ARRAY(TYPE={}, \*\*kw)**

<https://json-schema.org/understanding-json-schema/reference/array.html>

### Example

```
>>> from kwococo.util.jsonschema_elements import * # NOQA
>>> ARRAY(numItems=3)
>>> schema = ARRAY(minItems=3)
>>> schema.validate()
{'type': 'array', 'items': [], 'minItems': 3}
```

**OBJECT(PROPERTIES={}, \*\*kw)**

<https://json-schema.org/understanding-json-schema/reference/object.html>

## Example

```
>>> import jsonschema
>>> schema = elem.OBJECT()
>>> jsonschema.validate({}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.ANY(),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'])
>>> jsonschema.validate({'key1': None}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.OBJECT({'arr': elem.ARRAY()}),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'], title='a title')
>>> schema.validate()
>>> print('schema = {}'.format(ub.repr2(schema, sort=1, nl=-1)))
>>> jsonschema.validate({'key1': {'arr': []}}, schema)
schema = {
    'properties': {
        'key1': {
            'properties': {
                'arr': {'items': {}, 'type': 'array'}
            },
            'type': 'object'
        },
        'key2': {}
    },
    'required': ['key1'],
    'title': 'a title',
    'type': 'object'
}
```

## class kwcoco.util.jsonschema\_elements.SchemaElements

Bases: *ScalarElements*, *QuantifierElements*, *ContainerElements*

Functional interface into defining jsonschema structures.

See mixin classes for details.

## References

<https://json-schema.org/understanding-json-schema/>

---

### Todo:

- [ ] Generics: title, description, default, examples
-

## CommandLine

```
xdoctest -m /home/joncrall/code/kwcoco/kwcoco/util/jsonschema_elements.py
↳ SchemaElements
```

## Example

```
>>> from kwcoco.util.jsonschema_elements import * # NOQA
>>> elem = SchemaElements()
>>> elem.ARRAY(elem.ANY())
>>> schema = OBJECT({
>>>     'prop1': ARRAY(INTEGER, minItems=3),
>>>     'prop2': ARRAY(STRING, numItems=2),
>>>     'prop3': ARRAY(OBJECT({
>>>         'subprob1': NUMBER,
>>>         'subprob2': NUMBER,
>>>     }))
>>> })
>>> print('schema = {}'.format(ub.repr2(schema, nl=2, sort=1)))
schema = {
    'properties': {
        'prop1': {'items': {'type': 'integer'}, 'minItems': 3, 'type': 'array'},
        'prop2': {'items': {'type': 'string'}, 'maxItems': 2, 'minItems': 2, 'type':
↳ ': 'array'},
        'prop3': {'items': {'properties': {'subprob1': {'type': 'number'}, 'subprob2':
↳ ': {'type': 'number'}}}, 'type': 'object'}, 'type': 'array'},
    },
    'type': 'object',
}
```

```
>>> TYPE = elem.OBJECT({
>>>     'p1': ANY,
>>>     'p2': ANY,
>>> }, required=['p1'])
>>> import jsonschema
>>> inst = {'p1': None}
>>> jsonschema.validate(inst, schema=TYPE)
>>> #jsonschema.validate({'p2': None}, schema=TYPE)
```

kwcoc.util.jsonschema\_elements.**ALLOF**(\*TYPES)

kwcoc.util.jsonschema\_elements.**ANYOF**(\*TYPES)

kwcoc.util.jsonschema\_elements.**ARRAY**(TYPE={}, \*\*kw)

<https://json-schema.org/understanding-json-schema/reference/array.html>

## Example

```
>>> from kwcoco.util.jsonschema_elements import * # NOQA
>>> ARRAY(numItems=3)
>>> schema = ARRAY(minItems=3)
>>> schema.validate()
{'type': 'array', 'items': {}, 'minItems': 3}
```

`kwcoco.util.jsonschema_elements.NOT(TYPE)`

`kwcoco.util.jsonschema_elements.OBJECT(PROPERTIES={}, **kw)`

<https://json-schema.org/understanding-json-schema/reference/object.html>

## Example

```
>>> import jsonschema
>>> schema = elem.OBJECT()
>>> jsonschema.validate({}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.ANY(),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'])
>>> jsonschema.validate({'key1': None}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.OBJECT({'arr': elem.ARRAY()}),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'], title='a title')
>>> schema.validate()
>>> print('schema = {}'.format(ub.repr2(schema, sort=1, nl=-1)))
>>> jsonschema.validate({'key1': {'arr': []}}, schema)
schema = {
    'properties': {
        'key1': {
            'properties': {
                'arr': {'items': {}, 'type': 'array'}
            },
            'type': 'object'
        },
        'key2': {}
    },
    'required': ['key1'],
    'title': 'a title',
    'type': 'object'
}
```

`kwcoco.util.jsonschema_elements.ONEOF(*TYPES)`

### 2.1.1.6.2.3 kwcoc.util.lazy\_frame\_backends module

Ported to delayed\_image

### 2.1.1.6.2.4 kwcoc.util.util\_archive module

`class kwcoc.util.util_archive.Archive(fpather=None, mode='r', backend=None, file=None)`

Bases: `object`

Abstraction over zipfile and tarfile

---

**Todo:** see if we can use one of these other tools instead

---

**SeeAlso:**

<https://github.com/RKrahl/archive-tools> <https://pypi.org/project/arlib/>

### Example

```
>>> from kwcoc.util.util_archive import Archive
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwcoc', 'tests', 'util', 'archive')
>>> dpath.delete().ensuredir()
>>> # Test write mode
>>> mode = 'w'
>>> arc_zip = Archive(str(dpath / 'demo.zip'), mode=mode)
>>> arc_tar = Archive(str(dpath / 'demo.tar.gz'), mode=mode)
>>> open(dpath / 'data_1only.txt', 'w').write('bazbzzz')
>>> open(dpath / 'data_2only.txt', 'w').write('buzzz')
>>> open(dpath / 'data_both.txt', 'w').write('foobar')
>>> #
>>> arc_zip.add(dpath / 'data_both.txt')
>>> arc_zip.add(dpath / 'data_1only.txt')
>>> #
>>> arc_tar.add(dpath / 'data_both.txt')
>>> arc_tar.add(dpath / 'data_2only.txt')
>>> #
>>> arc_zip.close()
>>> arc_tar.close()
>>> #
>>> # Test read mode
>>> arc_zip = Archive(str(dpath / 'demo.zip'), mode='r')
>>> arc_tar = Archive(str(dpath / 'demo.tar.gz'), mode='r')
>>> # Test names
>>> name = 'data_both.txt'
>>> assert name in arc_zip.names()
>>> assert name in arc_tar.names()
>>> # Test read
>>> assert arc_zip.read(name, mode='r') == 'foobar'
>>> assert arc_tar.read(name, mode='r') == 'foobar'
>>> #
```

(continues on next page)

(continued from previous page)

```
>>> # Test extractall
>>> extract_dpath = ub.ensuredir(str(dpath / 'extracted'))
>>> extracted1 = arc_zip.extractall(extract_dpath)
>>> extracted2 = arc_tar.extractall(extract_dpath)
>>> for fpath in extracted2:
>>>     print(open(fpath, 'r').read())
>>> for fpath in extracted1:
>>>     print(open(fpath, 'r').read())
```

**names()****read(name, mode='rb')**

Read data directly out of the archive.

**Parameters**

- **name (str)** – the name of the archive member to read
- **mode (str)** – This is a conceptual parameter that emulates the usual open mode. Defaults to “rb”, which returns data as raw bytes. If “r” will decode the bytes into utf8-text.

**classmethod coerce(data)**

Either open an archive file path or coerce an existing ZipFile or tarfile structure into this wrapper class

**add(fpath, arcname=None)****close()****extractall(output\_dpath='.', verbose=1, overwrite=True)****kwcoco.util.util\_archive.unarchive\_file(archive\_fpath, output\_dpath='.', verbose=1, overwrite=True)**

### 2.1.1.6.2.5 kwcoco.util.util\_futures module

Deprecated and functionality moved to ubelt

**class kwcoco.util.util\_futures.Executor(mode='thread', max\_workers=0)**

Bases: `object`

A concrete asynchronous executor with a configurable backend.

The type of parallelism (or lack thereof) is configured via the `mode` parameter, which can be: “process”, “thread”, or “serial”. This allows the user to easily enable / disable parallelism or switch between processes and threads without modifying the surrounding logic.

**SeeAlso:**

- `concurrent.futures.ThreadPoolExecutor`
- `concurrent.futures.ProcessPoolExecutor`
- `SerialExecutor`
- `JobPool`

## Example

```
>>> import ubelt as ub
>>> # Prototype code using simple serial processing
>>> executor = ub.Executor(mode='serial', max_workers=0)
>>> jobs = [executor.submit(sum, [i + 1, i]) for i in range(10)]
>>> print([job.result() for job in jobs])
[1, 3, 5, 7, 9, 11, 13, 15, 17, 19]
```

```
>>> # Enable parallelism by only changing one parameter
>>> executor = ub.Executor(mode='process', max_workers=0)
>>> jobs = [executor.submit(sum, [i + 1, i]) for i in range(10)]
>>> print([job.result() for job in jobs])
[1, 3, 5, 7, 9, 11, 13, 15, 17, 19]
```

**submit(func, \*args, \*\*kw)**

Calls the submit function of the underlying backend.

**Returns**

a future representing the job

**Return type**

concurrent.futures.Future

**shutdown()**

Calls the shutdown function of the underlying backend.

**map(fn, \*iterables, \*\*kwargs)**

Calls the map function of the underlying backend.

## CommandLine

```
xdoctest -m ubelt.util_futures Executor.map
```

## Example

```
>>> import ubelt as ub
>>> import concurrent.futures
>>> import string
>>> with ub.Executor(mode='serial') as executor:
...     result_iter = executor.map(int, string.digits)
...     results = list(result_iter)
>>> print('results = {!r}'.format(results))
results = [0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
>>> with ub.Executor(mode='thread', max_workers=2) as executor:
...     result_iter = executor.map(int, string.digits)
...     results = list(result_iter)
>>> # xdoctest: +IGNORE_WANT
>>> print('results = {!r}'.format(results))
results = [0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
```

---

```
class kwcocoo.util.util_futures.JobPool(mode='thread', max_workers=0, transient=False)
```

Bases: `object`

Abstracts away boilerplate of submitting and collecting jobs

This is a basic wrapper around `ubelt.util_futures.Executor` that simplifies the most basic case by 1. keeping track of references to submitted futures for you and 2. providing an `as_completed` method to consume those futures as they are ready.

#### Parameters

- **mode** (*str*) – The backend parallelism mechanism. Can be either thread, serial, or process. Defaults to ‘thread’.
- **max\_workers** (*int*) – number of workers. If 0, serial is forced. Defaults to 0.
- **transient** (*bool*) – if True, references to jobs will be discarded as they are returned by `as_completed()`. Otherwise the `jobs` attribute holds a reference to all jobs ever submitted. Default to False.

#### Example

```
>>> import ubelt as ub
>>> def worker(data):
>>>     return data + 1
>>> pool = ub.JobPool('thread', max_workers=16)
>>> for data in ub.ProgIter(range(10), desc='submit jobs'):
>>>     pool.submit(worker, data)
>>> final = []
>>> for job in pool.as_completed(desc='collect jobs'):
>>>     info = job.result()
>>>     final.append(info)
>>> print('final = {!r}'.format(final))
```

**submit(func, \*args, \*\*kwargs)**

Submit a job managed by the pool

#### Parameters

- **func** (*Callable[..., Any]*) – A callable that will take as many arguments as there are passed iterables.
- **\*args** – positional arguments to pass to the function
- **\*kwargs** – keyword arguments to pass to the function

#### Returns

a future representing the job

#### Return type

`concurrent.futures.Future`

**shutdown()**

**as\_completed(timeout=None, desc=None, progkw=None)**

Generates completed jobs in an arbitrary order

#### Parameters

- **timeout** (*float | None*) – Specify the the maximum number of seconds to wait for a job.  
Note: this is ignored in serial mode.
- **desc** (*str | None*) – if specified, reports progress with a `ubelt.progiter.ProgIter` object.
- **progkw** (*dict | None*) – extra keyword arguments to `ubelt.progiter.ProgIter`.

**Yields**

`concurrent.futures.Future` – The completed future object containing the results of a job.

**CommandLine**

```
xdoc test -m ubelt.util_futures JobPool.as_completed
```

**Example**

```
>>> import ubelt as ub
>>> pool = ub.JobPool('thread', max_workers=8)
>>> text = ub.paragraph(
...     """
...     UDP is a cool protocol, check out the wiki:
...
...     UDP-based Data Transfer Protocol (UDT), is a high-performance
...     data transfer protocol designed for transferring large
...     volumetric datasets over high-speed wide area networks. Such
...     settings are typically disadvantageous for the more common TCP
...     protocol.
...     """)
>>> for word in text.split(' '):
...     pool.submit(print, word)
>>> for _ in pool.as_completed():
...     pass
>>> pool.shutdown()
```

**join(\*\*kwargs)**

Like `JobPool.as_completed()`, but executes the `result` method of each future and returns only after all processes are complete. This allows for lower-boilerplate prototyping.

**Parameters**

`**kwargs` – passed to `JobPool.as_completed()`

**Returns**

list of results

**Return type**

List[Any]

## Example

```
>>> import ubelt as ub
>>> # We just want to try replacing our simple iterative algorithm
>>> # with the embarrassingly parallel version
>>> arglist = list(zip(range(1000), range(1000)))
>>> func = ub.identity
>>> #
>>> # Original version
>>> for args in arglist:
>>>     func(*args)
>>> #
>>> # Potentially parallel version
>>> jobs = ub.JobPool(max_workers=0)
>>> for args in arglist:
>>>     jobs.submit(func, *args)
>>> _ = jobs.join(desc='running')
```

### 2.1.1.6.2.6 kwcoco.util.util\_json module

`kwcoco.util.util_json.ensure_json_serializable(dict_, normalize_containers=False, verbose=0)`

Attempt to convert common types (e.g. numpy) into something json compliant

Convert numpy and tuples into lists

#### Parameters

- `normalize_containers (bool)` – if True, normalizes dict containers to be standard python structures. Defaults to False.

## Example

```
>>> data = ub.ddict(lambda: int)
>>> data['foo'] = ub.ddict(lambda: int)
>>> data['bar'] = np.array([1, 2, 3])
>>> data['foo']['a'] = 1
>>> data['foo']['b'] = (1, np.array([1, 2, 3]), {3: np.int32(3), 4: np.float16(1.0)})
>>>
>>> dict_ = data
>>> print(ub.repr2(data, nl=-1))
>>> assert list(find_json_unserializable(data))
>>> result = ensure_json_serializable(data, normalize_containers=True)
>>> print(ub.repr2(result, nl=-1))
>>> assert not list(find_json_unserializable(result))
>>> assert type(result) is dict
```

`kwcoco.util.util_json.find_json_unserializable(data, quickcheck=False)`

Recurse through json datastructure and find any component that causes a serialization error. Record the location of these errors in the datastructure as we recurse through the call tree.

#### Parameters

- `data (object)` – data that should be json serializable

- **quickcheck** (*bool*) – if True, check the entire datastructure assuming its ok before doing the python-based recursive logic.

**Returns**

list of “bad part” dictionaries containing items

’value’ - the value that caused the serialization error

’loc’ - which contains a list of key/indexes that can be used to lookup the location of the unserializable value. If the “loc” is a list, then it indicates a rare case where a key in a dictionary is causing the serialization error.

**Return type**

List[Dict]

**Example**

```
>>> from kwcoc.util.util_json import * # NOQA
>>> part = ub.ddict(lambda: int)
>>> part['foo'] = ub.ddict(lambda: int)
>>> part['bar'] = np.array([1, 2, 3])
>>> part['foo']['a'] = 1
>>> # Create a dictionary with two unserializable parts
>>> data = [1, 2, {'nest1': [2, part]}, {frozenset({'badkey'}): 3, 2: 4}]
>>> parts = list(find_json_unserializable(data))
>>> print('parts = {}'.format(ub.repr2(parts, nl=1)))
>>> # Check expected structure of bad parts
>>> assert len(parts) == 2
>>> part = parts[1]
>>> assert list(part['loc']) == [2, 'nest1', 1, 'bar']
>>> # We can use the "loc" to find the bad value
>>> for part in parts:
>>>     # "loc" is a list of directions containing which keys/indexes
>>>     # to traverse at each descent into the data structure.
>>>     directions = part['loc']
>>>     curr = data
>>>     special_flag = False
>>>     for key in directions:
>>>         if isinstance(key, list):
>>>             # special case for bad keys
>>>             special_flag = True
>>>             break
>>>         else:
>>>             # normal case for bad values
>>>             curr = curr[key]
>>>     if special_flag:
>>>         assert part['data'] in curr.keys()
>>>         assert part['data'] is key[1]
>>>     else:
>>>         assert part['data'] is curr
```

`kwcoc.util.util_json.indexable_allclose(dct1, dct2, return_info=False)`

Walks through two nested data structures and ensures that everything is roughly the same.

---

**Note:** Use the version in ubelt instead

---

### Parameters

- **dct1** – a nested indexable item
- **dct2** – a nested indexable item

### Example

```
>>> from kwcoco.util.util_json import indexable_allclose
>>> dct1 = {
>>>     'foo': [1.222222, 1.333],
>>>     'bar': 1,
>>>     'baz': [],
>>> }
>>> dct2 = {
>>>     'foo': [1.22222, 1.333],
>>>     'bar': 1,
>>>     'baz': [],
>>> }
>>> assert indexable_allclose(dct1, dct2)
```

`kwcoco.util.util_json.coerce_indent(indent)`

### Example

#### 2.1.1.6.2.7 `kwcoco.util.util_monkey` module

`class kwcoco.util.util_monkey.SuppressPrint(*mods, **kw)`

Bases: `object`

Temporarily replace the print function in a module with a noop

### Parameters

- **\*mods** – the modules to disable print in
- **\*\*kw** – only accepts “enabled” enabled (bool, default=True): enables or disables this context

`class kwcoco.util.util_monkey.Reloadable`

Bases: `type`

This is a metaclass that overrides the behavior of `isinstance` and `issubclass` when invoked on classes derived from this such that they only check that the module and class names agree, which are preserved through module reloads, whereas class instances are not.

This is useful for interactive development, but should be removed in production.

## Example

```
>>> from kwcoc.util.util_monkey import * # NOQA
>>> # Illustrate what happens with a reload when using this utility
>>> # versus without it.
>>> class Base1:
>>>     ...
>>> class Derived1(Base1):
>>>     ...
>>> @Reloadable.add_metaclass
>>> class Base2:
>>>     ...
>>> class Derived2(Base2):
>>>     ...
>>> inst1 = Derived1()
>>> inst2 = Derived2()
>>> assert isinstance(inst1, Derived1)
>>> assert isinstance(inst2, Derived2)
>>> # Simulate reload
>>> class Base1:
>>>     ...
>>> class Derived1(Base1):
>>>     ...
>>> @Reloadable.add_metaclass
>>> class Base2:
>>>     ...
>>> class Derived2(Base2):
>>>     ...
>>> assert not isinstance(inst1, Derived1)
>>> assert isinstance(inst2, Derived2)
```

### classmethod add\_metaclass(cls)

Class decorator for creating a class with this as a metaclass

### classmethod developing(cls)

Like add\_metaclass, but warns the user that they are developing. This helps remind them to remove this in production

## 2.1.1.6.2.8 kwcoc.util.util\_reroot module

Rerooting is harder than you would think

`kwcoc.util.util_reroot.special_reroot_single(dset, verbose=0)`

`kwcoc.util.util_reroot.resolve_relative_to(path, dpath, strict=False)`

Given a path, try to resolve its symlinks such that it is relative to the given dpath.

## Example

```
>>> from kwcoco.util.util_reroot import * # NOQA
>>> import os
>>> def _symlink(self, target, verbose=0):
>>>     return ub.Path(ub.symlink(target, self, verbose=verbose))
>>> ub.Path._symlink = _symlink
>>> #
>>> # TODO: try to enumerate all basic cases
>>> #
>>> base = ub.Path.apendir('kwcoco/tests/reroot')
>>> base.delete().ensuredir()
>>> #
>>> drive1 = (base / 'drive1').ensuredir()
>>> drive2 = (base / 'drive2').ensuredir()
>>> #
>>> data_repo1 = (drive1 / 'data_repo1').ensuredir()
>>> cache = (data_repo1 / '.cache').ensuredir()
>>> real_file1 = (cache / 'real_file1').touch()
>>> #
>>> real_bundle = (data_repo1 / 'real_bundle').ensuredir()
>>> real_assets = (real_bundle / 'assets').ensuredir()
>>> #
>>> # Symlink file outside of the bundle
>>> link_file1 = (real_assets / 'link_file1')._symlink(real_file1)
>>> real_file2 = (real_assets / 'real_file2').touch()
>>> link_file2 = (real_assets / 'link_file2')._symlink(real_file2)
>>> #
>>> #
>>> # A symlink to the data repo
>>> data_repo2 = (drive1 / 'data_repo2')._symlink(data_repo1)
>>> data_repo3 = (drive2 / 'data_repo3')._symlink(data_repo1)
>>> data_repo4 = (drive2 / 'data_repo4')._symlink(data_repo2)
>>> #
>>> # A prediction repo TODO
>>> pred_repo5 = (drive2 / 'pred_repo5').ensuredir()
>>> #
>>> # _ = ub.cmd(f'tree -a {base}', verbose=3)
>>> #
>>> fpaths = []
>>> for r, ds, fs in os.walk(base, followlinks=True):
>>>     for f in fs:
>>>         if 'file' in f:
>>>             fpath = ub.Path(r) / f
>>>             fpaths.append(fpath)
>>> #
>>> #
>>> dpath = real_bundle.resolve()
>>> #
>>> for path in fpaths:
>>>     # print(f'{path}')
>>>     # print(f'{path.resolve()=}')
>>>     resolved_rel = resolve_relative_to(path, dpath)
```

(continues on next page)

(continued from previous page)

```
>>>     print('resolved_rel = {!r}'.format(resolved_rel))
```

`kwcoco.util.util_reroot.resolve_directory_symlinks(path)`

Only resolve symlinks of directories, not the base file

### 2.1.1.6.2.9 `kwcoco.util.util_sklearn module`

Extensions to sklearn constructs

`class kwcoco.util.util_sklearn.StratifiedGroupKFold(n_splits=3, shuffle=False, random_state=None)`

Bases: `_BaseKFold`

Stratified K-Folds cross-validator with Grouping

Provides train/test indices to split data in train/test sets.

This cross-validation object is a variation of GroupKFold that returns stratified folds. The folds are made by preserving the percentage of samples for each class.

This is an old interface and should likely be refactored and modernized.

#### Parameters

`n_splits (int, default=3)` – Number of folds. Must be at least 2.

`split(X, y, groups=None)`

Generate indices to split data into training and test set.

### 2.1.1.6.2.10 `kwcoco.util.util_truncate module`

Truncate utility based on python-slugify.

<https://pypi.org/project/python-slugify/1.2.2/>

`kwcoco.util.util_truncate.smart_truncate(string, max_length=0, separator='', trunc_loc=0.5, trunc_char='~')`

Truncate a string. :param string (str): string for modification :param max\_length (int): output string length :param word\_boundary (bool): :param save\_order (bool): if True then word order of output string is like input string :param separator (str): separator between words :param trunc\_loc (float): fraction of location where to remove the text

`trunc_char (str):` the character to denote where truncation is starting

#### Returns

### 2.1.1.6.3 Module contents

`mkinit ~/code/kwcoco/kwcoco/util/__init__.py -w` `mkinit ~/code/kwcoco/kwcoco/util/__init__.py -lazy`

`kwcoco.util.ALLOF(*TYPES)`

`kwcoco.util.ANYOF(*TYPES)`

`kwcoco.util.ARRAY(TYPE={}, **kw)`

<https://json-schema.org/understanding-json-schema/reference/array.html>

## Example

```
>>> from kwcocoo.util.jsonschema_elements import * # NOQA
>>> ARRAY(numItems=3)
>>> schema = ARRAY(minItems=3)
>>> schema.validate()
{'type': 'array', 'items': {}, 'minItems': 3}
```

`class kwcocoo.util.Archive(fpather=None, mode='r', backend=None, file=None)`

Bases: `object`

Abstraction over zipfile and tarfile

**Todo:** see if we can use one of these other tools instead

## SeeAlso:

<https://github.com/RKrahl/archive-tools> <https://pypi.org/project/arlib/>

## Example

```
>>> from kwcocoo.util.util_archive import Archive
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwcocoo', 'tests', 'util', 'archive')
>>> dpath.delete().ensuredir()
>>> # Test write mode
>>> mode = 'w'
>>> arc_zip = Archive(str(dpath / 'demo.zip'), mode=mode)
>>> arc_tar = Archive(str(dpath / 'demo.tar.gz'), mode=mode)
>>> open(dpath / 'data_1only.txt', 'w').write('bazbzzz')
>>> open(dpath / 'data_2only.txt', 'w').write('buzzz')
>>> open(dpath / 'data_both.txt', 'w').write('foobar')
>>> #
>>> arc_zip.add(dpath / 'data_both.txt')
>>> arc_zip.add(dpath / 'data_1only.txt')
>>> #
>>> arc_tar.add(dpath / 'data_both.txt')
>>> arc_tar.add(dpath / 'data_2only.txt')
>>> #
>>> arc_zip.close()
>>> arc_tar.close()
>>> #
>>> # Test read mode
>>> arc_zip = Archive(str(dpath / 'demo.zip'), mode='r')
>>> arc_tar = Archive(str(dpath / 'demo.tar.gz'), mode='r')
>>> # Test names
>>> name = 'data_both.txt'
>>> assert name in arc_zip.names()
>>> assert name in arc_tar.names()
>>> # Test read
>>> assert arc_zip.read(name, mode='r') == 'foobar'
>>> assert arc_tar.read(name, mode='r') == 'foobar'
```

(continues on next page)

(continued from previous page)

```
>>> #
>>> # Test extractall
>>> extract_dpath = ub.ensuredir(str(dpath / 'extracted'))
>>> extracted1 = arc_zip.extractall(extract_dpath)
>>> extracted2 = arc_tar.extractall(extract_dpath)
>>> for fpath in extracted2:
>>>     print(open(fpath, 'r').read())
>>> for fpath in extracted1:
>>>     print(open(fpath, 'r').read())
```

**names()****read(name, mode='rb')**

Read data directly out of the archive.

#### Parameters

- **name** (*str*) – the name of the archive member to read
- **mode** (*str*) – This is a conceptual parameter that emulates the usual open mode. Defaults to “rb”, which returns data as raw bytes. If “r” will decode the bytes into utf8-text.

**classmethod coerce(data)**

Either open an archive file path or coerce an existing ZipFile or tarfile structure into this wrapper class

**add(fpath, arcname=None)****close()****extractall(output\_dpath='.', verbose=1, overwrite=True)****class kwoco.util.ContainerElements**

Bases: *object*

Types that contain other types

### Example

```
>>> from kwoco.util.jsonschema_elements import * # NOQA
>>> print(elem.ARRAY().validate())
>>> print(elem.OBJECT().validate())
>>> print(elem.OBJECT().validate())
{'type': 'array', 'items': []}
{'type': 'object', 'properties': {}}
{'type': 'object', 'properties': {}}
```

**ARRAY(TYPE={}, \*\*kw)**

<https://json-schema.org/understanding-json-schema/reference/array.html>

## Example

```
>>> from kwcoco.util.jsonschema_elements import * # NOQA
>>> ARRAY(numItems=3)
>>> schema = ARRAY(minItems=3)
>>> schema.validate()
{'type': 'array', 'items': {}, 'minItems': 3}
```

**OBJECT(*PROPERTIES*={}, \*\**kw*)**

<https://json-schema.org/understanding-json-schema/reference/object.html>

## Example

```
>>> import jsonschema
>>> schema = elem.OBJECT()
>>> jsonschema.validate({}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.ANY(),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'])
>>> jsonschema.validate({'key1': None}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.OBJECT({'arr': elem.ARRAY()}),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'], title='a title')
>>> schema.validate()
>>> print('schema = {}'.format(ub.repr2(schema, sort=1, nl=-1)))
>>> jsonschema.validate({'key1': {'arr': []}}, schema)
schema = {
    'properties': {
        'key1': {
            'properties': {
                'arr': {'items': {}, 'type': 'array'}
            },
            'type': 'object'
        },
        'key2': {}
    },
    'required': ['key1'],
    'title': 'a title',
    'type': 'object'
}
```

**class kwcoco.util.DictLike**

Bases: `NiceRepr`

An inherited class must specify the `getitem`, `setitem`, and  
keys methods.

A class is dictionary like if it has:

`__iter__`, `__len__`, `__contains__`, `__getitem__`, `items`, `keys`, `values`, `get`,

and if it should be writable it should have: `__delitem__`, `__setitem__`, `update`,

And perhaps: `copy`,

`__iter__`, `__len__`, `__contains__`, `__getitem__`, `items`, `keys`, `values`, `get`,

and if it should be writable it should have: `__delitem__`, `__setitem__`, `update`,

And perhaps: `copy`,

**getitem(key)**

**Parameters**

`key (Any)` – a key

**Returns**

a value

**Return type**

`Any`

**setitem(key, value)**

**Parameters**

- `key (Any)`
- `value (Any)`

**delitem(key)**

**Parameters**

`key (Any)`

**keys()**

**Yields**

`Any` – a key

**items()**

**Yields**

`Tuple[Any, Any]` – a key value pair

**values()**

**Yields**

`Any` – a value

**copy()**

**Return type**

`Dict`

**to\_dict()**

**Return type**

`Dict`

`asdict()`

**Return type**

Dict

`update(other)`

`get(key, default=None)`

**Parameters**

- `key` (`Any`)
- `default` (`Any`)

**Return type**

`Any`

`class kwcocoo.util.Element(base, options={}, _magic=None)`

Bases: `dict`

A dictionary used to define an element of a JSON Schema.

The exact keys/values for the element will depend on the type of element being described. The `SchemaElements` defines exactly what these are for the core elements. (e.g. OBJECT, INTEGER, NULL, ARRAY, ANYOF)

## Example

```
>>> from kwcocoo.coco_schema import * # NOQA
>>> self = Element(base={'type': 'demo'}, options={'opt1', 'opt2'})
>>> new = self(opt1=3)
>>> print('self = {}'.format(ub.repr2(self, nl=1, sort=1)))
>>> print('new = {}'.format(ub.repr2(new, nl=1, sort=1)))
>>> print('new2 = {}'.format(ub.repr2(new(), nl=1, sort=1)))
>>> print('new3 = {}'.format(ub.repr2(new(title='myvar'), nl=1, sort=1)))
>>> print('new4 = {}'.format(ub.repr2(new(title='myvar')(examples=['']), nl=1, sort=1)))
>>> print('new5 = {}'.format(ub.repr2(new(badattr=True), nl=1, sort=1)))
self = {
    'type': 'demo',
}
new = {
    'opt1': 3,
    'type': 'demo',
}
new2 = {
    'opt1': 3,
    'type': 'demo',
}
new3 = {
    'opt1': 3,
    'title': 'myvar',
    'type': 'demo',
}
new4 = {
    'examples': [],
}
```

(continues on next page)

(continued from previous page)

```
'opt1': 3,
'title': 'myvar',
'type': 'demo',
}
new5 = {
    'opt1': 3,
    'type': 'demo',
}
```

### validate(*instance*=*NoParam*)

If *instance* is given, validates that that dictionary conforms to this schema. Otherwise validates that this is a valid schema element.

#### Parameters

**instance** (*dict*) – a dictionary to validate

```
class kwcoc.util.IndexableWalker(data, dict_cls=(<class 'dict'>, ), list_cls=(<class 'list'>, <class 'tuple'>))
```

Bases: **Generator**

Traverses through a nested tree-like indexable structure.

Generates a path and value to each node in the structure. The path is a list of indexes which if applied in order will reach the value.

The `__setitem__` method can be used to modify a nested value based on the path returned by the generator.

When generating values, you can use “send” to prevent traversal of a particular branch.

#### RelatedWork:

- <https://pypi.org/project/python-benedict/> - implements a **dictionary** subclass with similar nested indexing abilities.

#### Variables

- **data** (*dict* / *list* / *tuple*) – the wrapped indexable data
- **dict\_cls** (*Tuple[type]*) – the types that should be considered dictionary mappings for the purpose of nested iteration. Defaults to *dict*.
- **list\_cls** (*Tuple[type]*) – the types that should be considered list-like for the purposes of nested iteration. Defaults to (*list*, *tuple*).

#### Example

```
>>> import ubelt as ub
>>> # Given Nested Data
>>> data = {
>>>     'foo': {'bar': 1},
>>>     'baz': [{ 'biz': 3}, { 'buz': [4, 5, 6]}],
>>> }
>>> # Create an IndexableWalker
>>> walker = ub.IndexableWalker(data)
>>> # We iterate over the data as if it was flat
>>> # ignore the <want> string due to order issues on older Pythons
```

(continues on next page)

(continued from previous page)

```
>>> # xdoctest: +IGNORE_WANT
>>> for path, val in walker:
>>>     print(path)
['foo']
['baz']
['baz', 0]
['baz', 1]
['baz', 1, 'buz']
['baz', 1, 'buz', 0]
['baz', 1, 'buz', 1]
['baz', 1, 'buz', 2]
['baz', 0, 'biz']
['foo', 'bar']

>>> # We can use "paths" as keys to getitem into the walker
>>> path = ['baz', 1, 'buz', 2]
>>> val = walker[path]
>>> assert val == 6

>>> # We can use "paths" as keys to setitem into the walker
>>> assert data['baz'][1]['buz'][2] == 6
>>> walker[path] = 7
>>> assert data['baz'][1]['buz'][2] == 7

>>> # We can use "paths" as keys to delitem into the walker
>>> assert data['baz'][1]['buz'][1] == 5
>>> del walker[['baz', 1, 'buz', 1]]
>>> assert data['baz'][1]['buz'][1] == 7
```

## Example

```
>>> # Create nested data
>>> # xdoctest: +REQUIRES(module:numpy)
>>> import numpy as np
>>> import ubelt as ub
>>> data = ub.ddict(lambda: int)
>>> data['foo'] = ub.ddict(lambda: int)
>>> data['bar'] = np.array([1, 2, 3])
>>> data['foo']['a'] = 1
>>> data['foo']['b'] = np.array([1, 2, 3])
>>> data['foo']['c'] = [1, 2, 3]
>>> data['baz'] = 3
>>> print('data = {}'.format(ub.repr2(data, nl=True)))
>>> # We can walk through every node in the nested tree
>>> walker = ub.IndexableWalker(data)
>>> for path, value in walker:
>>>     print('walk path = {}'.format(ub.repr2(path, nl=0)))
>>>     if path[-1] == 'c':
>>>         # Use send to prevent traversing this branch
>>>         got = walker.send(False)
>>>         # We can modify the value based on the returned path
>>>         walker[path] = 'changed the value of c'
>>> print('data = {}'.format(ub.repr2(data, nl=True)))
>>> assert data['foo']['c'] == 'changed the value of c'
```

### Example

```
>>> # Test sending false for every data item
>>> import ubelt as ub
>>> data = {1: [1, 2, 3], 2: [1, 2, 3]}
>>> walker = ub.IndexableWalker(data)
>>> # Sending false means you wont traverse any further on that path
>>> num_iters_v1 = 0
>>> for path, value in walker:
>>>     print('[v1] walk path = {}'.format(ub.repr2(path, nl=0)))
>>>     walker.send(False)
>>>     num_iters_v1 += 1
>>> num_iters_v2 = 0
>>> for path, value in walker:
>>>     # When we dont send false we walk all the way down
>>>     print('[v2] walk path = {}'.format(ub.repr2(path, nl=0)))
>>>     num_iters_v2 += 1
>>> assert num_iters_v1 == 2
>>> assert num_iters_v2 == 8
```

### Example

```
>>> # Test numpy
>>> # xdoctest: +REQUIRES(CPython)
>>> # xdoctest: +REQUIRES(module:numpy)
>>> import ubelt as ub
>>> import numpy as np
>>> # By default we don't recurse into ndarrays because they
>>> # Are registered as an indexable class
>>> data = {2: np.array([1, 2, 3])}
>>> walker = ub.IndexableWalker(data)
>>> num_iters = 0
>>> for path, value in walker:
>>>     print('walk path = {}'.format(ub.repr2(path, nl=0)))
>>>     num_iters += 1
>>> assert num_iters == 1
>>> # Currently to use top-level ndarrays, you need to extend what the
>>> # list class is. This API may change in the future to be easier
>>> # to work with.
>>> data = np.random.rand(3, 5)
>>> walker = ub.IndexableWalker(data, list_cls=(list, tuple, np.ndarray))
>>> num_iters = 0
>>> for path, value in walker:
>>>     print('walk path = {}'.format(ub.repr2(path, nl=0)))
>>>     num_iters += 1
>>> assert num_iters == 3 + 3 * 5
```

**send(arg)** → send 'arg' into generator,

return next yielded value or raise StopIteration.

**throw(typ[, val[, tb ]])** → raise exception in generator,

return next yielded value or raise StopIteration.

**allclose**(*other*, *rel\_tol*=*1e-09*, *abs\_tol*=*0.0*, *return\_info*=*False*)

Walks through this and another nested data structures and checks if everything is roughly the same.

**Parameters**

- **other** (*IndexableWalker* | *List* | *Dict*) – a nested indexable item to compare against.
- **rel\_tol** (*float*) – maximum difference for being considered “close”, relative to the magnitude of the input values
- **abs\_tol** (*float*) – maximum difference for being considered “close”, regardless of the magnitude of the input values
- **return\_info** (*bool*, *default=False*) – if true, return extra info dict

**Returns**

A boolean result if *return\_info* is false, otherwise a tuple of the boolean result and an “info” dict containing detailed results indicating what matched and what did not.

**Return type**

*bool* | *Tuple[bool, Dict]*

**Example**

```
>>> import ubelt as ub
>>> items1 = ub.IndexableWalker({
>>>     'foo': [1.222222, 1.333],
>>>     'bar': 1,
>>>     'baz': [],
>>> })
>>> items2 = ub.IndexableWalker({
>>>     'foo': [1.22222, 1.333],
>>>     'bar': 1,
>>>     'baz': [],
>>> })
>>> flag, return_info = items1.allclose(items2, return_info=True)
>>> print('return_info = {}'.format(ub.repr2(return_info, nl=1)))
>>> print('flag = {!r}'.format(flag))
>>> for p1, v1, v2 in return_info['faillist']:
>>>     v1_ = items1[p1]
>>>     print('*fail p1, v1, v2 = {}, {}, {}'.format(p1, v1, v2))
>>> for p1 in return_info['passlist']:
>>>     v1_ = items1[p1]
>>>     print('*pass p1, v1_ = {}, {}'.format(p1, v1_))
>>> assert not flag
```

```
>>> import ubelt as ub
>>> items1 = ub.IndexableWalker({
>>>     'foo': [1.0000000000000001, 1.],
>>>     'bar': 1,
>>>     'baz': [],
>>> })
>>> items2 = ub.IndexableWalker({
>>>     'foo': [0.9999999999999999, 1.],
>>>     'bar': 1,
```

(continues on next page)

(continued from previous page)

```
>>>     'baz': [],
>>> })
>>> flag, return_info = items1.allclose(items2, return_info=True)
>>> print('return_info = {}'.format(ub.repr2(return_info, nl=1)))
>>> print('flag = {!r}'.format(flag))
>>> assert flag
```

### Example

```
>>> import ubelt as ub
>>> flag, return_info = ub.IndexableWalker([]).allclose(ub.IndexableWalker([]),
>>> ~ return_info=True)
>>> print('return_info = {!r}'.format(return_info))
>>> print('flag = {!r}'.format(flag))
>>> assert flag
```

### Example

```
>>> import ubelt as ub
>>> flag = ub.IndexableWalker([]).allclose([], return_info=False)
>>> print('flag = {!r}'.format(flag))
>>> assert flag
```

### Example

```
>>> import ubelt as ub
>>> flag, return_info = ub.IndexableWalker([]).allclose([1], return_info=True)
>>> print('return_info = {!r}'.format(return_info))
>>> print('flag = {!r}'.format(flag))
>>> assert not flag
```

### Example

```
>>> # xdoctest: +REQUIRES(module:numpy)
>>> import ubelt as ub
>>> import numpy as np
>>> a = np.random.rand(3, 5)
>>> b = a + 1
>>> wa = ub.IndexableWalker(a, list_cls=(np.ndarray,))
>>> wb = ub.IndexableWalker(b, list_cls=(np.ndarray,))
>>> flag, return_info = wa.allclose(wb, return_info=True)
>>> print('return_info = {!r}'.format(return_info))
>>> print('flag = {!r}'.format(flag))
>>> assert not flag
>>> a = np.random.rand(3, 5)
>>> b = a.copy() + 1e-17
```

(continues on next page)

(continued from previous page)

```
>>> wa = ub.IndexableWalker([a], list_cls=(np.ndarray, list))
>>> wb = ub.IndexableWalker([b], list_cls=(np.ndarray, list))
>>> flag, return_info = wa.allclose(wb, return_info=True)
>>> assert flag
>>> print('return_info = {!r}'.format(return_info))
>>> print('flag = {!r}'.format(flag))
```

kwcoco.util.NOT(*TYPE*)kwcoco.util.OBJECT(*PROPERTIES*={}, \*\**kw*)<https://json-schema.org/understanding-json-schema/reference/object.html>

## Example

```
>>> import jsonschema
>>> schema = elem.OBJECT()
>>> jsonschema.validate({}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.ANY(),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'])
>>> jsonschema.validate({'key1': None}, schema)
>>> #
>>> import jsonschema
>>> schema = elem.OBJECT({
>>>     'key1': elem.OBJECT({'arr': elem.ARRAY()}),
>>>     'key2': elem.ANY(),
>>> }, required=['key1'], title='a title')
>>> schema.validate()
>>> print('schema = {}'.format(ub.repr2(schema, sort=1, nl=-1)))
>>> jsonschema.validate({'key1': {'arr': []}}, schema)
schema = {
    'properties': {
        'key1': {
            'properties': {
                'arr': {'items': {}, 'type': 'array'}
            },
            'type': 'object'
        },
        'key2': {}
    },
    'required': ['key1'],
    'title': 'a title',
    'type': 'object'
}
```

kwcoco.util.ONEOF(\**TYPES*)**class kwcoco.util.QuantifierElements**Bases: `object`

Quantifier types

<https://json-schema.org/understanding-json-schema/reference/combing.html#allof>

### Example

```
>>> from kwcoco.util.jsonschema_elements import * # NOQA
>>> elem.ANYOF(elem.STRING, elem.NUMBER).validate()
>>> elem.ONEOF(elem.STRING, elem.NUMBER).validate()
>>> elem.NOT(elem.NULL).validate()
>>> elem.NOT(elem.ANY).validate()
>>> elem.ANY.validate()
```

**property ANY**

**ALLOF(\*TYPES)**

**ANYOF(\*TYPES)**

**ONEOF(\*TYPES)**

**NOT(TYPE)**

**class kwcoco.util.ScalarElements**

Bases: `object`

Single-valued elements

**property NULL**

[//json-schema.org/understanding-json-schema/reference/null.html](https://json-schema.org/understanding-json-schema/reference/null.html)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/null.html)

**property BOOLEAN**

[//json-schema.org/understanding-json-schema/reference/null.html](https://json-schema.org/understanding-json-schema/reference/null.html)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/null.html)

**property STRING**

[//json-schema.org/understanding-json-schema/reference/string.html](https://json-schema.org/understanding-json-schema/reference/string.html)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/string.html)

**property NUMBER**

[//json-schema.org/understanding-json-schema/reference/numeric.html#number](https://json-schema.org/understanding-json-schema/reference/numeric.html#number)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/numeric.html#number)

**property INTEGER**

[//json-schema.org/understanding-json-schema/reference/numeric.html#integer](https://json-schema.org/understanding-json-schema/reference/numeric.html#integer)

**Type**

[https](https://json-schema.org/understanding-json-schema/reference/numeric.html#integer)

**class kwcoco.util.SchemaElements**Bases: *ScalarElements*, *QuantifierElements*, *ContainerElements*

Functional interface into defining jsonschema structures.

See mixin classes for details.

**References**<https://json-schema.org/understanding-json-schema/>**Todo:**

- [ ] Generics: title, description, default, examples

**CommandLine**

```
xdoctest -m /home/joncrall/code/kwcoco/kwcoco/util/jsonschema_elements.py
→ SchemaElements
```

**Example**

```
>>> from kwcoco.util.jsonschema_elements import * # NOQA
>>> elem = SchemaElements()
>>> elem.ARRAY(elem.ANY())
>>> schema = OBJECT({
>>>     'prop1': ARRAY(INTEGER, minItems=3),
>>>     'prop2': ARRAY(STRING, numItems=2),
>>>     'prop3': ARRAY(OBJECT({
>>>         'subprob1': NUMBER,
>>>         'subprob2': NUMBER,
>>>     })),
>>> })
>>> print('schema = {}'.format(ub.repr2(schema, nl=2, sort=1)))
schema = {
    'properties': {
        'prop1': {'items': {'type': 'integer'}, 'minItems': 3, 'type': 'array'},
        'prop2': {'items': {'type': 'string'}, 'maxItems': 2, 'minItems': 2, 'type':
→ ': 'array'},
        'prop3': {'items': {'properties': {'subprob1': {'type': 'number'}, 'subprob2':
→ ': {'type': 'number'}}}, 'type': 'object'}, 'type': 'array'},
    },
    'type': 'object',
}
```

```
>>> TYPE = elem.OBJECT({
>>>     'p1': ANY,
>>>     'p2': ANY,
>>> }, required=['p1'])
```

(continues on next page)

(continued from previous page)

```
>>> import jsonschema
>>> inst = {'p1': None}
>>> jsonschema.validate(inst, schema=TYPE)
>>> #jsonschema.validate({'p2': None}, schema=TYPE)
```

**class** `kwcoco.util.StratifiedGroupKFold(n_splits=3, shuffle=False, random_state=None)`

Bases: `_BaseKFold`

Stratified K-Folds cross-validator with Grouping

Provides train/test indices to split data in train/test sets.

This cross-validation object is a variation of GroupKFold that returns stratified folds. The folds are made by preserving the percentage of samples for each class.

This is an old interface and should likely be refactored and modernized.

#### Parameters

`n_splits (int, default=3)` – Number of folds. Must be at least 2.

`split(X, y, groups=None)`

Generate indices to split data into training and test set.

**kwcoco.util.ensure\_json\_serializable(dict\_, normalize\_containers=False, verbose=0)**

Attempt to convert common types (e.g. numpy) into something json compliant

Convert numpy and tuples into lists

#### Parameters

`normalize_containers (bool)` – if True, normalizes dict containers to be standard python structures. Defaults to False.

## Example

```
>>> data = ub.ddict(lambda: int)
>>> data['foo'] = ub.ddict(lambda: int)
>>> data['bar'] = np.array([1, 2, 3])
>>> data['foo']['a'] = 1
>>> data['foo']['b'] = (1, np.array([1, 2, 3]), {3: np.int32(3), 4: np.float16(1.0)})
>)
>>> dict_ = data
>>> print(ub.repr2(data, nl=-1))
>>> assert list(find_json_unserializable(data))
>>> result = ensure_json_serializable(data, normalize_containers=True)
>>> print(ub.repr2(result, nl=-1))
>>> assert not list(find_json_unserializable(result))
>>> assert type(result) is dict
```

**kwcoco.util.find\_json\_unserializable(data, quickcheck=False)**

Recurse through json datastructure and find any component that causes a serialization error. Record the location of these errors in the datastructure as we recurse through the call tree.

#### Parameters

- `data (object)` – data that should be json serializable

- **quickcheck** (*bool*) – if True, check the entire datastructure assuming its ok before doing the python-based recursive logic.

**Returns**

list of “bad part” dictionaries containing items

’value’ - the value that caused the serialization error

’loc’ - which contains a list of key/indexes that can be used to lookup the location of the unserializable value. If the “loc” is a list, then it indicates a rare case where a key in a dictionary is causing the serialization error.

**Return type**

List[Dict]

**Example**

```
>>> from kwcocoo.util.util_json import * # NOQA
>>> part = ub.ddict(lambda: int)
>>> part['foo'] = ub.ddict(lambda: int)
>>> part['bar'] = np.array([1, 2, 3])
>>> part['foo']['a'] = 1
>>> # Create a dictionary with two unserializable parts
>>> data = [1, 2, {'nest1': [2, part]}, {frozenset({'badkey'}): 3, 2: 4}]
>>> parts = list(find_json_unserializable(data))
>>> print('parts = {}'.format(ub.repr2(parts, nl=1)))
>>> # Check expected structure of bad parts
>>> assert len(parts) == 2
>>> part = parts[1]
>>> assert list(part['loc']) == [2, 'nest1', 1, 'bar']
>>> # We can use the "loc" to find the bad value
>>> for part in parts:
>>>     # "loc" is a list of directions containing which keys/indexes
>>>     # to traverse at each descent into the data structure.
>>>     directions = part['loc']
>>>     curr = data
>>>     special_flag = False
>>>     for key in directions:
>>>         if isinstance(key, list):
>>>             # special case for bad keys
>>>             special_flag = True
>>>             break
>>>         else:
>>>             # normal case for bad values
>>>             curr = curr[key]
>>>     if special_flag:
>>>         assert part['data'] in curr.keys()
>>>         assert part['data'] is key[1]
>>>     else:
>>>         assert part['data'] is curr
```

`kwcocoo.util.indexable_allclose(dct1, dct2, return_info=False)`

Walks through two nested data structures and ensures that everything is roughly the same.

---

**Note:** Use the version in ubelt instead

---

### Parameters

- **dct1** – a nested indexable item
- **dct2** – a nested indexable item

### Example

```
>>> from kwcoc.util.util_json import indexable_allclose
>>> dct1 = {
>>>     'foo': [1.222222, 1.333],
>>>     'bar': 1,
>>>     'baz': [],
>>> }
>>> dct2 = {
>>>     'foo': [1.22222, 1.333],
>>>     'bar': 1,
>>>     'baz': [],
>>> }
>>> assert indexable_allclose(dct1, dct2)
```

`kwcoc.util.resolve_directory_symlinks(path)`

Only resolve symlinks of directories, not the base file

`kwcoc.util.resolve_relative_to(path, dpath, strict=False)`

Given a path, try to resolve its symlinks such that it is relative to the given dpath.

### Example

```
>>> from kwcoc.util.util_reroot import * # NOQA
>>> import os
>>> def _symlink(self, target, verbose=0):
>>>     return ub.Path(ub.symlink(target, self, verbose=verbose))
>>> ub.Path._symlink = _symlink
>>> #
>>> # TODO: try to enumerate all basic cases
>>> #
>>> base = ub.Path.apendir('kwcoc/tests/reroot')
>>> base.delete().ensuredir()
>>> #
>>> drive1 = (base / 'drive1').ensuredir()
>>> drive2 = (base / 'drive2').ensuredir()
>>> #
>>> data_repo1 = (drive1 / 'data_repo1').ensuredir()
>>> cache = (data_repo1 / '.cache').ensuredir()
>>> real_file1 = (cache / 'real_file1').touch()
>>> #
>>> real_bundle = (data_repo1 / 'real_bundle').ensuredir()
```

(continues on next page)

(continued from previous page)

```

>>> real_assets = (real_bundle / 'assets').ensuredir()
>>> #
>>> # Symlink file outside of the bundle
>>> link_file1 = (real_assets / 'link_file1')._symlink(real_file1)
>>> real_file2 = (real_assets / 'real_file2').touch()
>>> link_file2 = (real_assets / 'link_file2')._symlink(real_file2)
>>> #
>>> #
>>> # A symlink to the data repo
>>> data_repo2 = (drive1 / 'data_repo2')._symlink(data_repo1)
>>> data_repo3 = (drive2 / 'data_repo3')._symlink(data_repo1)
>>> data_repo4 = (drive2 / 'data_repo4')._symlink(data_repo2)
>>> #
>>> # A prediction repo TODO
>>> pred_repo5 = (drive2 / 'pred_repo5').ensuredir()
>>> #
>>> # _ = ub.cmd(f'tree -a {base}', verbose=3)
>>> #
>>> fpaths = []
>>> for r, ds, fs in os.walk(base, followlinks=True):
>>>     for f in fs:
>>>         if 'file' in f:
>>>             fpath = ub.Path(r) / f
>>>             fpaths.append(fpath)
>>> #
>>> #
>>> dpath = real_bundle.resolve()
>>> #
>>> for path in fpaths:
>>>     # print(f'{path}')
>>>     # print(f'{path.resolve()=}')
>>>     resolved_rel = resolve_relative_to(path, dpath)
>>>     print('resolved_rel = {!r}'.format(resolved_rel))

```

`kwcoco.util.smart_truncate(string, max_length=0, separator=' ', trunc_loc=0.5, trunc_char='~')`

Truncate a string. :param string (str): string for modification :param max\_length (int): output string length :param word\_boundary (bool): :param save\_order (bool): if True then word order of output string is like input string :param separator (str): separator between words :param trunc\_loc (float): fraction of location where to remove the text

trunc\_char (str): the character to denote where truncation is starting

#### Returns

`kwcoco.util.special_reroot_single(dset, verbose=0)`

`kwcoco.util.unarchive_file(archive_fpath, output_dpath='.', verbose=1, overwrite=True)`

## 2.1.2 Submodules

### 2.1.2.1 kwcoco.abstract\_coco\_dataset module

```
class kwcoco.abstract_coco_dataset.AbstractCocoDataset
```

Bases: ABC

This is a common base for all variants of the Coco Dataset

At the time of writing there is kwcoco.CocoDataset (which is the dictionary-based backend), and the kwcoco.coco\_sql\_dataset.CocoSqlDataset, which is experimental.

### 2.1.2.2 kwcoco.category\_tree module

The category\_tree module defines the `CategoryTree` class, which is used for maintaining flat or hierarchical category information. The kwcoco version of this class only contains the datastructure and does not contain any torch operations. See the ndsampler version for the extension with torch operations.

```
class kwcoco.category_tree.CategoryTree(graph=None, checks=True)
```

Bases: NiceRepr

Wrapper that maintains flat or hierarchical category information.

Helps compute softmaxes and probabilities for tree-based categories where a directed edge (A, B) represents that A is a superclass of B.

---

**Note:** There are three basic properties that this object maintains:

`node`:

Alphanumeric string names that should be generally descriptive. Using spaces `and` special characters `in` these names `is` discouraged, but can be done. This `is` the COCO category "name" attribute. For categories this may be denoted `as` (name, node, cname, catname).

`id`:

The integer `id` of a category should ideally remain consistent. These are often given by a dataset (e.g. a COCO dataset). This `is` the COCO category "id" attribute. For categories this `is` often denoted `as` (id, cid).

`index`:

Contiguous zero-based indices that indexes the `list` of categories. These should be used `for` the fastest access `in` backend computation tasks. Typically corresponds to the ordering of the channels `in` the final linear layer `in` an associated model. For categories this `is` often denoted `as` (index, cidx, idx, `or` cx).

---

## Variables

- `idx_to_node` (`List[str]`) – a list of class names. Implicitly maps from index to category name.

- **id\_to\_node** (*Dict[int, str]*) – maps integer ids to category names
- **node\_to\_id** (*Dict[str, int]*) – maps category names to ids
- **node\_to\_idx** (*Dict[str, int]*) – maps category names to indexes
- **graph** (*networkx.Graph*) – a Graph that stores any hierarchy information. For standard mutually exclusive classes, this graph is edgeless. Nodes in this graph can maintain category attributes / properties.
- **idx\_groups** (*List[List[int]]*) – groups of category indices that share the same parent category.

### Example

```
>>> from kwcoco.category_tree import *
>>> graph = nx.from_dict_of_lists({
>>>     'background': [],
>>>     'foreground': ['animal'],
>>>     'animal': ['mammal', 'fish', 'insect', 'reptile'],
>>>     'mammal': ['dog', 'cat', 'human', 'zebra'],
>>>     'zebra': ['grevys', 'plains'],
>>>     'grevys': ['fred'],
>>>     'dog': ['boxer', 'beagle', 'golden'],
>>>     'cat': ['maine coon', 'persian', 'sphynx'],
>>>     'reptile': ['bearded dragon', 't-rex'],
>>> }, nx.DiGraph)
>>> self = CategoryTree(graph)
>>> print(self)
<CategoryTree(nNodes=22, maxDepth=6, maxBreadth=4...)>
```

### Example

```
>>> # The coerce classmethod is the easiest way to create an instance
>>> import kwcoco
>>> kwcoco.CategoryTree.coerce(['a', 'b', 'c'])
<CategoryTree...nNodes=3, nodes='a', 'b', 'c'...
>>> kwcoco.CategoryTree.coerce(4)
<CategoryTree...nNodes=4, nodes='class_1', 'class_2', 'class_3', ...
>>> kwcoco.CategoryTree.coerce(4)
```

`copy()`

`classmethod from_mutex(nodes, bg_hack=True)`

#### Parameters

`nodes` (*List[str]*) – or a list of class names (in which case they will all be assumed to be mutually exclusive)

## Example

```
>>> print(CategoryTree.from_mutex(['a', 'b', 'c']))
<CategoryTree(nNodes=3, ...)>
```

**classmethod from\_json(state)**

### Parameters

**state** (*Dict*) – see `__getstate__` / `__json__` for details

**classmethod from\_coco(categories)**

Create a CategoryTree object from coco categories

### Parameters

**List[Dict]** – list of coco-style categories

**classmethod coerce(data, \*\*kw)**

Attempt to coerce data as a CategoryTree object.

This is primarily useful for when the software stack depends on categories being represented

This will work if the input data is a specially formatted json dict, a list of mutually exclusive classes, or if it is already a CategoryTree. Otherwise an error will be thrown.

### Parameters

- **data** (*object*) – a known representation of a category tree.
- **\*\*kwargs** – input type specific arguments

### Returns

`self`

### Return type

`CategoryTree`

### Raises

- `TypeError` – if the input format is unknown –
- `ValueError` – if kwargs are not compatible with the input format –

## Example

```
>>> import kwcoc
>>> classes1 = kwcoc.CategoryTree.coerce(3) # integer
>>> classes2 = kwcoc.CategoryTree.coerce(classes1.__json__()) # graph dict
>>> classes3 = kwcoc.CategoryTree.coerce(['class_1', 'class_2', 'class_3']) # mutex list
>>> classes4 = kwcoc.CategoryTree.coerce(classes1.graph) # nx Graph
>>> classes5 = kwcoc.CategoryTree.coerce(classes1) # cls
>>> # xdoctest: +REQUIRES(module:nd sampler)
>>> import nd sampler
>>> classes6 = nd sampler.CategoryTree.coerce(3)
>>> classes7 = nd sampler.CategoryTree.coerce(classes1)
>>> classes8 = kwcoc.CategoryTree.coerce(classes6)
```

**classmethod demo(key='coco', \*\*kwargs)**

#### Parameters

**key (str)** – specify which demo dataset to use. Can be ‘coco’ (which uses the default coco demo data). Can be ‘btree’ which creates a binary tree and accepts kwargs ‘r’ and ‘h’ for branching-factor and height. Can be ‘btree2’, which is the same as btree but returns strings

#### CommandLine

```
xdoctest -m ~/code/kwCOCO/kwCOCO/category_tree.py CategoryTree.demo
```

#### Example

```
>>> from kwCOCO.category_tree import *
>>> self = CategoryTree.demo()
>>> print('self = {}'.format(self))
self = <CategoryTree(nNodes=10, maxDepth=2, maxBreadth=4...)>
```

#### to\_coco()

Converts to a coco-style data structure

#### Yields

*Dict* – coco category dictionaries

#### property id\_to\_idx

Example:

```
>>> import kwCOCO
>>> self = kwCOCO.CategoryTree.demo()
>>> self.id_to_idx[1]
```

#### property idx\_to\_id

Example:

```
>>> import kwCOCO
>>> self = kwCOCO.CategoryTree.demo()
>>> self.idx_to_id[0]
```

#### idx\_to\_ancestor\_idxs(include\_self=True)

Mapping from a class index to its ancestors

#### Parameters

**include\_self (bool, default=True)** – if True includes each node as its own ancestor.

#### idx\_to\_descendants\_idxs(include\_self=False)

Mapping from a class index to its descendants (including itself)

#### Parameters

**include\_self (bool, default=False)** – if True includes each node as its own descendant.

#### idx\_pairwise\_distance()

Get a matrix encoding the distance from one class to another.

#### Distances

- from parents to children are positive (descendants),
- from children to parents are negative (ancestors),
- between unreachable nodes (wrt to forward and reverse graph) are nan.

### **is\_mutex()**

Returns True if all categories are mutually exclusive (i.e. flat)

If true, then the classes may be represented as a simple list of class names without any loss of information, otherwise the underlying category graph is necessary to preserve all knowledge.

---

### **Todo:**

- [ ] what happens when we have a dummy root?
- 

### **property num\_classes**

### **property class\_names**

### **property category\_names**

### **property cats**

Returns a mapping from category names to category attributes.

If this category tree was constructed from a coco-dataset, then this will contain the coco category attributes.

#### **Returns**

Dict[str, Dict[str, object]]

### **Example**

```
>>> from kwcoco.category_tree import *
>>> self = CategoryTree.demo()
>>> print('self.cats = {!r}'.format(self.cats))
```

### **index(node)**

Return the index that corresponds to the category name

### **show()**

### **forest\_str()**

### **normalize()**

Applies a normalization scheme to the categories.

Note: this may break other tasks that depend on exact category names.

#### **Returns**

CategoryTree

## Example

```
>>> from kwcoco.category_tree import * # NOQA
>>> import kwcoco
>>> orig = kwcoco.CategoryTree.demo('animals_v1')
>>> self = kwcoco.CategoryTree(nx.relabel_nodes(orig.graph, str.upper))
>>> norm = self.normalize()
```

### 2.1.2.3 kwcoco.channel\_spec module

The ChannelSpec and FusedChannelSpec represent a set of channels or bands in an image. This could be as simple as red|green|blue, or more complex like: red|green|blue|nir|swir16|swir22.

This functionality has been moved to “delayed\_image”.

### 2.1.2.4 kwcoco.coco\_dataset module

An implementation and extension of the original MS-COCO API [CocoFormat].

Extends the format to also include line annotations.

The following describes psuedo-code for the high level spec (some of which may not be have full support in the Python API). A formal json-schema is defined in [kwcoco.coco\\_schema](#).

**Note:** The main object in this file is [CocoDataset](#), which is composed of several mixin classes. See the class and method documentation for more details.

An informal description of the spec given in: [coco\\_schema\\_informal.rst](#).

For a formal description of the spec see the [coco\\_schema.json](#).

#### Todo:

- [ ] Use **ijson (modified to support NaN) to lazily load pieces of the** dataset in the background or on demand. This will give us faster access to categories / images, whereas we will always have to wait for annotations etc...
- [X] Should img\_root be changed to bundle\_dpath?
- [ ] Read video data, return numpy arrays (requires API for images)
- [ ] Spec for video URI, and convert to frames @ framerate function.
- [x] Document channel spec
- [x] Document sensor-channel spec
- [X] Add remove videos method
- [ ] **Efficiency: Make video annotations more efficient by only tracking** keyframes, provide an API to obtain a dense or interpolated annotation on an intermediate frame.
- [ ] **Efficiency: Allow each section of the kwcoco file to be written as a** separate json file. Perhaps allow generic pointer support? Might get messy.
- [ ] Reroot needs to be redesigned very carefully.
- [ ] Allow parts of the kwcoco file to be references to other json files.

## References

`class kwcoco.coco_dataset.MixinCocoDeprecate`

Bases: `object`

These functions are marked for deprecation and will be removed

`keypoint_annotation_frequency()`

DEPRECATED

### Example

```
>>> import kwcoco
>>> import ubelt as ub
>>> self = kwcoco.CocoDataset.demo('shapes', rng=0)
>>> hist = self.keypoint_annotation_frequency()
>>> hist = ub.odict(sorted(hist.items()))
>>> # FIXME: for whatever reason demodata generation is not deterministic when
>>> # seeded
>>> print(ub.repr2(hist))  # xdoc: +IGNORE_WANT
{
    'bot_tip': 6,
    'left_eye': 14,
    'mid_tip': 6,
    'right_eye': 14,
    'top_tip': 6,
}
```

`category_annotation_type_frequency()`

DEPRECATED

Reports the number of annotations of each type for each category

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> hist = self.category_annotation_frequency()
>>> print(ub.repr2(hist))
```

`imread(gid)`

DEPRECATED: use `load_image` or `delayed_image`

Loads a particular image

`class kwcoco.coco_dataset.MixinCocoAccessors`

Bases: `object`

TODO: better name

---

**delayed\_load(gid, channels=None, space='image')**

Experimental method

#### Parameters

- **gid** (*int*) – image id to load
- **channels** (*kwcoco.FusedChannelSpec*) – specific channels to load. if unspecified, all channels are loaded.
- **space** (*str*) – can either be “image” for loading in image space, or “video” for loading in video space.

---

#### Todo:

- [X] **Currently can only take all or none of the channels from each**  
base-image / auxiliary dict. For instance if the main image is r|g|b you can't just select g|b at the moment.
  - [X] **The order of the channels in the delayed load should**  
match the requested channel order.
  - [X] **TODO:** add nans to bands that don't exist or throw an error
- 

#### Example

```
>>> import kwcoco
>>> gid = 1
>>> #
>>> self = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> delayed = self.delayed_load(gid)
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> #
>>> self = kwcoco.CocoDataset.demo('shapes8')
>>> delayed = self.delayed_load(gid)
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
```

```
>>> crop = delayed.crop((slice(0, 3), slice(0, 3)))
>>> crop.finalize()
```

```
>>> # TODO: should only select the "red" channel
>>> self = kwcoco.CocoDataset.demo('shapes8')
>>> delayed = self.delayed_load(gid, channels='r')
```

```
>>> import kwcoco
>>> gid = 1
>>> #
>>> self = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> delayed = self.delayed_load(gid, channels='B1|B2', space='image')
>>> print('delayed = {!r}'.format(delayed))
>>> delayed = self.delayed_load(gid, channels='B1|B2|B11', space='image')
```

(continues on next page)

(continued from previous page)

```
>>> print('delayed = {!r}'.format(delayed))
>>> delayed = self.delayed_load(gid, channels='B8|B1', space='video')
>>> print('delayed = {!r}'.format(delayed))

>>> delayed = self.delayed_load(gid, channels='B8|foo|bar|B1', space='video')
>>> print('delayed = {!r}'.format(delayed))
```

**load\_image(*gid\_or\_img*, *channels=None*)**

Returns an image from disk and

**Parameters**

- **gid\_or\_img** (*int | dict*) – image id or image dict
- **channels** (*str | None*) – if specified, load data from auxiliary channels instead

**Returns**

the image

**Return type**

np.ndarray

---

**Todo:**

- [ ] allow specification of multiple channels - use delayed image for this.
- 

**get\_image\_fpath(*gid\_or\_img*, *channels=None*)**

Returns the full path to the image

**Parameters**

- **gid\_or\_img** (*int | dict*) – image id or image dict
- **channels** (*str | None*) – if specified, return a path to data containing auxiliary channels instead

**Returns**

full path to the image

**Return type**

PathLike

**get\_auxiliary\_fpath(*gid\_or\_img*, *channels*)**

Returns the full path to auxiliary data for an image

**Parameters**

- **gid\_or\_img** (*int | dict*) – an image or its id
- **channels** (*str*) – the auxiliary channel to load (e.g. disparity)

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('shapes8', aux=True)
>>> self.get_auxiliary_fpath(1, 'disparity')
```

**load\_annot\_sample(aid\_or\_ann, image=None, pad=None)**

Reads the chip of an annotation. Note this is much less efficient than using a sampler, but it doesn't require disk cache.

Maybe deprecate?

### Parameters

- **aid\_or\_int** (*int | dict*) – annot id or dict
- **image** (*ArrayLike | None*) – preloaded image (note: this process is inefficient unless image is specified)

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> sample = self.load_annot_sample(2, pad=100)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> kwplot.imshow(sample['im'])
>>> kwplot.show_if_requested()
```



### category\_graph()

Construct a networkx category hierarchy

#### Returns

graph: a directed graph where category names are the nodes, supercategories define edges, and items in each category dict (e.g. category id) are added as node properties.

#### Return type

networkx.DiGraph

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> graph = self.category_graph()
>>> assert 'astronaut' in graph.nodes()
>>> assert 'keypoints' in graph.nodes['human']
```

### object\_categories()

Construct a consistent CategoryTree representation of object classes

#### Returns

category data structure

#### Return type

*kwcoco.CategoryTree*

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> classes = self.object_categories()
>>> print('classes = {}'.format(classes))
```

**keypoint\_categories()**

Construct a consistent CategoryTree representation of keypoint classes

**Returns**

category data structure

**Return type**

*kwcoco.CategoryTree*

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> classes = self.keypoint_categories()
>>> print('classes = {}'.format(classes))
```

**coco\_image(*gid*)****Parameters**

*gid* (*int*) – image id

**Returns**

*kwcoco.coco\_image.CocoImage*

**class kwcoco.coco\_dataset.MixinCocoExtras**

Bases: *object*

Misc functions for coco

**classmethod coerce(*key*, *sqlview=False*, \*\**kw*)**

Attempt to transform the input into the intended CocoDataset.

**Parameters**

- **key** – this can either be an instance of a CocoDataset, a string URI pointing to an on-disk dataset, or a special key for creating demodata.
- **sqlview** (*bool* | *str*) – If truthy, will return the dataset as a cached sql view, which can be quicker to load and use in some instances. Can be given as a string, which sets the backend that is used: either sqlite or postgresql. Defaults to False.
- **\*\*kw** – passed to whatever constructor is chosen (if any)

**Returns**

*AbstractCocoDataset* | *kwcoco.CocoDataset* | *kwcoco.CocoSqlDatabase*

## Example

```
>>> # test coerce for various input methods
>>> import kwcoco
>>> from kwcoco.coco_sql_dataset import assert_dsets_allclose
>>> dct_dset = kwcoco.CocoDataset.coerce('special:shapes8')
>>> copy1 = kwcoco.CocoDataset.coerce(dct_dset)
>>> copy2 = kwcoco.CocoDataset.coerce(dct_dset.fpath)
>>> assert assert_dsets_allclose(dct_dset, copy1)
>>> assert assert_dsets_allclose(dct_dset, copy2)
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> sql_dset = dct_dset.view_sql()
>>> copy3 = kwcoco.CocoDataset.coerce(sql_dset)
>>> copy4 = kwcoco.CocoDataset.coerce(sql_dset.fpath)
>>> assert assert_dsets_allclose(dct_dset, sql_dset)
>>> assert assert_dsets_allclose(dct_dset, copy3)
>>> assert assert_dsets_allclose(dct_dset, copy4)
```

**classmethod demo(key='photos', \*\*kwargs)**

Create a toy coco dataset for testing and demo purposes

### Parameters

- **key (str)** – Either ‘photos’ (default), ‘shapes’, or ‘vidshapes’. There are also special suffixes that can control behavior.

Basic options that define which flavor of demodata to generate are: *photos*, *shapes*, and *vidshapes*. A numeric suffix e.g. *vidshapes8* can be specified to indicate the size of the generated demo dataset. There are other special suffixes that are available. See the code in this function for explicit details on what is allowed.

TODO: better documentation for these demo datasets.

As a quick summary: the *vidshapes* key is the most robust and mature demodata set, and here are several useful variants of the *vidshapes* key.

- (1) *vidshapes8* - the 8 suffix is the number of videos in this case.
  - (2) *vidshapes8-multispectral* - generate 8 multispectral videos.
  - (3) *vidshapes8-msi* - msi is an alias for multispectral.
  - (4) *vidshapes8-frames5* - generate 8 videos with 5 frames each.
  - (5) *vidshapes2-tracks5* - generate 2 videos with 5 tracks each.
  - (6) *vidshapes2-speed0.1-frames7* - generate 2 videos with 7 frames where the objects move with a speed of 0.1.
- **\*\*kwargs** – if key is shapes, these arguments are passed to toydata generation. The Kwargs section of this docstring documents a subset of the available options. For full details, see `demodata_toy_dset()` and `random_video_dset()`.

### Kwargs:

`image_size (Tuple[int, int]): width / height size of the images`

### dpath (str | PathLike):

`path to the directory where any generated demo bundles will be written to. Defaults to using kwcoco cache dir.`


aux (bool): if True generates dummy auxiliary channels  
**rng** (int | RandomState | None):  
 random number generator or seed  
 verbose (int): verbosity mode. Defaults to 3.

### Example

```
>>> # Basic demodata keys
>>> print(CocoDataset.demo('photos', verbose=1))
>>> print(CocoDataset.demo('shapes', verbose=1))
>>> print(CocoDataset.demo('vidshapes', verbose=1))
>>> # Variants of demodata keys
>>> print(CocoDataset.demo('shapes8', verbose=0))
>>> print(CocoDataset.demo('shapes8-msi', verbose=0))
>>> print(CocoDataset.demo('shapes8-frames1-speed0.2-msi', verbose=0))
```

### Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes5', num_frames=5,
>>>                               verbose=0, rng=None)
>>> dset = kwcoco.CocoDataset.demo('vidshapes5', num_frames=5,
>>>                               num_tracks=4, verbose=0, rng=44)
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> pnums = kwplot.PlotNums(nSubplots=len(dset.index.imgs))
>>> fnum = 1
>>> for gx, gid in enumerate(dset.index.imgs.keys()):
>>>     canvas = dset.draw_image(gid=gid)
>>>     kwplot.imshow(canvas, pnum=pnums[gx], fnum=fnum)
>>>     #dset.show_image(gid=gid, pnum=pnums[gx])
>>> kwplot.show_if_requested()
```



### Example

```
>>> import kwCOCO  
>>> dset = kwCOCO.CocoDataset.demo('vidshapes5-aux', num_frames=1,  
>>>                                         verbose=0, rng=None)
```

### Example

```
>>> import kwCOCO  
>>> dset = kwCOCO.CocoDataset.demo('vidshapes1-multispectral', num_frames=5,  
>>>                                         verbose=0, rng=None)  
>>> # This is the first use-case of image names  
>>> assert len(dset.index.file_name_to_img) == 0, (  
>>>     'the multispectral demo case has no "base" image')  
>>> assert len(dset.index.name_to_img) == len(dset.index.imgs) == 5  
>>> dset.remove_images([1])  
>>> assert len(dset.index.name_to_img) == len(dset.index.imgs) == 4  
>>> dset.remove_videos([1])  
>>> assert len(dset.index.name_to_img) == len(dset.index.imgs) == 0
```

**classmethod random(rng=None)**

Creates a random CocoDataset according to distribution parameters

---

**Todo:**

- [ ] parametrize
- 

**missing\_images**(*check\_aux=True, verbose=0*)

Check for images that don't exist

**Parameters**

- **check\_aux** (*bool*) – if specified also checks auxiliary images
- **verbose** (*int*) – verbosity level

**Returns**

bad indexes and paths and ids

**Return type**

List[Tuple[int, str, int]]

**corrupted\_images**(*check\_aux=False, verbose=0*)

Check for images that don't exist or can't be opened

**Parameters**

- **check\_aux** (*bool*) – if specified also checks auxiliary images
- **verbose** (*int*) – verbosity level

**Returns**

bad indexes and paths and ids

**Return type**

List[Tuple[int, str, int]]

**rename\_categories**(*mapper, rebuild=True, merge\_policy='ignore'*)

Rename categories with a potentially coarser categorization.

**Parameters**

- **mapper** (*dict | Callable*) – maps old names to new names. If multiple names are mapped to the same category, those categories will be merged.
- **merge\_policy** (*str*) – How to handle multiple categories that map to the same name. Can be update or ignore.

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> self.rename_categories({'astronomer': 'person',
>>>                         'astronaut': 'person',
>>>                         'mouth': 'person',
>>>                         'helmet': 'hat'})
>>> assert 'hat' in self.name_to_cat
>>> assert 'helmet' not in self.name_to_cat
>>> # Test merge case
>>> self = kwcoco.CocoDataset.demo()
>>> mapper = {
```

(continues on next page)

(continued from previous page)

```
>>>     'helmet': 'rocket',
>>>     'astronomer': 'rocket',
>>>     'human': 'rocket',
>>>     'mouth': 'helmet',
>>>     'star': 'gas'
>>> }
>>> self.rename_categories(mapper)
```

**rerooot**(*new\_root=None*, *old\_prefix=None*, *new\_prefix=None*, *absolute=False*, *check=True*, *safe=True*, *verbose=0*)

Modify the prefix of the image/data paths onto a new image/data root.

#### Parameters

- **new\_root** (*str | None*) – New image root. If unspecified the current `self.bundle_dpath` is used. If `old_prefix` and `new_prefix` are unspecified, they will attempt to be determined based on the current root (which assumes the file paths exist at that root) and this new root. Defaults to `None`.
- **old\_prefix** (*str | None*) – If specified, removes this prefix from file names. This also prevents any inferences that might be made via “`new_root`”. Defaults to `None`.
- **new\_prefix** (*str | None*) – If specified, adds this prefix to the file names. This also prevents any inferences that might be made via “`new_root`”. Defaults to `None`.
- **absolute** (*bool*) – if `True`, file names are stored as absolute paths, otherwise they are relative to the new image root. Defaults to `False`.
- **check** (*bool*) – if `True`, checks that the images all exist. Defaults to `True`.
- **safe** (*bool*) – if `True`, does not overwrite values until all checks pass. Defaults to `True`.
- **verbose** (*int*) – verbosity level, default=0.

#### CommandLine

```
xdotest -m kwcoco.coco_dataset MixinCocoExtras.rerooot
```

---

#### Todo:

- [ ] Incorporate maximum ordered subtree embedding?
- 

#### Example

```
>>> import kwCOCO
>>> def report(dset, name):
>>>     gid = 1
>>>     abs_fpath = dset.get_image_fpath(gid)
>>>     rel_fpath = dset.index.imgs[gid]['file_name']
>>>     color = 'green' if exists(abs_fpath) else 'red'
>>>     print('strategy_name = {!r}'.format(name))
>>>     print(ub.color_text('abs_fpath = {!r}'.format(abs_fpath), color))
```

(continues on next page)

(continued from previous page)

```
>>>     print('rel_fpath = {!r}'.format(rel_fpath))
>>> dset = self = kwcoco.CocoDataset.demo()
>>> # Change base relative directory
>>> bundle_dpath = ub.expandpath('~')
>>> print('ORIG self.imgs = {!r}'.format(self.imgs))
>>> print('ORIG dset.bundle_dpath = {!r}'.format(dset.bundle_dpath))
>>> print('NEW bundle_dpath      = {!r}'.format(bundle_dpath))
>>> self.reroot(bundle_dpath)
>>> report(self, 'self')
>>> print('NEW self.imgs = {!r}'.format(self.imgs))
>>> assert self.imgs[1]['file_name'].startswith('.cache')
```

```
>>> # Use absolute paths
>>> self.reroot(absolute=True)
>>> assert self.imgs[1]['file_name'].startswith(bundle_dpath)
```

```
>>> # Switch back to relative paths
>>> self.reroot()
>>> assert self.imgs[1]['file_name'].startswith('.cache')
```

## Example

```
>>> # demo with auxiliary data
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('shapes8', aux=True)
>>> bundle_dpath = ub.expandpath('~')
>>> print(self.imgs[1]['file_name'])
>>> print(self.imgs[1]['auxiliary'][0]['file_name'])
>>> self.reroot(new_root=bundle_dpath)
>>> print(self.imgs[1]['file_name'])
>>> print(self.imgs[1]['auxiliary'][0]['file_name'])
>>> assert self.imgs[1]['file_name'].startswith('.cache')
>>> assert self.imgs[1]['auxiliary'][0]['file_name'].startswith('.cache')
```

### **property data\_root**

In the future we will deprecate data\_root for bundle\_dpath

### **property img\_root**

In the future we will deprecate img\_root for bundle\_dpath

### **property data\_fpath**

data\_fpath is an alias of fpath

## **class kwcoco.coco\_dataset.MixinCocoObjects**

Bases: `object`

Expose methods to construct object lists / groups.

This is an alternative vectorized ORM-like interface to the coco dataset

`annots(annot_ids=None, image_id=None, trackid=None, aids=None, gid=None)`

Return vectorized annotation objects

**Parameters**

- **annot\_ids** (*List[int] | None*) – annotation ids to reference, if unspecified all annotations are returned. An alias is “aids”, which may be removed in the future.
- **image\_id** (*int | None*) – return all annotations that belong to this image id. Mutually exclusive with other arguments. An alias is “gids”, which may be removed in the future.
- **trackid** (*int | None*) – return all annotations that belong to this track. mutually exclusive with other arguments.

**Returns**

vectorized annotation object

**Return type***kwcoco.coco\_objectsId.Annots***Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> annots = self.annots()
>>> print(annots)
<Annots(num=11)>
>>> sub_annots = annots.take([1, 2, 3])
>>> print(sub_annots)
<Annots(num=3)>
>>> print(ub.repr2(sub_annots.get('bbox', None)))
[
    [350, 5, 130, 290],
    None,
    None,
]
```

**images**(*image\_ids=None, video\_id=None, names=None, gids=None, vidid=None*)

Return vectorized image objects

**Parameters**

- **image\_ids** (*List[int] | None*) – image ids to reference, if unspecified all images are returned. An alias is *gids*.
- **video\_id** (*int | None*) – returns all images that belong to this video id. mutually exclusive with *image\_ids* arg.
- **names** (*List[str] | None*) – lookup images by their names.

**Returns**

vectorized image object

**Return type***kwcoco.coco\_objectsId.Images*

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> images = self.images()
>>> print(images)
<Images(num=3)>
```

```
>>> self = kwcoco.CocoDataset.demo('vidshapes2')
>>> video_id = 1
>>> images = self.images(video_id=video_id)
>>> assert all(v == video_id for v in images.lookup('video_id'))
>>> print(images)
<Images(num=2)>
```

### `categories(category_ids=None, cids=None)`

Return vectorized category objects

#### Parameters

`category_ids` (*List[int] | None*) – category ids to reference, if unspecified all categories are returned. The `cids` argument is an alias.

#### Returns

vectorized category object

#### Return type

*kwcoco.coco\_objects1d.Categories*

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> categories = self.categories()
>>> print(categories)
<Categories(num=8)>
```

### `videos(video_ids=None, names=None, vidids=None)`

Return vectorized video objects

#### Parameters

- `video_ids` (*List[int] | None*) – video ids to reference, if unspecified all videos are returned. The `vidids` argument is an alias. Mutually exclusive with other args.
- `names` (*List[str] | None*) – lookup videos by their name. Mutually exclusive with other args.

#### Returns

vectorized video object

#### Return type

*kwcoco.coco\_objects1d.Videos*

---

#### Todo:

- [ ] This conflicts with what should be the property that should redirect to `index.videos`, we should resolve this somehow. E.g. all other main members of the index (anns, imgs, cats) have a toplevel dataset property, we don't have one for videos because the name we would pick conflicts with this.
- 

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('vidshapes2')
>>> videos = self.videos()
>>> print(videos)
>>> videos.lookup('name')
>>> videos.lookup('id')
>>> print('videos objs = {}'.format(ub.repr2(videos.objs[0:2], nl=1)))
```

`class kwcoco.coco_dataset.MixinCocoStats`

Bases: `object`

Methods for getting stats about the dataset

**property n\_annot**

The number of annotations in the dataset

**property n\_images**

The number of images in the dataset

**property n\_cats**

The number of categories in the dataset

**property n\_videos**

The number of videos in the dataset

**category\_annotation\_frequency()**

Reports the number of annotations of each category

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> hist = self.category_annotation_frequency()
>>> print(ub.repr2(hist))
{
    'astroturf': 0,
    'human': 0,
    'astronaut': 1,
    'astronomer': 1,
    'helmet': 1,
    'rocket': 1,
    'mouth': 2,
    'star': 5,
}
```

**conform(\*\*config)**

Make the COCO file conform a stricter spec, infers attributes where possible.

Corresponds to the `kwcoco conform` CLI tool.

**KWArgs:****\*\*config :**

- pycocotools\_info (default=True): returns info required by pycocotools
- ensure\_imgsize (default=True): ensure image size is populated
- mmlab (default=False): if True tries to convert data to be compatible with open-mmlab tooling.
- legacy (default=False): if True tries to convert data structures to items compatible with the original pycocotools spec
- workers (int): number of parallel jobs for IO tasks

**Example**

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('shapes8')
>>> dset.index.imgs[1].pop('width')
>>> dset.conform(legacy=True)
>>> assert 'width' in dset.index.imgs[1]
>>> assert 'area' in dset.index.anns[1]
```

**validate(\*\*config)**

Performs checks on this coco dataset.

Corresponds to the `kwcoco validate` CLI tool.

**Parameters**

- \*\*config** – schema (default=True): if True, validate the json-schema
- unique (default=True): if True, validate unique secondary keys
- missing (default=True): if True, validate registered files exist
- corrupted (default=False): if True, validate data in registered files
- channels (default=True): if True, validate that channels in auxiliary/asset items are all unique.
- require\_relative (default=False): if True, causes validation to fail if paths are non-portable, i.e. all paths must be relative to the bundle directory. if>0, paths must be relative to bundle root. if>1, paths must be inside bundle root.
- img\_attrs (default='warn'): if truthy, check that image attributes contain width and height entries. If 'warn', then warn if they do not exist. If 'error', then fail.
- verbose (default=1): verbosity flag
- fastfail (default=False): if True raise errors immediately

**Returns****result containing keys -**

- status (bool): False if any errors occurred
- errors (List[str]): list of all error messages missing
- (List): List of any missing images corrupted
- (List): List of any corrupted images

**Return type**

dict

**SeeAlso:**`_check_integrity()` - performs internal checks**Example**

```
>>> import kwCOCO
>>> self = kwCOCO.CocoDataset.demo()
>>> import pytest
>>> with pytest.warns(UserWarning):
>>>     result = self.validate()
>>> assert not result['errors']
>>> assert result['warnings']
```

**stats(\*\*kwargs)**

Compute summary statistics to describe the dataset at a high level

This function corresponds to `kwCOCO.cli.coco_stats`.

**KWargs:**

`basic(bool): return basic stats'`, default=True  
`extended(bool): return extended stats'`, default=True  
`cat-freq(bool): return category frequency stats'`, default=True  
`boxes(bool): return bounding box stats'`, default=False

`annot_attrs(bool): return annotation attribute information'`, default=True  
`image_attrs(bool): return image attribute information'`, default=True

**Returns**

info

**Return type**

dict

**basic\_stats()**

Reports number of images, annotations, and categories.

**SeeAlso:**

`kwCOCO.coco_dataset.MixinCocoStats.basic_stats()`      `kwCOCO.coco_dataset.MixinCocoStats.extended_stats()`

**Example**

```
>>> import kwCOCO
>>> self = kwCOCO.CocoDataset.demo()
>>> print(ub.repr2(self.basic_stats()))
{
    'n_annts': 11,
    'n_imgs': 3,
    'n_videos': 0,
    'n_cats': 8,
}
```

```
>>> from kwcoco.demo.toydata_video import random_video_dset
>>> dset = random_video_dset(render=True, num_frames=2, num_tracks=10, rng=0)
>>> print(ub.repr2(dset.basic_stats()))
{
    'n_anns': 20,
    'n_imgs': 2,
    'n_videos': 1,
    'n_cats': 3,
}
```

**extended\_stats()**

Reports number of images, annotations, and categories.

**SeeAlso:**

<i>kwcoco.coco_dataset.MixinCocoStats.basic_stats()</i>	<i>kwcoco.coco_dataset.</i>
<i>MixinCocoStats.extended_stats()</i>	

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> print(ub.repr2(self.extended_stats()))
```

**boxsize\_stats(anchors=None, perclass=True, gids=None, aids=None, verbose=0, clusterkw={}, statskw={})**

Compute statistics about bounding box sizes.

Also computes anchor boxes using kmeans if anchors is specified.

**Parameters**

- **anchors** (*int | None*) – if specified also computes box anchors via KMeans clustering
- **perclass** (*bool*) – if True also computes stats for each category
- **gids** (*List[int] | None*) – if specified only compute stats for these image ids. Defaults to None.
- **aids** (*List[int] | None*) – if specified only compute stats for these annotation ids. Defaults to None.
- **verbose** (*int*) – verbosity level
- **clusterkw** (*dict*) – kwargs for `sklearn.cluster.KMeans` used if computing anchors.
- **statskw** (*dict*) – kwargs for `kwarray.stats_dict()`

**Returns**

Stats are returned in width-height format.

**Return type**

`Dict[str, Dict[str, Dict | ndarray]]`

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('shapes32')
>>> infos = self.boxsize_stats(anchors=4, perclass=False)
>>> print(ub.repr2(infos, nl=-1, precision=2))
```

```
>>> infos = self.boxsize_stats(gids=[1], statskw=dict(median=True))
>>> print(ub.repr2(infos, nl=-1, precision=2))
```

### `find_representative_images(gids=None)`

Find images that have a wide array of categories.

Attempt to find the fewest images that cover all categories using images that contain both a large and small number of annotations.

#### Parameters

`gids (None | List)` – Subset of image ids to consider when finding representative images. Uses all images if unspecified.

#### Returns

list of image ids determined to be representative

#### Return type

List

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> gids = self.find_representative_images()
>>> print('gids = {!r}'.format(gids))
>>> gids = self.find_representative_images([3])
>>> print('gids = {!r}'.format(gids))
```

```
>>> self = kwcoco.CocoDataset.demo('shapes8')
>>> gids = self.find_representative_images()
>>> print('gids = {!r}'.format(gids))
>>> valid = {7, 1}
>>> gids = self.find_representative_images(valid)
>>> assert valid.issuperset(gids)
>>> print('gids = {!r}'.format(gids))
```

## `class kwcoco.coco_dataset.MixinCocoDraw`

Bases: `object`

Matplotlib / display functionality

### `draw_image(gid, channels=None)`

Use kwimage to draw all annotations on an image and return the pixels as a numpy array.

#### Parameters

- `gid (int)` – image id to draw
- `channels (kwcoco.ChannelSpec)` – the channel to draw on

**Returns**

canvas

**Return type**

ndarray

**SeeAlso**

`kwcoco.coco_dataset.MixinCocoDraw.draw_image()` `kwcoco.coco_dataset.MixinCocoDraw.show_image()`

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('shapes8')
>>> self.draw_image(1)
>>> # Now you can dump the annotated image to disk / whatever
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> kwplot.imshow(canvas)
```

**show\_image**(*gid=None*, *aids=None*, *aid=None*, *channels=None*, *setlim=None*, *\*\*kwargs*)

Use matplotlib to show an image with annotations overlaid

**Parameters**


- **gid** (*int | None*) – image id to show
- **aids** (*list | None*) – aids to highlight within the image
- **aid** (*int | None*) – a specific aid to focus on. If gid is not give, look up gid based on this aid.
- **setlim** (*None | str*) – if ‘image’ sets the limit to the image extent
- **\*\*kwargs** – show\_annot, show\_aid, show\_catname, show\_kpname, show\_segmentation, title, show\_gid, show\_filename, show\_boxes,

**SeeAlso**

`kwcoco.coco_dataset.MixinCocoDraw.draw_image()` `kwcoco.coco_dataset.MixinCocoDraw.show_image()`

**Example**

```
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-msi')
>>> # xdoctest: +REQUIRES(--show)
>>> import kwplot
>>> kwplot.autopl()
>>> # xdoctest: -REQUIRES(--show)
>>> dset.show_image(gid=1, channels='B8')
>>> # xdoctest: +REQUIRES(--show)
>>> kwplot.show_if_requested()
```

**class kwCOCO.coco\_dataset.MixinCocoAddRemove**Bases: `object`

Mixin functions to dynamically add / remove annotations images and categories while maintaining lookup indexes.

**add\_video(name, id=None, \*\*kw)**

Register a new video with the dataset

**Parameters**

- **name** (`str`) – Unique name for this video.
- **id** (`None` | `int`) – ADVANCED. Force using this image id.
- **\*\*kw** – stores arbitrary key/value pairs in this new video

**Returns**

the video id assigned to the new video

**Return type**`int`

## Example

```
>>> import kwCOCO
>>> self = kwCOCO.CocoDataset()
>>> print('self.index.videos = {}'.format(ub.repr2(self.index.videos, nl=1)))
>>> print('self.index.imgs = {}'.format(ub.repr2(self.index.imgs, nl=1)))
>>> print('self.index.vidid_to_gids = {!r}'.format(self.index.vidid_to_gids))
```

```
>>> vidid1 = self.add_video('foo', id=3)
>>> vidid2 = self.add_video('bar')
>>> vidid3 = self.add_video('baz')
>>> print('self.index.videos = {}'.format(ub.repr2(self.index.videos, nl=1)))
>>> print('self.index.imgs = {}'.format(ub.repr2(self.index.imgs, nl=1)))
>>> print('self.index.vidid_to_gids = {!r}'.format(self.index.vidid_to_gids))
```

```
>>> gid1 = self.add_image('foo1.jpg', video_id=vidid1, frame_index=0)
>>> gid2 = self.add_image('foo2.jpg', video_id=vidid1, frame_index=1)
>>> gid3 = self.add_image('foo3.jpg', video_id=vidid1, frame_index=2)
>>> gid4 = self.add_image('bar1.jpg', video_id=vidid2, frame_index=0)
>>> print('self.index.videos = {}'.format(ub.repr2(self.index.videos, nl=1)))
>>> print('self.index.imgs = {}'.format(ub.repr2(self.index.imgs, nl=1)))
>>> print('self.index.vidid_to_gids = {!r}'.format(self.index.vidid_to_gids))
```

```
>>> self.remove_images([gid2])
>>> print('self.index.vidid_to_gids = {!r}'.format(self.index.vidid_to_gids))
```

### `add_image(file_name=None, id=None, **kw)`

Register a new image with the dataset

#### Parameters

- **file\_name** (*str* | *None*) – relative or absolute path to image. if not given, then “name” must be specified and we will expect that “auxiliary” assets are eventually added.
- **id** (*None* | *int*) – ADVANCED. Force using this image id.
- **name** (*str*) – a unique key to identify this image
- **width** (*int*) – base width of the image
- **height** (*int*) – base height of the image
- **channels** (*ChannelSpec*) – specification of base channels. Only relevant if file\_name is given.
- **auxiliary** (*List[Dict]*) – specification of auxiliary assets. See CocoImage.add\_auxiliary\_item for details
- **video\_id** (*int*) – id of parent video, if applicable
- **frame\_index** (*int*) – frame index in parent video
- **timestamp** (*number* | *str*) – timestamp of frame index
- **warp\_img\_to\_vid** (*Dict*) – this transform is used to align the image to a video if it belongs to one.
- **\*\*kw** – stores arbitrary key/value pairs in this new image

**Returns**

the image id assigned to the new image

**Return type**

int

**SeeAlso:**

`add_image()` `add_images()` `ensure_image()`

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> import kwimage
>>> gname = kwimage.grab_test_image_fpath('paraview')
>>> gid = self.add_image(gname)
>>> assert self.imgs[gid]['file_name'] == gname
```

`add_auxiliary_item(gid, file_name=None, channels=None, **kwargs)`

Adds an auxiliary / asset item to the image dictionary.

**Parameters**

- **gid** (int) – The image id to add the auxiliary/asset item to.
- **file\_name** (str | None) – The name of the file relative to the bundle directory. If unspecified, imdata must be given.
- **channels** (str | `kwcoco.FusedChannelSpec`) – The channel code indicating what each of the bands represents. These channels should be disjoint wrt to the existing data in this image (this is not checked).
- **\*\*kwargs** – See `CocoImage.add_auxiliary_item()` for more details

**Example**

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset()
>>> gid = dset.add_image(name='my_image_name', width=200, height=200)
>>> dset.add_auxiliary_item(gid, 'path/fake_B0.tif', channels='B0',
>>>                               width=200, height=200,
>>>                               warp_aux_to_img={'scale': 1.0})
```

`add_annotation(image_id, category_id=None, bbox=NoParam, segmentation=NoParam, keypoints=NoParam, id=None, **kw)`

Register a new annotation with the dataset

**Parameters**

- **image\_id** (int) – image\_id the annoatation is added to.
- **category\_id** (int | None) – category\_id for the new annotaiton
- **bbox** (list | `kwimage.Boxes`) – bounding box in xywh format

- **segmentation** (*Dict* | *List* | *Any*) – keypoints in some accepted format, see `kwimage.Mask.to_coco()` and `kwimage.MultiPolygon.to_coco()`. Extended types: *MaskLike* | *MultiPolygonLike*.
- **keypoints** (*Any*) – keypoints in some accepted format, see `kwimage.Keypoints.to_coco()`. Extended types: *KeypointsLike*.
- **id** (*None* | *int*) – Force using this annotation id. Typically you should NOT specify this. A new unused id will be chosen and returned.
- **\*\*kw** – stores arbitrary key/value pairs in this new image, Common respected key/values include but are not limited to the following: `track_id` (*int* | *str*): some value used to associate annotations that belong to the same “track”. `score` : *float* `prob` : *List[float]* `weight` (*float*): a weight, usually used to indicate if a ground truth annotation is difficult / important. This generalizes standard “`is_hard`” or “`ignore`” attributes in other formats. `caption` (*str*): a text caption for this annotation

**Returns**

the annotation id assigned to the new annotation

**Return type**

*int*

**SeeAlso:**

`kwcoco.coco_dataset.MixinCocoAddRemove.add_annotation()`   `kwcoco.coco_dataset.MixinCocoAddRemove.add_annotations()`

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> image_id = 1
>>> cid = 1
>>> bbox = [10, 10, 20, 20]
>>> aid = self.add_annotation(image_id, cid, bbox)
>>> assert self.anns[aid]['bbox'] == bbox
```

**Example**

```
>>> import kwimage
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> new_det = kwimage.Detections.random(1, segmentations=True, keypoints=True)
>>> # kwimage datastructures have methods to convert to coco recognized formats
>>> new_ann_data = list(new_det.to_coco(style='new'))[0]
>>> image_id = 1
>>> aid = self.add_annotation(image_id, **new_ann_data)
>>> # Lookup the annotation we just added
>>> ann = self.index.anns[aid]
>>> print('ann = {}'.format(ub.repr2(ann, nl=-2)))
```

## Example

```
>>> # Attempt to add annot without a category or bbox
>>> import kwCOCO
>>> self = kwCOCO.CocoDataset.demo()
>>> image_id = 1
>>> aid = self.add_annotation(image_id)
>>> assert None in self.index.cid_to_aids
```

## Example

```
>>> # Attempt to add annot using various styles of kwimage structures
>>> import kwCOCO
>>> import kwimage
>>> self = kwCOCO.CocoDataset.demo()
>>> image_id = 1
>>> #--
>>> kw = {}
>>> kw['segmentation'] = kwimage.Polygon.random()
>>> kw['keypoints'] = kwimage.Points.random()
>>> aid = self.add_annotation(image_id, **kw)
>>> ann = self.index.anns[aid]
>>> print('ann = {}'.format(ub.repr2(ann, nl=2)))
>>> #--
>>> kw = {}
>>> kw['segmentation'] = kwimage.Mask.random()
>>> aid = self.add_annotation(image_id, **kw)
>>> ann = self.index.anns[aid]
>>> assert ann.get('segmentation', None) is not None
>>> print('ann = {}'.format(ub.repr2(ann, nl=2)))
>>> #--
>>> kw = {}
>>> kw['segmentation'] = kwimage.Mask.random().to_array_rle()
>>> aid = self.add_annotation(image_id, **kw)
>>> ann = self.index.anns[aid]
>>> assert ann.get('segmentation', None) is not None
>>> print('ann = {}'.format(ub.repr2(ann, nl=2)))
>>> #--
>>> kw = {}
>>> kw['segmentation'] = kwimage.Polygon.random().to_coco()
>>> kw['keypoints'] = kwimage.Points.random().to_coco()
>>> aid = self.add_annotation(image_id, **kw)
>>> ann = self.index.anns[aid]
>>> assert ann.get('segmentation', None) is not None
>>> assert ann.get('keypoints', None) is not None
>>> print('ann = {}'.format(ub.repr2(ann, nl=2)))
```

**add\_category**(*name*, *supercategory*=None, *id*=None, \*\**kw*)

Register a new category with the dataset

### Parameters

- **name** (*str*) – name of the new category

- **supercategory** (*str | None*) – parent of this category
- **id** (*int | None*) – use this category id, if it was not taken
- **\*\*kw** – stores arbitrary key/value pairs in this new image

**Returns**

the category id assigned to the new category

**Return type**

`int`

**SeeAlso:**

`kwCOCO.coco_dataset.MixinCocoAddRemove.add_category()`      `kwCOCO.coco_dataset.MixinCocoAddRemove.ensure_category()`

**Example**

```
>>> import kwCOCO
>>> self = kwCOCO.CocoDataset.demo()
>>> prev_n_cats = self.n_cats
>>> cid = self.add_category('dog', supercategory='object')
>>> assert self.cats[cid]['name'] == 'dog'
>>> assert self.n_cats == prev_n_cats + 1
>>> import pytest
>>> with pytest.raises(ValueError):
>>>     self.add_category('dog', supercategory='object')
```

**ensure\_image(*file\_name*, *id=None*, **\*\*kw**)**

Register an image if it is new or returns an existing id.

Like `kwCOCO.coco_dataset.MixinCocoAddRemove.add_image()`, but returns the existing image id if it already exists instead of failing. In this case all metadata is ignored.

**Parameters**

- **file\_name** (*str*) – relative or absolute path to image
- **id** (*None | int*) – ADVANCED. Force using this image id.
- **\*\*kw** – stores arbitrary key/value pairs in this new image

**Returns**

the existing or new image id

**Return type**

`int`

**SeeAlso:**

`kwCOCO.coco_dataset.MixinCocoAddRemove.add_image()`      `kwCOCO.coco_dataset.MixinCocoAddRemove.add_images()`      `kwCOCO.coco_dataset.MixinCocoAddRemove.ensure_image()`

**ensure\_category(*name*, *supercategory=None*, *id=None*, **\*\*kw**)**

Register a category if it is new or returns an existing id.

Like `kwCOCO.coco_dataset.MixinCocoAddRemove.add_category()`, but returns the existing category id if it already exists instead of failing. In this case all metadata is ignored.

**Returns**

the existing or new category id

**Return type**

int

**SeeAlso:**

`kwcoco.coco_dataset.MixinCocoAddRemove.add_category()`    `kwcoco.coco_dataset.MixinCocoAddRemove.ensure_category()`

**add\_annotations(*anns*)**

Faster less-safe multi-item alternative to add\_annotation.

We assume the annotations are well formatted in kwcoco compliant dictionaries, including the “id” field. No validation checks are made when calling this function.

**Parameters**

*anns* (*List[Dict]*) – list of annotation dictionaries

**SeeAlso:**

`add_annotation()` `add_annotations()`

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> anns = [self.anns[aid] for aid in [2, 3, 5, 7]]
>>> self.remove_annotations(anns)
>>> assert self.n_anno == 7 and self._check_index()
>>> self.add_annotations(anns)
>>> assert self.n_anno == 11 and self._check_index()
```

**add\_images(*imgs*)**

Faster less-safe multi-item alternative

We assume the images are well formatted in kwcoco compliant dictionaries, including the “id” field. No validation checks are made when calling this function.

---

**Note:** THIS FUNCTION WAS DESIGNED FOR SPEED, AS SUCH IT DOES NOT CHECK IF THE IMAGE-IDS OR FILE\_NAMES ARE DUPLICATED AND WILL BLINDLY ADD DATA EVEN IF IT IS BAD. THE SINGLE IMAGE VERSION IS SLOWER BUT SAFER.

---

**Parameters**

*imgs* (*List[Dict]*) – list of image dictionaries

**SeeAlso:**

`kwcoco.coco_dataset.MixinCocoAddRemove.add_image()`    `kwcoco.coco_dataset.MixinCocoAddRemove.add_images()`    `kwcoco.coco_dataset.MixinCocoAddRemove.ensure_image()`

**Example**

```
>>> import kwcoco
>>> imgs = kwcoco.CocoDataset.demo().dataset['images']
>>> self = kwcoco.CocoDataset()
>>> self.add_images(imgs)
>>> assert self.n_images == 3 and self._check_index()
```

**clear\_images()**

Removes all images and annotations (but not categories)

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> self.clear_images()
>>> print(ub.repr2(self.basic_stats(), nobr=1, nl=0, si=1))
n_anns: 0, n_imgs: 0, n_videos: 0, n_cats: 8
```

**clear\_annotations()**

Removes all annotations (but not images and categories)

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> self.clear_annotations()
>>> print(ub.repr2(self.basic_stats(), nobr=1, nl=0, si=1))
n_anns: 0, n_imgs: 3, n_videos: 0, n_cats: 8
```

**remove\_annotation(*aid\_or\_ann*)**

Remove a single annotation from the dataset

If you have multiple annotations to remove its more efficient to remove them in batch with [\*kwcoco.coco\\_dataset.MixinCocoAddRemove.remove\\_annotations\(\)\*](#)

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> aids_or_anns = [self.anns[2], 3, 4, self.anns[1]]
>>> self.remove_annotations(aids_or_anns)
>>> assert len(self.dataset['annotations']) == 7
>>> self._check_index()
```

**remove\_annotations(*aids\_or\_anns*, *verbose*=0, *safe*=True)**

Remove multiple annotations from the dataset.

**Parameters**

- **anns\_or\_aids** (*List*) – list of annotation dicts or ids

- **safe** (*bool*) – if True, we perform checks to remove duplicates and non-existing identifiers.  
Defaults to True.

**Returns**

num\_removed: information on the number of items removed

**Return type**

Dict

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> prev_n_anno = self.n_anno
>>> aids_or_anno = [self.anno[2], 3, 4, self.anno[1]]
>>> self.remove_annotation(aids_or_anno) # xdoc: +IGNORE_WANT
{'annotations': 4}
>>> assert len(self.dataset['annotations']) == prev_n_anno - 4
>>> self._check_index()
```

**remove\_categories**(*cat\_identifiers*, *keep\_anno=False*, *verbose=0*, *safe=True*)

Remove categories and all annotations in those categories.

Currently does not change any hierarchy information

**Parameters**

- **cat\_identifiers** (*List*) – list of category dicts, names, or ids
- **keep\_anno** (*bool*) – if True, keeps annotations, but removes category labels. Defaults to False.
- **safe** (*bool*) – if True, we perform checks to remove duplicates and non-existing identifiers.  
Defaults to True.

**Returns**

num\_removed: information on the number of items removed

**Return type**

Dict

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> cat_identifiers = [self.cat[1], 'rocket', 3]
>>> self.remove_categories(cat_identifiers)
>>> assert len(self.dataset['categories']) == 5
>>> self._check_index()
```

**remove\_images**(*gids\_or\_imgs*, *verbose=0*, *safe=True*)

Remove images and any annotations contained by them

**Parameters**

- **gids\_or\_imgs** (*List*) – list of image dicts, names, or ids
- **safe** (*bool*) – if True, we perform checks to remove duplicates and non-existing identifiers.

**Returns**

num\_removed: information on the number of items removed

**Return type**

Dict

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> assert len(self.dataset['images']) == 3
>>> gids_or_imgs = [self.imgs[2], 'astro.png']
>>> self.remove_images(gids_or_imgs) # xdoc: +IGNORE_WANT
{'annotations': 11, 'images': 2}
>>> assert len(self.dataset['images']) == 1
>>> self._check_index()
>>> gids_or_imgs = [3]
>>> self.remove_images(gids_or_imgs)
>>> assert len(self.dataset['images']) == 0
>>> self._check_index()
```

**remove\_videos(vidids\_or\_videos, verbose=0, safe=True)**

Remove videos and any images / annotations contained by them

**Parameters**

- **vidids\_or\_videos** (*List*) – list of video dicts, names, or ids
- **safe** (*bool*) – if True, we perform checks to remove duplicates and non-existing identifiers.

**Returns**

num\_removed: information on the number of items removed

**Return type**

Dict

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('vidshapes8')
>>> assert len(self.dataset['videos']) == 8
>>> vidids_or_videos = [self.dataset['videos'][0]['id']]
>>> self.remove_videos(vidids_or_videos) # xdoc: +IGNORE_WANT
{'annotations': 4, 'images': 2, 'videos': 1}
>>> assert len(self.dataset['videos']) == 7
>>> self._check_index()
```

**remove\_annotation\_keypoints(kp\_identifiers)**

Removes all keypoints with a particular category

**Parameters**

**kp\_identifiers** (*List*) – list of keypoint category dicts, names, or ids

**Returns**

num\_removed: information on the number of items removed

**Return type**

Dict

**remove\_keypoint\_categories(*kp\_identifiers*)**

Removes all keypoints of a particular category as well as all annotation keypoints with those ids.

**Parameters**

**kp\_identifiers** (*List*) – list of keypoint category dicts, names, or ids

**Returns**

num\_removed: information on the number of items removed

**Return type**

Dict

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('shapes', rng=0)
>>> kp_identifiers = ['left_eye', 'mid_tip']
>>> remove_info = self.remove_keypoint_categories(kp_identifiers)
>>> print('remove_info = {!r}'.format(remove_info))
>>> # FIXME: for whatever reason demodata generation is not determinstic when
>>> # seeded
>>> # assert remove_info == {'keypoint_categories': 2, 'annotation_keypoints': 16,
>>> # 'reflection_ids': 1}
>>> assert self._resolve_to_kpcat('right_eye')['reflection_id'] is None
```

**set\_annotation\_category(*aid\_or\_ann, cid\_or\_cat*)**

Sets the category of a single annotation

**Parameters**

- **aid\_or\_ann** (*dict | int*) – annotation dict or id
- **cid\_or\_cat** (*dict | int*) – category dict or id

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> old_freq = self.category_annotation_frequency()
>>> aid_or_ann = aid = 2
>>> cid_or_cat = new_cid = self.ensure_category('kitten')
>>> self.set_annotation_category(aid, new_cid)
>>> new_freq = self.category_annotation_frequency()
>>> print('new_freq = {}'.format(ub.repr2(new_freq, nl=1)))
>>> print('old_freq = {}'.format(ub.repr2(old_freq, nl=1)))
>>> assert sum(new_freq.values()) == sum(old_freq.values())
>>> assert new_freq['kitten'] == 1
```

**class kwcoco.coco\_dataset.CocoIndex**

Bases: *object*

Fast lookup index for the COCO dataset with dynamic modification

## Variables

- **imgs** (*Dict[int, dict]*) – mapping between image ids and the image dictionaries
- **anns** (*Dict[int, dict]*) – mapping between annotation ids and the annotation dictionaries
- **cats** (*Dict[int, dict]*) – mapping between category ids and the category dictionaries
- **kpcats** (*Dict[int, dict]*) – mapping between keypoint category ids and keypoint category dictionaries
- **gid\_to\_aids** (*Dict[int, List[int]]*) – mapping between an image-id and annotation-ids that belong to it
- **cid\_to\_aids** (*Dict[int, List[int]]*) – mapping between an category-id and annotation-ids that belong to it
- **cid\_to\_gids** (*Dict[int, List[int]]*) – mapping between an category-id and image-ids that contain at least one annotation with this category id.
- **trackid\_to\_aids** (*Dict[int, List[int]]*) – mapping between a track-id and annotation-ids that belong to it
- **vidid\_to\_gids** (*Dict[int, List[int]]*) – mapping between an video-id and images-ids that belong to it
- **name\_to\_video** (*Dict[str, dict]*) – mapping between a video name and the video dictionary.
- **name\_to\_cat** (*Dict[str, dict]*) – mapping between a category name and the category dictionary.
- **name\_to\_img** (*Dict[str, dict]*) – mapping between a image name and the image dictionary.
- **file\_name\_to\_img** (*Dict[str, dict]*) – mapping between a image file\_name and the image dictionary.

**property cid\_to\_gids**

**Example:**

```
>>> import kwCOCO
>>> self = dset = kwCOCO.CocoDataset()
>>> self.index.cid_to_gids
```

**clear()**

**build(parent)**

Build all id-to-obj reverse indexes from scratch.

**Parameters**

**parent** (*kwCOCO.CocoDataset*) – the dataset to index

**Notation:**

aid - Annotation ID  
gid - imaGe ID  
cid - Category ID  
vidid - Video ID

## Example

```
>>> import kwcoco
>>> parent = kwcoco.CocoDataset.demo('vidshapes1', num_frames=4, rng=1)
>>> index = parent.index
>>> index.build(parent)
```

```
class kwcoco.coco_dataset.MixinCocoIndex
```

Bases: `object`

Give the dataset top level access to index attributes

```
property anns
```

```
property imgs
```

```
property cats
```

```
property gid_to_aids
```

```
property cid_to_aids
```

```
property name_to_cat
```

```
class kwcoco.coco_dataset.CocoDataset(data=None, tag=None, bundle_dpath=None, img_root=None,
                                         fname=None, autobuild=True)
```

Bases: `AbstractCocoDataset`, `MixinCocoAddRemove`, `MixinCocoStats`, `MixinCocoObjects`, `MixinCocoDraw`, `MixinCocoAccessors`, `MixinCocoExtras`, `MixinCocoIndex`, `MixinCocoDeprivate`, `NiceRepr`

The main coco dataset class with a json dataset backend.

## Variables

- **dataset** (`Dict`) – raw json data structure. This is the base dictionary that contains {‘annotations’: List, ‘images’: List, ‘categories’: List}
- **index** (`CocoIndex`) – an efficient lookup index into the coco data structure. The index defines its own attributes like `anns`, `cats`, `imgs`, `gid_to_aids`, `file_name_to_img`, etc. See `CocoIndex` for more details on which attributes are available.
- **fpath** (`PathLike` / `None`) – if known, this stores the filepath the dataset was loaded from
- **tag** (`str` / `None`) – A tag indicating the name of the dataset.
- **bundle\_dpath** (`PathLike` / `None`) – If known, this is the root path that all image file names are relative to. This can also be manually overwritten by the user.
- **hashid** (`str` / `None`) – If computed, this will be a hash uniquely identifying the dataset. To ensure this is computed see `kwcoco.coco_dataset.MixinCocoExtras._build_hashid()`.

## References

<http://cocodataset.org/#format> <http://cocodataset.org/#download>

## CommandLine

```
python -m kwCOCO.coco_dataset CocoDataset --show
```


## Example

```
>>> from kwCOCO.coco_dataset import demo_coco_data
>>> import kwCOCO
>>> import ubelt as ub
>>> # Returns a coco json structure
>>> dataset = demo_coco_data()
>>> # Pass the coco json structure to the API
>>> self = kwCOCO.CocoDataset(dataset, tag='demo')
>>> # Now you can access the data using the index and helper methods
>>> #
>>> # Start by looking up an image by its COCO id.
>>> image_id = 1
>>> img = self.index.imgs[image_id]
>>> print(ub.repr2(img, nl=1, sort=1))
{
    'file_name': 'astro.png',
    'id': 1,
    'url': 'https://i.imgur.com/KXhKM72.png',
}
>>> #
>>> # Use the (gid_to_aids) index to lookup annotations in the image
>>> annotation_id = sorted(self.index.gid_to_aids[image_id])[0]
>>> ann = self.index.anns[annotation_id]
>>> print(ub.repr2(ub.dict_diff(ann, {'segmentation'}), nl=1))
{
    'bbox': [10, 10, 360, 490],
    'category_id': 1,
    'id': 1,
    'image_id': 1,
    'keypoints': [247, 101, 2, 202, 100, 2],
}
>>> #
>>> # Use annotation category id to look up that information
>>> category_id = ann['category_id']
>>> cat = self.index.cats[category_id]
>>> print('cat = {}'.format(ub.repr2(cat, nl=1, sort=1)))
cat = {
    'id': 1,
    'name': 'astronaut',
    'supercategory': 'human',
}
>>> #
```

(continues on next page)

(continued from previous page)

```
>>> # Now play with some helper functions, like extended statistics
>>> extended_stats = self.extended_stats()
>>> # xdoctest: +IGNORE_WANT
>>> print('extended_stats = {}'.format(ub.repr2(extended_stats, nl=1, precision=2,
    sort=1)))
extended_stats = {
    'annots_per_img': {'mean': 3.67, 'std': 3.86, 'min': 0.00, 'max': 9.00, 'nMin': 1,
    'nMax': 1, 'shape': (3,)},
    'imgs_per_cat': {'mean': 0.88, 'std': 0.60, 'min': 0.00, 'max': 2.00, 'nMin': 2,
    'nMax': 1, 'shape': (8,)},
    'cats_per_img': {'mean': 2.33, 'std': 2.05, 'min': 0.00, 'max': 5.00, 'nMin': 1,
    'nMax': 1, 'shape': (3,)},
    'annots_per_cat': {'mean': 1.38, 'std': 1.49, 'min': 0.00, 'max': 5.00, 'nMin': 2,
    'nMax': 1, 'shape': (8,)},
    'imgs_per_video': {'empty_list': True},
}
>>> # You can "draw" a raster of the annotated image with cv2
>>> canvas = self.draw_image(2)
>>> # Or if you have matplotlib you can "show" the image with mpl objects
>>> # xdoctest: +REQUIRES(--show)
>>> from matplotlib import pyplot as plt
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(1, 2, 1)
>>> self.show_image(gid=2)
>>> ax2 = fig.add_subplot(1, 2, 2)
>>> ax2.imshow(canvas)
>>> ax1.set_title('show with matplotlib')
>>> ax2.set_title('draw with cv2')
>>> plt.show()
```

**property fpath**

In the future we will deprecate img\_root for bundle\_dpath

**classmethod from\_data(data, bundle\_dpath=None, img\_root=None)**

Constructor from a json dictionary

**classmethod from\_image\_paths(gpaths, bundle\_dpath=None, img\_root=None)**

Constructor from a list of images paths.

This is a convinience method.

**Parameters**

**gpaths** (*List[str]*) – list of image paths

**Example**

```
>>> import kwcoco
>>> coco_dset = kwcoco.CocoDataset.from_image_paths(['a.png', 'b.png'])
>>> assert coco_dset.n_images == 2
```

**classmethod from\_coco\_paths(fpaths, max\_workers=0, verbose=1, mode='thread', union='try')**

Constructor from multiple coco file paths.

Loads multiple coco datasets and unions the result

---

**Note:** if the union operation fails, the list of individually loaded files is returned instead.

---

### Parameters

- **fpaths** (*List[str]*) – list of paths to multiple coco files to be loaded and unioned.
- **max\_workers** (*int*) – number of worker threads / processes
- **verbose** (*int*) – verbosity level
- **mode** (*str*) – thread, process, or serial
- **union** (*str | bool*) – If True, unions the result datasets after loading. If False, just returns the result list. If ‘try’, then try to preform the union, but return the result list if it fails. Default=’try’

### copy()

Deep copies this object

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> new = self.copy()
>>> assert new.imgs[1] is new.dataset['images'][0]
>>> assert new.imgs[1] == self.dataset['images'][0]
>>> assert new.imgs[1] is not self.dataset['images'][0]
```

### dumps(*indent=None, newlines=False*)

Writes the dataset out to the json format

### Parameters

- **newlines** (*bool*) – if True, each annotation, image, category gets its own line
- **indent** (*int | str | None*) – indentation for the json file. See [json.dump\(\)](#) for details.
- **newlines** (*bool*) – if True, each annotation, image, category gets its own line.

---

**Note:**

**Using newlines=True is similar to:**

`print(ub.repr2(dset.dataset, nl=2, trailsep=False))` However, the above may not output valid json if it contains ndarrays.

---

## Example

```
>>> import kwcoco
>>> import json
>>> self = kwcoco.CocoDataset.demo()
>>> text = self.dumps(newlines=True)
>>> print(text)
>>> self2 = kwcoco.CocoDataset(json.loads(text), tag='demo2')
>>> assert self2.dataset == self.dataset
>>> assert self2.dataset is not self.dataset
```

```
>>> text = self.dumps(newlines=True)
>>> print(text)
>>> self2 = kwcoco.CocoDataset(json.loads(text), tag='demo2')
>>> assert self2.dataset == self.dataset
>>> assert self2.dataset is not self.dataset
```

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.coerce('vidshapes1-msi-multisensor', verbose=3)
>>> self.remove_annotations(self.annots())
>>> text = self.dumps(newlines=0, indent=' ')
>>> print(text)
>>> text = self.dumps(newlines=True, indent=' ')
>>> print(text)
```

**dump(file=None, indent=None, newlines=False, temp\_file=True, compress='auto')**

Writes the dataset out to the json format

### Parameters

- **file** (*PathLike* | *IO* | *None*) – Where to write the data. Can either be a path to a file or an open file pointer / stream. If unspecified, it will be written to the current `fpath` property.
- **indent** (*int* | *str* | *None*) – indentation for the json file. See `json.dump()` for details.
- **newlines** (*bool*) – if True, each annotation, image, category gets its own line.
- **temp\_file** (*bool* | *str*) – Argument to `safer.open()`. Ignored if `file` is not a *PathLike* object. Defaults to True.
- **compress** (*bool* | *str*) – if True, dumps the kwcoco file as a compressed zipfile. In this case a literal IO file object must be opened in binary write mode. If auto, then it will default to False unless it can introspect the file name and the name ends with .zip

## Example

```
>>> import kwcoco
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwcoco/demo/dump').ensuredir()
>>> dset = kwcoco.CocoDataset.demo()
>>> dset.fpath = dpath / 'my_coco_file.json'
>>> # Calling dump writes to the current fpath attribute.
>>> dset.dump()
>>> assert dset.dataset == kwcoco.CocoDataset(dset.fpath).dataset
>>> assert dset.dumps() == dset.fpath.read_text()
>>> #
>>> # Using compress=True can save a lot of space and it
>>> # is transparent when reading files via CocoDataset
>>> dset.dump(compress=True)
>>> assert dset.dataset == kwcoco.CocoDataset(dset.fpath).dataset
>>> assert dset.dumps() != dset.fpath.read_text(errors='replace')
```

## Example

```
>>> import kwcoco
>>> import ubelt as ub
>>> # Compression auto-defaults based on the file name.
>>> dpath = ub.Path.appdir('kwcoco/demo/dump').ensuredir()
>>> dset = kwcoco.CocoDataset.demo()
>>> fpath1 = dset.fpath = dpath / 'my_coco_file.zip'
>>> dset.dump()
>>> fpath2 = dset.fpath = dpath / 'my_coco_file.json'
>>> dset.dump()
>>> assert fpath1.read_bytes()[0:8] != fpath2.read_bytes()[0:8]
```

## union(\*, disjoint\_tracks=True, \*\*kwargs)

Merges multiple `CocoDataset` items into one. Names and associations are retained, but ids may be different.

### Parameters

- **\*others** – a series of CocoDatasets that we will merge. Note, if called as an instance method, the “self” instance will be the first item in the “others” list. But if called like a classmethod, “others” will be empty by default.
- **disjoint\_tracks (bool)** – if True, we will assume track-ids are disjoint and if two datasets share the same track-id, we will disambiguate them. Otherwise they will be copied over as-is. Defaults to True.
- **\*\*kwargs** – constructor options for the new merged CocoDataset

### Returns

a new merged coco dataset

### Return type

`kwcoco.CocoDataset`

## CommandLine

```
xdoctest -m kwcoco.coco_dataset CocoDataset.union
```

## Example

```
>>> import kwcoco
>>> # Test union works with different keypoint categories
>>> dset1 = kwcoco.CocoDataset.demo('shapes1')
>>> dset2 = kwcoco.CocoDataset.demo('shapes2')
>>> dset1.remove_keypoint_categories(['bot_tip', 'mid_tip', 'right_eye'])
>>> dset2.remove_keypoint_categories(['top_tip', 'left_eye'])
>>> dset_12a = kwcoco.CocoDataset.union(dset1, dset2)
>>> dset_12b = dset1.union(dset2)
>>> dset_21 = dset2.union(dset1)
>>> def add_hist(h1, h2):
>>>     return {k: h1.get(k, 0) + h2.get(k, 0) for k in set(h1) | set(h2)}
>>> kpfreq1 = dset1.keypoint_annotation_frequency()
>>> kpfreq2 = dset2.keypoint_annotation_frequency()
>>> kpfreq_want = add_hist(kpfreq1, kpfreq2)
>>> kpfreq_got1 = dset_12a.keypoint_annotation_frequency()
>>> kpfreq_got2 = dset_12b.keypoint_annotation_frequency()
>>> assert kpfreq_want == kpfreq_got1
>>> assert kpfreq_want == kpfreq_got2
```

```
>>> # Test disjoint gid datasets
>>> dset1 = kwcoco.CocoDataset.demo('shapes3')
>>> for new_gid, img in enumerate(dset1.dataset['images'], start=10):
>>>     for aid in dset1.gid_to_aids[img['id']]:
>>>         dset1.anns[aid]['image_id'] = new_gid
>>>     img['id'] = new_gid
>>> dset1.index.clear()
>>> dset1._build_index()
>>> # -----
>>> dset2 = kwcoco.CocoDataset.demo('shapes2')
>>> for new_gid, img in enumerate(dset2.dataset['images'], start=100):
>>>     for aid in dset2.gid_to_aids[img['id']]:
>>>         dset2.anns[aid]['image_id'] = new_gid
>>>     img['id'] = new_gid
>>> dset1.index.clear()
>>> dset2._build_index()
>>> others = [dset1, dset2]
>>> merged = kwcoco.CocoDataset.union(*others)
>>> print('merged = {!r}'.format(merged))
>>> print('merged imgs = {}'.format(ub.repr2(merged.imgs, nl=1)))
>>> assert set(merged.imgs) & set([10, 11, 12, 100, 101]) == set(merged.imgs)
```

```
>>> # Test data is not preserved
>>> dset2 = kwcoco.CocoDataset.demo('shapes2')
>>> dset1 = kwcoco.CocoDataset.demo('shapes3')
>>> others = (dset1, dset2)
```

(continues on next page)

(continued from previous page)

```
>>> cls = self = kwcoco.CocoDataset
>>> merged = cls.union(*others)
>>> print('merged = {!r}'.format(merged))
>>> print('merged imgs = {}'.format(ub.repr2(merged.imgs, nl=1)))
>>> assert set(merged.imgs) & set([1, 2, 3, 4, 5]) == set(merged.imgs)
```

```
>>> # Test track-ids are mapped correctly
>>> dset1 = kwcoco.CocoDataset.demo('vidshapes1')
>>> dset2 = kwcoco.CocoDataset.demo('vidshapes2')
>>> dset3 = kwcoco.CocoDataset.demo('vidshapes3')
>>> others = (dset1, dset2, dset3)
>>> for dset in others:
>>>     [a.pop('segmentation', None) for a in dset.index.anns.values()]
>>>     [a.pop('keypoints', None) for a in dset.index.anns.values()]
>>> cls = self = kwcoco.CocoDataset
>>> merged = cls.union(*others, disjoint_tracks=1)
>>> print('dset1.anns = {}'.format(ub.repr2(dset1.anns, nl=1)))
>>> print('dset2.anns = {}'.format(ub.repr2(dset2.anns, nl=1)))
>>> print('dset3.anns = {}'.format(ub.repr2(dset3.anns, nl=1)))
>>> print('merged.anns = {}'.format(ub.repr2(merged.anns, nl=1)))
```

## Example

```
>>> import kwcoco
>>> # Test empty union
>>> empty_union = kwcoco.CocoDataset.union()
>>> assert len(empty_union.index.imgs) == 0
```

---

## Todo:

- [ ] are supercategories broken?
  - [ ] reuse image ids where possible
  - [ ] reuse annotation / category ids where possible
  - [X] handle case where no inputs are given
  - [x] disambiguate track-ids
  - [x] disambiguate video-ids
- 

## `subset(gids, copy=False, autobuild=True)`

Return a subset of the larger coco dataset by specifying which images to port. All annotations in those images will be taken.

### Parameters

- **gids** (*List[int]*) – image-ids to copy into a new dataset
- **copy** (*bool*) – if True, makes a deep copy of all nested attributes, otherwise makes a shallow copy. Defaults to True.
- **autobuild** (*bool*) – if True will automatically build the fast lookup index. Defaults to True.

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> gids = [1, 3]
>>> sub_dset = self.subset(gids)
>>> assert len(self.index.gid_to_aids) == 3
>>> assert len(sub_dset.gid_to_aids) == 2
```

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('vidshapes2')
>>> gids = [1, 2]
>>> sub_dset = self.subset(gids, copy=True)
>>> assert len(sub_dset.index.videos) == 1
>>> assert len(self.index.videos) == 2
```

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> sub1 = self.subset([1])
>>> sub2 = self.subset([2])
>>> sub3 = self.subset([3])
>>> others = [sub1, sub2, sub3]
>>> rejoined = kwcoco.CocoDataset.union(*others)
>>> assert len(sub1.anns) == 9
>>> assert len(sub2.anns) == 2
>>> assert len(sub3.anns) == 0
>>> assert rejoined.basic_stats() == self.basic_stats()
```

**view\_sql**(*force\_rewrite=False*, *memory=False*, *backend='sqlite'*, *sql\_db\_fpath=None*)

Create a cached SQL interface to this dataset suitable for large scale multiprocessing use cases.

**Parameters**

- **force\_rewrite** (*bool*) – if True, forces an update to any existing cache file on disk
- **memory** (*bool*) – if True, the database is constructed in memory.
- **backend** (*str*) – sqlite or postgresql
- **sql\_db\_fpath** (*str* | *PathLike* | *None*) – overrides the database uri

---

**Note:** This view cache is experimental and currently depends on the timestamp of the file pointed to by `self.fpath`. In other words dont use this on in-memory datasets.

---

## CommandLine

```
KWCOCO_WITH_POSTGRESQL=1 xdoctest -m /home/joncrall/code/kwCOCO/kwCOCO/coco_
dataset.py CocoDataset.view_sql
```

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> # xdoctest: +REQUIRES(env:KWCOCO_WITH_POSTGRESQL)
>>> # xdoctest: +REQUIRES(module:psycopg2)
>>> import kwCOCO
>>> dset = kwCOCO.CocoDataset.demo('vidshapes32')
>>> postgres_dset = dset.view_sql(backend='postgresql', force_rewrite=True)
>>> sqlite_dset = dset.view_sql(backend='sqlite', force_rewrite=True)
>>> list(dset.anns.keys())
>>> list(postgres_dset.anns.keys())
>>> list(sqlite_dset.anns.keys())
```

```
import timerit
ti = timerit.Timerit(100, bestof=10, verbose=2)
for timer in ti.reset('dct_dset'):
    dset.annots().detections
    for timer in ti.reset('postgresql'):
        postgres_dset.annots().detections
    for timer in ti.reset('sqlite'):
        sqlite_dset.annots().detections
    ub.udict(sql_dset.annots().objs[0]) - {'segmentation'}
    ub.udict(dct_dset.annots().objs[0]) - {'segmentation'}
```


kwCOCO.coco\_dataset.demo\_coco\_data()

Simple data for testing.

This contains several non-standard fields, which help ensure robustness of functions tested with this data. For more compliant demodata see the kwCOCO.demodata submodule.

## Example

```
>>> # xdoctest: +REQUIRES(--show)
>>> import kwCOCO
>>> from kwCOCO.coco_dataset import demo_coco_data
>>> dataset = demo_coco_data()
>>> self = kwCOCO.CocoDataset(dataset, tag='demo')
>>> import kwplot
>>> kwplot.autopl()
>>> self.show_image(gid=1)
>>> kwplot.show_if_requested()
```



### 2.1.2.5 `kwcoco.coco_evaluator` module

Evaluates a predicted coco dataset against a truth coco dataset.

This currently computes detection-level metrics.

The components in this module work programmatically or as a command line script.

---

#### **Todo:**

- [ ] does `evaluate` return one result or multiple results based on different configurations?
  - [ ] `max_dets` - TODO: in original pycocoutils but not here
  - [ ] Flag that allows for polygon instead of bounding box overlap
  - [ ] How do we note what `iou_thresh` and `area-range` were in the result plots?
-

## CommandLine

```
xdotest -m kwCOCO.coco_evaluator __doc__:0 --vd --slow
```

## Example

```
>>> from kwCOCO.coco_evaluator import * # NOQA
>>> from kwCOCO.coco_evaluator import CocoEvaluator
>>> import kwCOCO
>>> # note: increase the number of images for better looking metrics
>>> true_dset = kwCOCO.CocoDataset.demo('shapes8')
>>> from kwCOCO.demo.perterb import perterb_coco
>>> kwargs = {
>>>     'box_noise': 0.5,
>>>     'n_fp': (0, 10),
>>>     'n_fn': (0, 10),
>>>     'with_probs': True,
>>> }
>>> pred_dset = perterb_coco(true_dset, **kwargs)
>>> print('true_dset = {!r}'.format(true_dset))
>>> print('pred_dset = {!r}'.format(pred_dset))
>>> config = {
>>>     'true_dataset': true_dset,
>>>     'pred_dataset': pred_dset,
>>>     'area_range': ['all', 'small'],
>>>     'iou_thresh': [0.3, 0.95],
>>> }
>>> coco_eval = CocoEvaluator(config)
>>> results = coco_eval.evaluate()
>>> # Now we can draw / serialize the results as we please
>>> dpath = ub.Path.appdir('kwCOCO/tests/test_out_dpath').ensuredir()
>>> results_fpath = dpath / 'metrics.json'
>>> print('results_fpath = {!r}'.format(results_fpath))
>>> results.dump(results_fpath, indent='    ')
>>> measures = results['area_range=all,iou_thresh=0.3'].ncls_measures
>>> import pandas as pd
>>> print(pd.DataFrame(ub.dict_isect(
>>>     measures, ['f1', 'g1', 'mcc', 'thresholds',
>>>                 'ppv', 'tpr', 'tnr', 'npv', 'fpr',
>>>                 'tp_count', 'fp_count',
>>>                 'tn_count', 'fn_count'])).iloc[:100])
>>> # xdotest: +REQUIRES(module:kwpplot)
>>> # xdotest: +REQUIRES(--slow)
>>> results.dump_figures(dpath)
>>> print('dpath = {!r}'.format(dpath))
>>> # xdotest: +REQUIRES(--vd)
>>> if ub.argflag('--vd') or 1:
>>>     import xdev
>>>     xdev.view_directory(dpath)
```

```
class kwCOCO.coco_evaluator.CocoEvalConfig(data=None, default=None, cmdline=False)
```

Bases: Config

Evaluate and score predicted versus truth detections / classifications in a COCO dataset

```
default = {'ap_method': <Value(None: 'pycocotools')>, 'area_range': <Value(None: ['all'])>, 'assign_workers': <Value(None: 8)>, 'classes_of_interest': <Value(<class 'list'>: None)>, 'compat': <Value(None: 'mutex')>, 'force_pycocoutils': <Value(None: False)>, 'fp_cutoff': <Value(None: inf)>, 'ignore_classes': <Value(<class 'list'>: None)>, 'implicit_ignore_classes': <Value(None: ['ignore'])>, 'implicit_negative_classes': <Value(None: ['background'])>, 'iou_bias': <Value(None: 1)>, 'iou_thresh': <Value(None: 0.5)>, 'load_workers': <Value(None: 0)>, 'max_dets': <Value(None: inf)>, 'monotonic_ppv': <Value(None: True)>, 'ovthresh': <Value(None: None)>, 'pred_dataset': <Value(<class 'str'>: None)>, 'true_dataset': <Value(<class 'str'>: None)>, 'use_area_attr': <Value(None: 'try')>, 'use_image_names': <Value(None: False)>}
```

`normalize()`

`class kwcoco.coco_evaluator.CocoEvaluator(config)`

Bases: `object`

Abstracts the evaluation process to execute on two coco datasets.

This can be run as a standalone script where the user specifies the paths to the true and predited dataset explicitly, or this can be used by a higher level script that produces the predictions and then sends them to this evaluator.

## Example

```
>>> from kwcoco.coco_evaluator import CocoEvaluator
>>> from kwcoco.demo.perterb import perterb_coco
>>> import kwcoco
>>> true_dset = kwcoco.CocoDataset.demo('shapes8')
>>> kwargs = {
>>>     'box_noise': 0.5,
>>>     'n_fp': (0, 10),
>>>     'n_fn': (0, 10),
>>>     'with_probs': True,
>>> }
>>> pred_dset = perterb_coco(true_dset, **kwargs)
>>> config = {
>>>     'true_dataset': true_dset,
>>>     'pred_dataset': pred_dset,
>>>     'classes_of_interest': [],
>>> }
>>> coco_eval = CocoEvaluator(config)
>>> results = coco_eval.evaluate()
```

## Config

alias of `CocoEvalConfig`

`log(msg, level='INFO')`

`evaluate()`

Executes the main evaluation logic. Performs assignments between detections to make DetectionMetrics object, then creates per-item and ovr confusion vectors, and performs various threshold-vs-confusion analyses.

**Returns**

**container storing (and capable of drawing / serializing) results**

**Return type**

*CocoResults*

```
kwcoco.coco_evaluator.dmet_area_weights(dmet, orig_weights, cfsn_vecs, area_ranges, coco_eval,  
                                         use_area_attr=False)
```

Hacky function to compute confusion vector ignore weights for different area thresholds. Needs to be slightly refactored.

```
class kwcoco.coco_evaluator.CocoResults(resdata=None)
```

Bases: *NiceRepr*, *DictProxy*

**CommandLine**

```
xdoctest -m /home/joncrall/code/kwcoco/kwcoco/coco_evaluator.py CocoResults --  
--profile
```

**Example**

```
>>> from kwcoco.coco_evaluator import * # NOQA  
>>> from kwcoco.coco_evaluator import CocoEvaluator  
>>> import kwcoco  
>>> true_dset = kwcoco.CocoDataset.demo('shapes2')  
>>> from kwcoco.demo.perterb import perterb_coco  
>>> kwargs = {  
>>>     'box_noise': 0.5,  
>>>     'n_fp': (0, 10),  
>>>     'n_fn': (0, 10),  
>>> }  
>>> pred_dset = perterb_coco(true_dset, **kwargs)  
>>> print('true_dset = {!r}'.format(true_dset))  
>>> print('pred_dset = {!r}'.format(pred_dset))  
>>> config = {  
>>>     'true_dataset': true_dset,  
>>>     'pred_dataset': pred_dset,  
>>>     'area_range': ['small'],  
>>>     'iou_thresh': [0.3],  
>>> }  
>>> coco_eval = CocoEvaluator(config)  
>>> results = coco_eval.evaluate()  
>>> # Now we can draw / serialize the results as we please  
>>> dpath = ub.Path.appdir('kwcoco/tests/test_out_dpath').ensuredir()  
>>> #  
>>> # test deserialization works  
>>> state = results.__json__()  
>>> self2 = CocoResults.from_json(state)  
>>> #  
>>> # xdoctest: +REQUIRES(module:kwplot)
```

(continues on next page)

(continued from previous page)

```
>>> results.dump_figures(dpath, figsize=(3, 2), tight=False) # make this go faster
>>> results.dump(dpath / 'metrics.json', indent=' ')
```

**dump\_figures**(*out\_dpath*, *expt\_title*=None, *figsize*='auto', *tight*=True)

**classmethod from\_json**(*state*)

**dump**(*file*, *indent*=' ')

Serialize to json file

**class kwcoco.coco\_evaluator.CocoSingleResult**(*nocls\_measures*, *ovr\_measures*, *cfsn\_vecs*, *meta*=None)

Bases: `NiceRepr`

Container class to store, draw, summarize, and serialize results from CocoEvaluator.

## Example

```
>>> # xdoctest: +REQUIRES(--slow)
>>> from kwcoco.coco_evaluator import * # NOQA
>>> from kwcoco.coco_evaluator import CocoEvaluator
>>> import kwcoco
>>> true_dset = kwcoco.CocoDataset.demo('shapes8')
>>> from kwcoco.demo.perterb import perterb_coco
>>> kwargs = {
>>>     'box_noise': 0.2,
>>>     'n_fp': (0, 3),
>>>     'n_fn': (0, 3),
>>>     'with_probs': False,
>>> }
>>> pred_dset = perterb_coco(true_dset, **kwargs)
>>> print('true_dset = {!r}'.format(true_dset))
>>> print('pred_dset = {!r}'.format(pred_dset))
>>> config = {
>>>     'true_dataset': true_dset,
>>>     'pred_dataset': pred_dset,
>>>     'area_range': [(0, 32 ** 2), (32 ** 2, 96 ** 2)],
>>>     'iou_thresh': [0.3, 0.5, 0.95],
>>> }
>>> coco_eval = CocoEvaluator(config)
>>> results = coco_eval.evaluate()
>>> result = ub.peek(results.values())
>>> state = result.__json__()
>>> print('state = {}'.format(ub.repr2(state, nl=-1)))
>>> recon = CocoSingleResult.from_json(state)
>>> state = recon.__json__()
>>> print('state = {}'.format(ub.repr2(state, nl=-1)))
```

**classmethod from\_json**(*state*)

**dump**(*file*, *indent*=' ')

Serialize to json file

**dump\_figures**(*out\_dpath*, *expt\_title*=None, *figsize*='auto', *tight*=True, *verbose*=1)

## 2.1.2.6 kwcoco.coco\_image module

Defines the CocoImage class which is an object oriented way of manipulating data pointed to by a COCO image dictionary.

Notably this provides the .imdelay method for delayed image loading ( which enables things like fast loading of subimage-regions / coarser scales in images that contain tiles / overviews - e.g. Cloud Optimized Geotiffs or COGs (Medical image formats may be supported in the future).

```
class kwcoco.coco_image.CocoImage(img, dset=None)
```

Bases: `NiceRepr`

An object-oriented representation of a coco image.

It provides helper methods that are specific to a single image.

This operates directly on a single coco image dictionary, but it can optionally be connected to a parent dataset, which allows it to use CocoDataset methods to query about relationships and resolve pointers.

This is different than the Images class in coco\_object1d, which is just a vectorized interface to multiple objects.

### Example

```
>>> import kwcoco
>>> dset1 = kwcoco.CocoDataset.demo('shapes8')
>>> dset2 = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
```

```
>>> self = CocoImage(dset1.imgs[1], dset1)
>>> print('self = {!r}'.format(self))
>>> print('self.channels = {}'.format(ub.repr2(self.channels, nl=1)))
```

```
>>> self = CocoImage(dset2.imgs[1], dset2)
>>> print('self.channels = {}'.format(ub.repr2(self.channels, nl=1)))
>>> self.primary_asset()
```

`classmethod from_gid(dset, gid)`

`property bundle_dpath`

`property video`

Helper to grab the video for this image if it exists

`detach()`

Removes references to the underlying coco dataset, but keeps special information such that it wont be needed.

`property assets`

`annots()`

**Returns**

a 1d annotations object referencing annotations in this image

**Return type**

`Annots`

`stats()`

**keys()**  
 Proxy getter attribute for underlying *self.img* dictionary

**get(key, default=NoParam)**  
 Proxy getter attribute for underlying *self.img* dictionary

### Example

```
>>> import pytest
>>> # without extra populated
>>> import kwcoco
>>> self = kwcoco.CocoImage({'foo': 1})
>>> assert self.get('foo') == 1
>>> assert self.get('foo', None) == 1
>>> # with extra populated
>>> self = kwcoco.CocoImage({'extra': {'foo': 1}})
>>> assert self.get('foo') == 1
>>> assert self.get('foo', None) == 1
>>> # without extra empty
>>> self = kwcoco.CocoImage({})
>>> with pytest.raises(KeyError):
>>>     self.get('foo')
>>> assert self.get('foo', None) is None
>>> # with extra empty
>>> self = kwcoco.CocoImage({'extra': {'bar': 1}})
>>> with pytest.raises(KeyError):
>>>     self.get('foo')
>>> assert self.get('foo', None) is None
```

**property channels**

**property num\_channels**

**property dsize**

**primary\_image\_filepath**(*requires=None*)

**primary\_asset**(*requires=None*)

Compute a “main” image asset.

### Notes

Uses a heuristic.

- First, try to find the auxiliary image that has the smallest distortion to the base image (if known via *warp\_aux\_to\_img*)
- Second, break ties by using the largest image if w / h is known
- Last, if previous information not available use the first auxiliary image.

### Parameters

**requires** (*List[str] | None*) – list of attribute that must be non-None to consider an object as the primary one.

**Returns**

the asset dict or None if it is not found

**Return type**

None | dict

---

**Todo:**

- [ ] Add in primary heuristics
- 

**Example**

```
>>> import kwarray
>>> from kwcoco.coco_image import * # NOQA
>>> rng = kwarray.ensure_rng(0)
>>> def random_auxiliary(name, w=None, h=None):
>>>     return {'file_name': name, 'width': w, 'height': h}
>>> self = CocoImage({
>>>     'auxiliary': [
>>>         random_auxiliary('1'),
>>>         random_auxiliary('2'),
>>>         random_auxiliary('3'),
>>>     ]
>>> })
>>> assert self.primary_asset()['file_name'] == '1'
>>> self = CocoImage({
>>>     'auxiliary': [
>>>         random_auxiliary('1'),
>>>         random_auxiliary('2', 3, 3),
>>>         random_auxiliary('3'),
>>>     ]
>>> })
>>> assert self.primary_asset()['file_name'] == '2'
```

**iter\_image\_filepaths(*with\_bundle=True*)**

Could rename to iter\_asset\_filepaths

**Parameters**

**with\_bundle** (bool) – If True, prepends the bundle dpath to fully specify the path. Otherwise, just returns the registered string in the file\_name attribute of each asset. Defaults to True.

**iter\_asset\_objs()**

Iterate through base + auxiliary dicts that have file paths

**Yields**

*dict* – an image or auxiliary dictionary

**find\_asset\_obj(*channels*)**

Find the asset dictionary with the specified channels

## Example

```
>>> import kwcoco
>>> coco_img = kwcoco.CocoImage({'width': 128, 'height': 128})
>>> coco_img.add_auxiliary_item(
    'rgb.png', channels='red|green|blue', width=32, height=32)
>>> assert coco_img.find_asset_obj('red') is not None
>>> assert coco_img.find_asset_obj('green') is not None
>>> assert coco_img.find_asset_obj('blue') is not None
>>> assert coco_img.find_asset_obj('red|blue') is not None
>>> assert coco_img.find_asset_obj('red|green|blue') is not None
>>> assert coco_img.find_asset_obj('red|green|blue') is not None
>>> assert coco_img.find_asset_obj('black') is None
>>> assert coco_img.find_asset_obj('r') is None
```

## Example

```
>>> # Test with concise channel code
>>> import kwcoco
>>> coco_img = kwcoco.CocoImage({'width': 128, 'height': 128})
>>> coco_img.add_auxiliary_item(
    'msi.png', channels='foo.0:128', width=32, height=32)
>>> assert coco_img.find_asset_obj('foo') is None
>>> assert coco_img.find_asset_obj('foo.3') is not None
>>> assert coco_img.find_asset_obj('foo.3:5') is not None
>>> assert coco_img.find_asset_obj('foo.3000') is None
```

### `add_annotation(**ann)`

Adds an annotation to this image.

This is a convinience method, and requires that this CocoImage is still connected to a parent dataset.

#### Parameters

`**ann` – annotation attributes (e.g. bbox, category\_id)

#### Returns

the new annotation id

#### Return type

`int`

#### SeeAlso:

`kwcoco.CocoDataset.add_annotation()`

### `add_asset(file_name=None, channels=None, imdata=None, warp_aux_to_img=None, width=None, height=None, imwrite=False)`

Adds an auxiliary / asset item to the image dictionary.

This operation can be done purely in-memory (the default), or the image data can be written to a file on disk (via the `imwrite=True` flag).

#### Parameters

- `file_name` (`str | PathLike | None`) – The name of the file relative to the bundle directory. If unspecified, `imdata` must be given.

- **channels** (*str | kwcoco.FusedChannelSpec | None*) – The channel code indicating what each of the bands represents. These channels should be disjoint wrt to the existing data in this image (this is not checked).
- **imdata** (*ndarray | None*) – The underlying image data this auxiliary item represents. If unspecified, it is assumed file\_name points to a path on disk that will eventually exist. If imdata, file\_name, and the special imwrite=True flag are specified, this function will write the data to disk.
- **warp\_aux\_to\_img** (*kwimage.Affine | None*) – The transformation from this auxiliary space to image space. If unspecified, assumes this item is related to image space by only a scale factor.
- **width** (*int | None*) – Width of the data in auxiliary space (inferred if unspecified)
- **height** (*int | None*) – Height of the data in auxiliary space (inferred if unspecified)
- **imwrite** (*bool*) – If specified, both imdata and file\_name must be specified, and this will write the data to disk. Note: it is recommended that you simply call imwrite yourself before or after calling this function. This lets you better control imwrite parameters.

---

**Todo:**

- [ ] Allow imwrite to specify an executor that is used to return a Future so the imwrite call does not block.
- 

**Example**

```
>>> from kwcoco.coco_image import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> coco_img = dset.coco_image(1)
>>> imdata = np.random.rand(32, 32, 5)
>>> channels = kwcoco.FusedChannelSpec.coerce('Aux:5')
>>> coco_img.add_asset(imdata=imdata, channels=channels)
```

**Example**

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset()
>>> gid = dset.add_image(name='my_image_name', width=200, height=200)
>>> coco_img = dset.coco_image(gid)
>>> coco_img.add_asset('path/img1_B0.tif', channels='B0', width=200, height=200)
>>> coco_img.add_asset('path/img1_B1.tif', channels='B1', width=200, height=200)
>>> coco_img.add_asset('path/img1_B2.tif', channels='B2', width=200, height=200)
>>> coco_img.add_asset('path/img1_TCI.tif', channels='rgb', width=200, height=200)
```

```
imdelay(channels=None, space='image', resolution=None, bundle_dpath=None, interpolation='linear',
         antialias=True, nodata_method=None, RESOLUTION_KEY=None)
```

Perform a delayed load on the data in this image.

The delayed load can load a subset of channels, and perform lazy warping operations. If the underlying data is in a tiled format this can reduce the amount of disk IO needed to read the data if only a small crop or lower resolution view of the data is needed.

---

**Note:** This method is experimental and relies on the delayed load proof-of-concept.

---

### Parameters

- **gid** (*int*) – image id to load
- **channels** (*kwcoco.FusedChannelSpec*) – specific channels to load. if unspecified, all channels are loaded.
- **space** (*str*) – can either be “image” for loading in image space, or “video” for loading in video space.
- **resolution** (*None | str | float*) – If specified, applies an additional scale factor to the result such that the data is loaded at this specified resolution. This requires that the image / video has a registered resolution attribute and that its units agree with this request.

---

**Todo:**

- [ ] **This function could stand to have a better name. Maybe imread**  
with a delayed=True flag? Or maybe just delayed\_load?
- 

### Example

```
>>> from kwcoco.coco_image import * # NOQA
>>> import kwcoco
>>> gid = 1
>>> #
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> self = CocoImage(dset.imgs[gid], dset)
>>> delayed = self.imdelay()
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> #
>>> dset = kwcoco.CocoDataset.demo('shapes8')
>>> delayed = dset.coco_image(gid).imdelay()
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
```

```
>>> crop = delayed.crop((slice(0, 3), slice(0, 3)))
>>> crop.finalize()
```

```
>>> # TODO: should only select the "red" channel
>>> dset = kwcoco.CocoDataset.demo('shapes8')
>>> delayed = CocoImage(dset.imgs[gid], dset).imdelay(channels='r')
```

```
>>> import kwCOCO
>>> gid = 1
>>> #
>>> dset = kwCOCO.CocoDataset.demo('vidshapes8-multispectral')
>>> delayed = dset.coco_image(gid).imdelay(channels='B1|B2', space='image')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> delayed = dset.coco_image(gid).imdelay(channels='B1|B2|B11', space='image')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> delayed = dset.coco_image(gid).imdelay(channels='B8|B1', space='video')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))

>>> delayed = dset.coco_image(gid).imdelay(channels='B8|foo|bar|B1', space=
    ~'video')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
```

### Example

```
>>> import kwCOCO
>>> dset = kwCOCO.CocoDataset.demo()
>>> coco_img = dset.coco_image(1)
>>> # Test case where nothing is registered in the dataset
>>> delayed = coco_img.imdelay()
>>> final = delayed.finalize()
>>> assert final.shape == (512, 512, 3)

>>> delayed = coco_img.imdelay()
>>> final = delayed.finalize()
>>> print('final.shape = {}'.format(ub.repr2(final.shape, nl=1)))
>>> assert final.shape == (512, 512, 3)
```

### Example

```
>>> # Test that delay works when imdata is stored in the image
>>> # dictionary itself.
>>> from kwCOCO.coco_image import * # NOQA
>>> import kwCOCO
>>> dset = kwCOCO.CocoDataset.demo('vidshapes8-multispectral')
>>> coco_img = dset.coco_image(1)
>>> imdata = np.random.rand(6, 6, 5)
>>> imdata[:] = np.arange(5)[None, None, :]
>>> channels = kwCOCO.FusedChannelSpec.coerce('Aux:5')
>>> coco_img.add_auxiliary_item(imdata=imdata, channels=channels)
>>> delayed = coco_img.imdelay(channels='B1|Aux:2:4')
>>> final = delayed.finalize()
```

**Example**

```
>>> # Test delay when loading in asset space
>>> from kwcoco.coco_image import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-msi-multisensor')
>>> coco_img = dset.coco_image(1)
>>> stream1 = coco_img.channels.streams()[0]
>>> stream2 = coco_img.channels.streams()[1]
>>> asset_delayed = coco_img.imdelay(stream1, space='asset')
>>> img_delayed = coco_img.imdelay(stream1, space='image')
>>> vid_delayed = coco_img.imdelay(stream1, space='video')
>>> #
>>> aux_imdata = asset_delayed.as_xarray().finalize()
>>> img_imdata = img_delayed.as_xarray().finalize()
>>> assert aux_imdata.shape != img_imdata.shape
>>> # Cannot load multiple asset items at the same time in
>>> # asset space
>>> import pytest
>>> fused_channels = stream1 | stream2
>>> from delayed_image.delayed_nodes import CoordinateCompatibilityError
>>> with pytest.raises(CoordinateCompatibilityError):
>>>     aux_delayed2 = coco_img.imdelay(fused_channels, space='asset')
```

**Example**

```
>>> # Test loading at a specific resolution.
>>> from kwcoco.coco_image import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-msi-multisensor')
>>> coco_img = dset.coco_image(1)
>>> coco_img.img['resolution'] = '1 meter'
>>> img_delayed1 = coco_img.imdelay(space='image')
>>> vid_delayed1 = coco_img.imdelay(space='video')
>>> # test with unitless request
>>> img_delayed2 = coco_img.imdelay(space='image', resolution=3.1)
>>> vid_delayed2 = coco_img.imdelay(space='video', resolution='3.1 meter')
>>> np.ceil(img_delayed1.shape[0] / 3.1) == img_delayed2.shape[0]
>>> np.ceil(vid_delayed1.shape[0] / 3.1) == vid_delayed2.shape[0]
>>> # test with unitless data
>>> coco_img.img['resolution'] = 1
>>> img_delayed2 = coco_img.imdelay(space='image', resolution=3.1)
>>> vid_delayed2 = coco_img.imdelay(space='video', resolution='3.1 meter')
>>> np.ceil(img_delayed1.shape[0] / 3.1) == img_delayed2.shape[0]
>>> np.ceil(vid_delayed1.shape[0] / 3.1) == vid_delayed2.shape[0]
```

**valid\_region(space='image')**

If this image has a valid polygon, return it in image, or video space

**property warp\_vid\_from\_img**

Affine transformation that warps image space -> video space.

**property warp\_img\_from\_vid**

Affine transformation that warps video space -> image space.

**resolution(*space='image'*, *channel=None*, *RESOLUTION\_KEY=None*)**

Returns the resolution of this CocoImage in the requested space if known. Errors if this information is not registered.

**Parameters**

- **space (str)** – the space to the resolution of. Can be either “image”, “video”, or “asset”.
- **channel (str | kwcoco.FusedChannelSpec | None)** – a channel that identifies a single asset, only relevant if asking for asset space

**Returns**

has items mag (with the magnitude of the resolution) and unit, which is a convinience and only loosely enforced.

**Return type**

Dict

**Example**

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> self = dset.coco_image(1)
>>> self.img['resolution'] = 1
>>> self.resolution()
>>> self.img['resolution'] = '1 meter'
>>> self.resolution(space='video')
{'mag': (1.0, 1.0), 'unit': 'meter'}
>>> self.resolution(space='asset', channel='B11')
>>> self.resolution(space='asset', channel='B1')
```

**add\_auxiliary\_item(\*\*kwargs)****delay(\*\*kwargs)****class kwcoco.coco\_image.CocoAsset(*obj*)**

Bases: `object`

A Coco Asset / Auxiliary Item

Represents one 2D image file relative to a parent img.

Could be a single asset, or an image with sub-assets, but sub-assets are ignored here.

Initially we called these “auxiliary” items, but I think we should change their name to “assets”, which better maps with STAC terminology.

**keys()**

Proxy getter attribute for underlying `self.obj` dictionary

**get(*key*, *default=NoParam*)**

Proxy getter attribute for underlying `self.obj` dictionary

**kwcoco.coco\_image.parse\_quantity(*expr*)****kwcoco.coco\_image.coerce\_resolution(*expr*)**

### 2.1.2.7 `kwcoco.coco_objects1d` module

Vectorized ORM-like objects used in conjunction with coco\_dataset.

This powers the `.images()`, `.videos()`, and `.annotation()` methods of `kwcoco.CocoDataset`.

**See:**

```
kwcoco.coco_dataset.MixinCocoObjects.categories()           kwcoco.coco_dataset.
MixinCocoObjects.videos()      kwcoco.coco_dataset.MixinCocoObjects.images()      kwcoco.
coco_dataset.MixinCocoObjects.annots()
```

**class** `kwcoco.coco_objects1d.ObjectList1D(ids, dset, key)`

Bases: `NiceRepr`

Vectorized access to lists of dictionary objects

Lightweight reference to a set of object (e.g. annotations, images) that allows for convenient property access.

#### Parameters

- `ids` (`List[int]`) – list of ids
- `dset` (`CocoDataset`) – parent dataset
- `key` (`str`) – main object name (e.g. ‘images’, ‘annotations’)

#### Types:

`ObjT` = `Ann` | `Img` | `Cat` # can be one of these types `ObjectList1D` gives us access to a `List[ObjT]`

#### Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> # Both annots and images are object lists
>>> self = dset.annots()
>>> self = dset.images()
>>> # can call with a list of ids or not, for everything
>>> self = dset.annots([1, 2, 11])
>>> self = dset.images([1, 2, 3])
>>> self.lookup('id')
>>> self.lookup(['id'])
```

#### `unique()`

Removes any duplicates entries in this object

#### Returns

`ObjectList1D`

#### `property objs`

Get the underlying object dictionary for each object.

#### Returns

all object dictionaries

#### `Return type`

`List[ObjT]`

### `take(idxs)`

Take a subset by index

#### Returns

ObjectList1D

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().annots()
>>> assert len(self.take([0, 2, 3])) == 3
```

### `compress(flags)`

Take a subset by flags

#### Returns

ObjectList1D

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().images()
>>> assert len(self.compress([True, False, True])) == 2
```

### `peek()`

Return the first object dictionary

#### Returns

object dictionary

#### Return type

ObjT

### Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> self = dset.images()
>>> assert self.peek()['id'] == 1
>>> # Check that subsets return correct items
>>> sub0 = self.compress([i % 2 == 0 for i in range(len(self))])
>>> sub1 = self.compress([i % 2 == 1 for i in range(len(self))])
>>> assert sub0.peek()['id'] == 1
>>> assert sub1.peek()['id'] == 2
```

### `lookup(key, default=NoParam, keepid=False)`

Lookup a list of object attributes

#### Parameters

- **key** (`str | Iterable`) – name of the property you want to lookup can also be a list of names, in which case we return a dict
- **default** – if specified, uses this value if it doesn't exist in an ObjT.

- **keepid** – if True, return a mapping from ids to the property

**Returns**

a list of whatever type the object is Dict[str, ObjT]

**Return type**

List[ObjT]

**Example**

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> self = dset.annots()
>>> self.lookup('id')
>>> key = ['id']
>>> default = None
>>> self.lookup(key=['id', 'image_id'])
>>> self.lookup(key=['id', 'image_id'])
>>> self.lookup(key='foo', default=None, keepid=True)
>>> self.lookup(key=['foo'], default=None, keepid=True)
>>> self.lookup(key=['id', 'image_id'], keepid=True)
```

**get**(*key*, *default*=*NoParam*, *keepid*=*False*)

Lookup a list of object attributes

**Parameters**

- **key** (*str*) – name of the property you want to lookup
- **default** – if specified, uses this value if it doesn't exist in an ObjT.
- **keepid** – if True, return a mapping from ids to the property

**Returns**

a list of whatever type the object is Dict[str, ObjT]

**Return type**

List[ObjT]

**Example**

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> self = dset.annots()
>>> self.get('id')
>>> self.get(key='foo', default=None, keepid=True)
```

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> import kwcoco
>>> dct_dset = kwcoco.CocoDataset.demo('vidshapes8', rng=303232)
>>> dct_dset.anns[3]['blorgo'] = 3
>>> dct_dset.annots().lookup('blorgo', default=None)
>>> for a in dct_dset.anns.values():
...     a['wizard'] = '10!'
>>> dset = dct_dset.view_sql(force_rewrite=1)
>>> assert dset.anns[3]['blorgo'] == 3
>>> assert dset.anns[3]['wizard'] == '10!'
>>> assert 'blorgo' not in dset.anns[2]
>>> dset.annots().lookup('blorgo', default=None)
>>> dset.annots().lookup('wizard', default=None)
>>> import pytest
>>> with pytest.raises(KeyError):
...     dset.annots().lookup('blorgo')
>>> dset.annots().lookup('wizard')
>>> #self = dset.annots()
```

## set(key, values)

Assign a value to each annotation

### Parameters

- **key** (*str*) – the annotation property to modify
- **values** (*Iterable* | *Any*) – an iterable of values to set for each annot in the dataset. If the item is not iterable, it is assigned to all objects.

## Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> self = dset.annots()
>>> self.set('my-key1', 'my-scalar-value')
>>> self.set('my-key2', np.random.rand(len(self)))
>>> print('dset.imgs = {}'.format(ub.repr2(dset.imgs, nl=1)))
>>> self.get('my-key2')
```

## attribute\_frequency()

Compute the number of times each key is used in a dictionary

### Returns

Dict[str, int]

**Example**

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> self = dset.annots()
>>> attrs = self.attribute_frequency()
>>> print('attrs = {}'.format(ub.repr2(attrs, nl=1)))
```

**class** kwcoco.coco\_objects1d.**ObjectGroups**(*groups, dset*)

Bases: *NiceRepr*

An object for holding a groups of *ObjectList1D* objects

**lookup**(*key, default=NoParam*)

**class** kwcoco.coco\_objects1d.**Categories**(*ids, dset*)

Bases: *ObjectList1D*

Vectorized access to category attributes

**SeeAlso:**

*kwcoco.coco\_dataset.MixinCocoObjects.categories()*

**Example**

```
>>> from kwcoco.coco_objects1d import Categories # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo()
>>> ids = list(dset.cats.keys())
>>> self = Categories(ids, dset)
>>> print('self.name = {!r}'.format(self.name))
>>> print('self.supercategory = {!r}'.format(self.supercategory))
```

**property** cids

**property** name

**property** supercategory

**class** kwcoco.coco\_objects1d.**Videos**(*ids, dset*)

Bases: *ObjectList1D*

Vectorized access to video attributes

**SeeAlso:**

*kwcoco.coco\_dataset.MixinCocoObjects.videos()*

## Example

```
>>> from kwcoco.coco_objects1d import Videos # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes5')
>>> ids = list(dset.index.videos.keys())
>>> self = Videos(ids, dset)
>>> print('self = {!r}'.format(self))
self = <Videos(num=5) at ...>
```

**property images**

Example:

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('vidshapes8').videos()
>>> print(self.images)
<ImageGroups(n=8, m=2.0, s=0.0)>
```

**class kwcoco.coco\_objects1d.Images(*ids, dset*)**

Bases: *ObjectList1D*

Vectorized access to image attributes

## Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('photos')
>>> images = dset.images()
>>> print('images = {}'.format(images))
images = <Images(num=3)...>
>>> print('images.gname = {}'.format(images.gname))
images.gname = ['astro.png', 'carl.jpg', 'stars.png']
```

SeeAlso:

`kwcoco.coco_dataset.MixinCocoObjects.images()`

**property coco\_images**

**property gids**

**property gname**

**property gpath**

**property width**

**property height**

**property size**

Example:

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().images()
>>> self._dset._ensure_imgszie()
...
>>> print(self.size)
[(512, 512), (328, 448), (256, 256)]
```

**property area****Example:**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().images()
>>> self._dset._ensure_imgszie()
...
>>> print(self.area)
[262144, 146944, 65536]
```

**property n\_annots****Example:**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().images()
>>> print(ub.repr2(self.n_annots, nl=0))
[9, 2, 0]
```

**property aids****Example:**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().images()
>>> print(ub.repr2(list(map(list, self.aids)), nl=0))
[[1, 2, 3, 4, 5, 6, 7, 8, 9], [10, 11], []]
```

**property annots****Example:**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().images()
>>> print(self.annot)
<AnnotGroups(n=3, m=3.7, s=3.9)>
```

**class kwcoco.coco\_objects1d.Annots(ids, dset)**Bases: *ObjectList1D*

Vectorized access to annotation attributes

**SeeAlso:***kwcoco.coco\_dataset.MixinCocoObjects.annot()*

## Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('photos')
>>> annots = dset.annots()
>>> print('annots = {}'.format(annots))
annots = <Annots(num=11)>
>>> image_ids = annots.lookup('image_id')
>>> print('image_ids = {}'.format(image_ids))
image_ids = [1, 1, 1, 1, 1, 1, 1, 1, 1, 2, 2]
```

### property aids

The annotation ids of this column of annotations

### property images

Get the column of images

#### Returns

Images

### property image\_id

### property category\_id

### property gids

Get the column of image-ids

#### Returns

list of image ids

#### Return type

List[int]

### property cids

Get the column of category-ids

#### Returns

List[int]

### property cnames

Get the column of category names

#### Returns

List[int]

### property category\_names

Get the column of category names

#### Returns

List[int]

### property detections

Get the kwimage-style detection objects

#### Returns

kwimage.Detections

**Example**

```
>>> # xdoctest: +REQUIRES(module:kwimage)
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('shapes32').annots([1, 2, 11])
>>> dets = self.detections
>>> print('dets.data = {!r}'.format(dets.data))
>>> print('dets.meta = {!r}'.format(dets.meta))
```

**property boxes**

Get the column of kwimage-style bounding boxes

**Returns**

kwimage.Boxes

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().annots([1, 2, 11])
>>> print(self.boxes)
<Boxes(xywh,
       array([[ 10,   10, 360, 490],
              [350,    5, 130, 290],
              [156, 130,   45,  18]]))>
```

**property xywh**

Returns raw boxes

DEPRECATED.

**Returns**

raw boxes in xywh format

**Return type**

List[List[int]]

**Example**

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo().annots([1, 2, 11])
>>> print(self.xywh)
```

**class** kwcoco.coco\_objects1d.**AnnotGroups**(groups, dset)

Bases: *ObjectGroups*

Annotation groups are vectorized lists of lists.

Each item represents a set of annotations that corresponds with something (i.e. belongs to a particular image).

## Example

```
>>> from kwcoco.coco_objects1d import ImageGroups
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('photos')
>>> images = dset.images()
>>> # Requesting the "annots" property from a Images object
>>> # will return an AnnotGroups object
>>> group: AnnotGroups = images.annots
>>> # Printing the group gives info on the mean/std of the number
>>> # of items per group.
>>> print(group)
<AnnotGroups(n=3, m=3.7, s=3.9)...>
>>> # Groups are fairly restrictive, they dont provide property level
>>> # access in many cases, but the lookup method is available
>>> print(group.lookup('id'))
[[1, 2, 3, 4, 5, 6, 7, 8, 9], [10, 11], []]
>>> print(group.lookup('image_id'))
[[1, 1, 1, 1, 1, 1, 1, 1], [2, 2], []]
>>> print(group.lookup('category_id'))
[[1, 2, 3, 4, 5, 5, 5, 5], [6, 4], []]
```

## property cids

Get the grouped category ids for annotations in this group

### Return type

List[List[int]]

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('photos').images().annots
>>> print('self.cids = {}'.format(ub.repr2(self.cids, nl=0)))
self.cids = [[1, 2, 3, 4, 5, 5, 5, 5, 5], [6, 4], []]
```

## property cnames

Get the grouped category names for annotations in this group

### Return type

List[List[str]]

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('photos').images().annots
>>> print('self.cnames = {}'.format(ub.repr2(self.cnames, nl=0)))
self.cnames = [['astronaut', 'rocket', 'helmet', 'mouth', 'star', 'star', 'star', 'star', 'star'], ['astronomer', 'mouth'], []]
```

## class kwcoco.coco\_objects1d.ImageGroups(groups, dset)

Bases: *ObjectGroups*

Image groups are vectorized lists of other Image objects.

Each item represents a set of images that corresponds with something (i.e. belongs to a particular video).

### Example

```
>>> from kwcoco.coco_objects1d import ImageGroups
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8')
>>> videos = dset.videos()
>>> # Requesting the "images" property from a Videos object
>>> # will return an ImageGroups object
>>> group: ImageGroups = videos.images
>>> # Printing the group gives info on the mean/std of the number
>>> # of items per group.
>>> print(group)
<ImageGroups(n=8, m=2.0, s=0.0)...>
>>> # Groups are fairly restrictive, they dont provide property level
>>> # access in many cases, but the lookup method is available
>>> print(group.lookup('id'))
[[1, 2], [3, 4], [5, 6], [7, 8], [9, 10], [11, 12], [13, 14], [15, 16]]
>>> print(group.lookup('video_id'))
[[1, 1], [2, 2], [3, 3], [4, 4], [5, 5], [6, 6], [7, 7], [8, 8]]
>>> print(group.lookup('frame_index'))
[[0, 1], [0, 1], [0, 1], [0, 1], [0, 1], [0, 1], [0, 1], [0, 1]]
```

### 2.1.2.8 kwcoco.coco\_schema module

The place where the formal KWCOCO schema is defined.

#### CommandLine

```
python -m kwcoco.coco_schema
xdoctest -m kwcoco.coco_schema __doc__
```

### Example

```
>>> import kwcoco
>>> from kwcoco.coco_schema import COCO_SCHEMA
>>> import jsonschema
>>> dset = kwcoco.CocoDataset.demo('shapes1')
>>> # print('dset.dataset = {}'.format(ub.repr2(dset.dataset, nl=2)))
>>> COCO_SCHEMA.validate(dset.dataset)
```

```
>>> try:
>>>     jsonschema.validate(dset.dataset, schema=COCO_SCHEMA)
>>> except jsonschema.exceptions.ValidationError as ex:
>>>     vali_ex = ex
>>>     print('ex = {!r}'.format(ex))
>>>     raise
```

(continues on next page)

(continued from previous page)

```
>>> except jsonschema.exceptions.SchemaError as ex:  
>>>     print('ex = {!r}'.format(ex))  
>>>     schema_ex = ex  
>>>     print('schema_ex.instance = {!r}'.format(ub.repr2(schema_ex.instance, nl=-1)))  
>>>     raise
```

```
>>> # Test the multispectral image definition  
>>> import copy  
>>> dataset = dset.copy().dataset  
>>> img = dataset['images'][0]  
>>> img.pop('file_name')  
>>> import pytest  
>>> with pytest.raises(jsonschema.ValidationError):  
>>>     COCO_SCHEMA.validate(dataset)  
>>> import pytest  
>>> img['auxiliary'] = [{'file_name': 'foobar'}]  
>>> with pytest.raises(jsonschema.ValidationError):  
>>>     COCO_SCHEMA.validate(dataset)  
>>> img['name'] = 'aux-only images must have a name'  
>>> COCO_SCHEMA.validate(dataset)
```

kwcoc.coco\_schema.deprecated(\*args)

kwcoc.coco\_schema.TUPLE(\*args, \*\*kw)

### 2.1.2.9 kwcoc.coco\_sql\_dataset module

---

#### Todo:

- [ ] We get better speeds with raw SQL over alchemy. Can we mitigate the speed difference so we can take advantage of alchemy's expressiveness?
- 

Finally got a baseline implementation of an SQLite backend for COCO datasets. This mostly plugs into my existing tools (as long as only read operations are used; haven't implemented writing yet) by duck-typing the dict API.

This solves the issue of forking and then accessing nested dictionaries in the JSON-style COCO objects. (When you access the dictionary Python will increment a reference count which triggers copy-on-write for whatever memory page that data happened to live in. Non-contiguous access had the effect of excessive memory copies).

For "medium sized" datasets it's quite a bit slower. Running through a torch DataLoader with 4 workers for 10,000 images executes at a rate of 100Hz but takes 850MB of RAM. Using the duck-typed SQL backend only uses 500MB (which includes the cost of caching), but runs at 45Hz (which includes the benefit of caching).

However, once I scale up to 100,000 images I start seeing benefits. The in-memory dictionary interface chugs at 1.05HZ, and is taking more than 4GB of memory at the time I killed the process (eta was over an hour). The SQL backend ran at 45Hz and took about 3 minutes and used about 2.45GB of memory.

Without a cache, SQL runs at 30HZ and takes 400MB for 10,000 images, and for 100,000 images it gets 30Hz with 1.1GB. There is also a much larger startup time. I'm not exactly sure what it is yet, but it's probably some preprocessing I'm doing.

Using a LRU cache we get 45Hz and 1.05GB of memory, so that's a clear win. We do need to be sure to disable the cache if we ever implement write mode.

I'd like to be a bit faster on the medium sized datasets (I'd really like to avoid caching rows, which is why the speed is currently semi-reasonable), but I don't think I can do any better than this because single-row lookup time is  $O(\log(N))$  for sqlite, whereas its  $O(1)$  for dictionaries. (I wish sqlite had an option to create a hash-table index for a table, but I don't think it does). I optimized as many of the dictionary operations as possible (for instance, iterating through keys, values, and items should be  $O(N)$  instead of  $O(N \log(N))$ ), but the majority of the runtime cost is in the single-row lookup time.

There are a few questions I still have if anyone has insight:

- Say I want to select a subset of K rows from a table with N entries, and I have a list of all of the rowids that I want. Is there any way to do this better than  $O(K \log(N))$ ? I tried using a `SELECT col FROM table WHERE id IN (?, ?, ?, ?, ...)` filling in enough ? as there are rows in my subset. I'm not sure what the complexity of using a query like this is. I'm not sure what the `IN` implementation looks like. Can this be done more efficiently by with a temporary table and a `JOIN`?
- There really is no way to do  $O(1)$  row lookup in sqlite right? Is there a way in PostgreSQL or some other backend sqlalchemy supports?

I found that PostgreSQL does support hash indexes: <https://www.postgresql.org/docs/13/indexes-types.html> I'm really not interested in setting up a global service though . I also found a 10-year old thread with a hash-index feature request for SQLite, which I unabashedly resurrected <http://sqlite.1065341.n5.nabble.com/Feature-request-hash-index-td23367.html> <https://web.archive.org/web/20210326010915/http://sqlite.1065341.n5.nabble.com/Feature-request-hash-index-td23367.html>

```
class kwcoco.coco_sql_dataset.FallbackCocoBase
    Bases: object

class kwcoco.coco_sql_dataset.Category(**kwargs)
    Bases: Base

    id
        unique internal id

    name
        unique external name or identifier

    alias
        list of alter egos

    supercategory
        coarser category name

class kwcoco.coco_sql_dataset.KeypointCategory(**kwargs)
    Bases: Base

    id
        unique internal id

    name
        unique external name or identifier

    alias
        list of alter egos

    supercategory
        coarser category name

    reflection_id
        if augmentation reflects the image, change keypoint id to this
```

```
class kwcoco.coco_sql_dataset.Video(**kwargs)
Bases: Base

    id
        unique internal id
    name
    caption
    width
    height

class kwcoco.coco_sql_dataset.Image(**kwargs)
Bases: Base

    id
        unique internal id
    name
    file_name
    width
    height
    video_id
    timestamp
    frame_index
    channels
        See ChannelSpec
    warp_img_to_vid
        See TransformSpec
    auxiliary

class kwcoco.coco_sql_dataset.Annotation(**kwargs)
Bases: Base

    id
    image_id
    category_id
    track_id
    segmentation
    keypoints
    bbox
    score
```

```

weight
prob
iscrowd
caption

kwcoco.coco_sql_dataset.cls
    alias of Image

kwcoco.coco_sql_dataset.orm_to_dict(obj)
kwcoco.coco_sql_dataset.dict_restructure(item)
    Removes the unstructured field so the API is transparent to the user.

class kwcoco.coco_sql_dataset.SqlListProxy(session, cls)
    Bases: NiceRepr
    A view of an SQL table that behaves like a Python list

class kwcoco.coco_sql_dataset.SqlDictProxy(session, cls, keyattr=None, ignore_null=False)
    Bases: DictLike
    Duck-types an SQL table as a dictionary of dictionaries.

The key is specified by an indexed column (by default it is the id column). The values are dictionaries containing all data for that row.

```

---

**Note:** With SQLite indexes are B-Trees so lookup is O(log(N)) and not O(1) as will regular dictionaries. Iteration should still be O(N), but databases have much more overhead than Python dictionaries.

---

## Parameters

- **session** (*Session*) – the sqlalchemy session
- **cls** (*Type*) – the declarative sqlalchemy table class
- **keyattr** – the indexed column to use as the keys
- **ignore\_null** (*bool*) – if True, ignores any keys set to NULL, otherwise NULL keys are allowed.

## Example

```

>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> import pytest
>>> sql_dset, dct_dset = demo(num=10)
>>> proxy = sql_dset.index.anns

```

```

>>> keys = list(proxy.keys())
>>> values = list(proxy.values())
>>> items = list(proxy.items())
>>> item_keys = [t[0] for t in items]
>>> item_vals = [t[1] for t in items]

```

(continues on next page)

(continued from previous page)

```
>>> lut_vals = [proxy[key] for key in keys]
>>> assert item_vals == lut_vals == values
>>> assert item_keys == keys
>>> assert len(proxy) == len(keys)
```

```
>>> goodkey1 = keys[1]
>>> badkey1 = -10000000000000
>>> badkey2 = 'foobarbazbiz'
>>> badkey3 = object()
>>> assert goodkey1 in proxy
>>> assert badkey1 not in proxy
>>> assert badkey2 not in proxy
>>> assert badkey3 not in proxy
>>> with pytest.raises(KeyError):
>>>     proxy[badkey1]
>>> with pytest.raises(KeyError):
>>>     proxy[badkey2]
>>> with pytest.raises(KeyError):
>>>     proxy[badkey3]
```

```
>>> # xdoctest: +SKIP
>>> from kwcoc.coco_sql_dataset import _benchmark_dict_proxy_ops
>>> ti = _benchmark_dict_proxy_ops(proxy)
>>> print('ti.measures = {}'.format(ub.repr2(ti.measures, nl=2, align=':', precision=6)))
```

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoc.coco_sql_dataset import * # NOQA
>>> import kwcoc
>>> # Test the variant of the SqlDictProxy where we ignore None keys
>>> # This is the case for name_to_img and file_name_to_img
>>> dct_dset = kwcoc.CocoDataset.demo('shapes1')
>>> dct_dset.add_image(name='no_file_image1')
>>> dct_dset.add_image(name='no_file_image2')
>>> dct_dset.add_image(name='no_file_image3')
>>> sql_dset = dct_dset.view_sql(memory=True)
>>> assert len(dct_dset.index.imgs) == 4
>>> assert len(dct_dset.index.file_name_to_img) == 1
>>> assert len(dct_dset.index.name_to_img) == 3
>>> assert len(sql_dset.index.imgs) == 4
>>> assert len(sql_dset.index.file_name_to_img) == 1
>>> assert len(sql_dset.index.name_to_img) == 3
```

```
>>> proxy = sql_dset.index.file_name_to_img
>>> assert len(list(proxy.keys())) == 1
>>> assert len(list(proxy.values())) == 1
```

```
>>> proxy = sql_dset.index.name_to_img
>>> assert len(list(proxy.keys())) == 3
>>> assert len(list(proxy.values())) == 3
```

```
>>> proxy = sql_dset.index.imgs
>>> assert len(list(proxy.keys())) == 4
>>> assert len(list(proxy.values())) == 4
```

`keys()`

`values()`

`items()`

```
class kwcoco.coco_sql_dataset.SqlIdGroupDictProxy(session, valattr, keyattr, parent_keyattr,
                                                 group_order_attr=None)
```

Bases: `DictLike`

Similar to `SqlDictProxy`, but maps ids to groups of other ids.

Simulates a dictionary that maps ids of a parent table to all ids of another table corresponding to rows where a specific column has that parent id.

The items in the group can be sorted by the `group_order_attr` if specified.

For example, imagine two tables: images with one column (id) and annotations with two columns (id, image\_id). This class can help provide a mapping from each `image.id` to a `Set[annotation.id]` where those annotation rows have `annotation.image_id = image.id`.

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> sql_dset, dct_dset = demo(num=10)
>>> proxy = sql_dset.index.gid_to_aids
```

```
>>> keys = list(proxy.keys())
>>> values = list(proxy.values())
>>> items = list(proxy.items())
>>> item_keys = [t[0] for t in items]
>>> item_vals = [t[1] for t in items]
>>> lut_vals = [proxy[key] for key in keys]
>>> assert item_vals == lut_vals == values
>>> assert item_keys == keys
>>> assert len(proxy) == len(keys)
```

```
>>> # xdoctest: +SKIP
>>> from kwcoco.coco_sql_dataset import _benchmark_dict_proxy_ops
>>> ti = _benchmark_dict_proxy_ops(proxy)
>>> print('ti.measures = {}'.format(ub.repr2(ti.measures, nl=2, align=':', precision=6)))
```

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> import kwcoco
>>> # Test the group sorted variant of this by using vidid_to_gids
>>> # where the "gids" must be sorted by the image frame indexes
>>> dct_dset = kwcoco.CocoDataset.demo('vidshapes1')
>>> dct_dset.add_image(name='frame-index-order-demo1', frame_index=-30, video_id=1)
>>> dct_dset.add_image(name='frame-index-order-demo2', frame_index=10, video_id=1)
>>> dct_dset.add_image(name='frame-index-order-demo3', frame_index=3, video_id=1)
>>> dct_dset.add_video(name='empty-video1')
>>> dct_dset.add_video(name='empty-video2')
>>> dct_dset.add_video(name='empty-video3')
>>> sql_dset = dct_dset.view_sql(memory=True)
>>> orig = dct_dset.index.vidid_to_gids
>>> proxy = sql_dset.index.vidid_to_gids
>>> from kwcoco.util.util_json import indexable_allclose
>>> assert indexable_allclose(orig, dict(proxy))
>>> items = list(proxy.items())
>>> vals = list(proxy.values())
>>> keys = list(proxy.keys())
>>> assert len(keys) == len(vals)
>>> assert dict(zip(keys, vals)) == dict(items)
```

`keys()`

`items()`

`values()`

`class kwcoco.coco_sql_dataset.CocoSqlIndex`

Bases: `object`

Simulates the dictionary provided by `kwcoco.coco_dataset.CocoIndex`

`build(parent)`

`class kwcoco.coco_sql_dataset.CocoSqlDatabase(uri=None, tag=None, img_root=None)`

Bases: `AbstractCocoDataset`, `MixinCocoAccessors`, `MixinCocoObjects`, `MixinCocoStats`, `MixinCocoDraw`, `NiceRepr`

Provides an API nearly identical to `kwcoco.CocoDatabase`, but uses an SQL backend data store. This makes it robust to copy-on-write memory issues that arise when forking, as discussed in<sup>1</sup>.

---

**Note:** By default constructing an instance of the CocoSqlDatabase does not create a connection to the database. Use the `connect()` method to open a connection.

---

<sup>1</sup> <https://github.com/pytorch/pytorch/issues/13246>

## References

### Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> sql_dset, dct_dset = demo()
>>> dset1, dset2 = sql_dset, dct_dset
>>> tag1, tag2 = 'dset1', 'dset2'
>>> assert_dsets_allclose(sql_dset, dct_dset)
```

**MEMORY\_URI** = 'sqlite:///memory:'

**classmethod coerce**(*data, backend=None*)

Create an SQL CocoDataset from the input pointer.

### Example

```
import kwcoco dset = kwcoco.CocoDataset.demo('shapes8') data = dset.fpath self = CocoSqlDatabase.coerce(data)

from kwcoco.coco_sql_dataset import CocoSqlDatabase import kwcoco dset = kwcoco.CocoDataset.coerce('spacenet7.kwcoco.json')

self = CocoSqlDatabase.coerce(dset)

from kwcoco.coco_sql_dataset import CocoSqlDatabase sql_dset = CocoSqlDatabase.coerce('spacenet7.kwcoco.json')

# from kwcoco.coco_sql_dataset import CocoSqlDatabase import kwcoco sql_dset = kwcoco.CocoDataset.coerce('_spacenet7.kwcoco.view.v006.sqlite')
```

**disconnect()**

Drop references to any SQL or cache objects

**connect**(*readonly=False, verbose=0*)

Connects this instance to the underlying database.

## References

# details on read only mode, some of these didnt seem to work <https://github.com/sqlalchemy/sqlalchemy/blob/master/lib/sqlalchemy/dialects/sqlite/pysqlite.py#L71> <https://github.com/pudo/dataset/issues/136> <https://writeonly.wordpress.com/2009/07/16/simple-read-only-sqlalchemy-sessions/>

## CommandLine

```
KWCOCO_WITH_POSTGRESQL=1 xdoctest -m /home/joncrall/code/kwcoco/kwcoco/coco_sql_
dataset.py CocoSqlDatabase.connect
```

## Example

```
>>> # xdoctest: +REQUIRES(env:KWCOCO_WITH_POSTGRESQL)
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> # xdoctest: +REQUIRES(module:psycopg2)
>>> from kwkoco.coco_sql_dataset import * # NOQA
>>> dset = CocoSqlDatabase('postgresql+psycopg2://kwcoco:kwcoco_'
-> pw@localhost:5432/mydb')
>>> self = dset
>>> dset.connect(verbose=1)
```

**property fpath**

**delete(verbose=0)**

**populate\_from(dset, verbose=1)**

Copy the information in a CocoDataset into this SQL database.

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwkoco.coco_sql_dataset import _benchmark_dset_readtime # NOQA
>>> import kwkoco
>>> from kwkoco.coco_sql_dataset import *
>>> dset2 = dset = kwkoco.CocoDataset.demo()
>>> dset2.clear_annotations()
>>> dset1 = self = CocoSqlDatabase('sqlite:///memory:')
>>> self.connect()
>>> self.populate_from(dset)
>>> dset1.images = list(dset1.dataset['images'])
>>> print('dset1_images = {}'.format(ub.repr(dset1.images, nl=1)))
>>> print(dset2.dumps(newlines=True))
>>> assert_dsets_allclose(dset1, dset2, tag1='sql', tag2='dct')
>>> ti_sql = _benchmark_dset_readtime(dset1, 'sql')
>>> ti_dct = _benchmark_dset_readtime(dset2, 'dct')
>>> print('ti_sql.rankings = {}'.format(ub.repr2(ti_sql.rankings, nl=2,
-> precision=6, align=':')))
>>> print('ti_dct.rankings = {}'.format(ub.repr2(ti_dct.rankings, nl=2,
-> precision=6, align=':')))
```

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwkoco.coco_sql_dataset import _benchmark_dset_readtime # NOQA
>>> import kwkoco
>>> from kwkoco.coco_sql_dataset import *
>>> dset2 = dset = kwkoco.CocoDataset.demo()
>>> dset1 = self = CocoSqlDatabase('sqlite:///memory:')
>>> self.connect()
>>> self.populate_from(dset)
>>> assert_dsets_allclose(dset1, dset2, tag1='sql', tag2='dct')
```

(continues on next page)

(continued from previous page)

```
>>> ti_sql = _benchmark_dset_readtime(dset1, 'sql')
>>> ti_dct = _benchmark_dset_readtime(dset2, 'dct')
>>> print('ti_sql.rankings = {}'.format(ub.repr2(ti_sql.rankings, nl=2,
->precision=6, align=':')))
>>> print('ti_dct.rankings = {}'.format(ub.repr2(ti_dct.rankings, nl=2,
->precision=6, align=':')))
```

## CommandLine

```
KWCOCO_WITH_POSTGRESQL=1 xdoctest -m /home/joncrall/code/kwcoco/kwcoco/coco_sql_
-dataset.py CocoSqlDatabase.populate_from:1
```

## Example

```
>>> # xdoctest: +REQUIRES(env:KWCOCO_WITH_POSTGRESQL)
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> # xdoctest: +REQUIRES(module:psycopg2)
>>> from kwcoco.coco_sql_dataset import *  # NOQA
>>> import kwcoco
>>> dset = dset2 = kwcoco.CocoDataset.demo()
>>> self = dset1 = CocoSqlDatabase('postgresql+psycopg2://kwcoco:kwcoco_'
->pw@localhost:5432/test_populate')
>>> self.delete(verbose=1)
>>> self.connect(verbose=1)
>>> #self.populate_from(dset)
```

**property dataset**

**property anns**

**property cats**

**property imgs**

**property name\_to\_cat**

**raw\_table(table\_name)**

Loads an entire SQL table as a pandas DataFrame

**Parameters**

**table\_name (str)** – name of the table

**Returns**

pandas.DataFrame

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> self, dset = demo()
>>> table_df = self.raw_table('annotations')
>>> print(table_df)
```

### `tabular_targets()`

Convinience method to create an in-memory summary of basic annotation properties with minimal SQL overhead.

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> self, dset = demo()
>>> targets = self.tabular_targets()
>>> print(targets.pandas())
```

### `property bundle_dpath`

### `property data_fpath`

`data_fpath` is an alias of `fpath`

`kwcoco.coco_sql_dataset.cached_sql_coco_view(dct_db_fpath=None, sql_db_fpath=None, dset=None, force_rewrite=False, backend=None)`

Attempts to load a cached SQL-View dataset, only loading and converting the json dataset if necessary.

`kwcoco.coco_sql_dataset.ensure_sql_coco_view(dset, db_fpath=None, force_rewrite=False, backend=None)`

Create a cached on-disk SQL view of an on-disk COCO dataset.

# DEPRECATE, use cache function instead

---

**Note:** This function is fragile. It depends on looking at file modified timestamps to determine if it needs to write the dataset.

---

`kwcoco.coco_sql_dataset.demo(num=10, backend=None)`

`kwcoco.coco_sql_dataset.assert_dsets_allclose(dset1, dset2, tag1='dset1', tag2='dset2')`

`kwcoco.coco_sql_dataset.devcheck()`

Scratch work for things that should eventually become unit or doc tests

from kwcoco.coco\_sql\_dataset import \* # NOQA self, dset = demo()

### 2.1.2.10 kwcoco.compat\_dataset module

A wrapper around the basic kwcoco dataset with a pycocotools API.

We do not recommend using this API because it has some idiosyncrasies, where names can be misleading and APIs are not always clear / efficient: e.g.

- (1) catToImgs returns integer image ids but imgToAnns returns annotation dictionaries.
- (2) showAnns takes a dictionary list as an argument instead of an integer list

The cool thing is that this extends the kwcoco API so you can drop this for compatibility with the old API, but you still get access to all of the kwcoco API including dynamic addition / removal of categories / annotations / images.

```
class kwcoco.compat_dataset.COCO(annotation_file=None, **kw)
```

Bases: *CocoDataset*

A wrapper around the basic kwcoco dataset with a pycocotools API.

#### Example

```
>>> from kwcoco.compat_dataset import * # NOQA
>>> import kwcoco
>>> basic = kwcoco.CocoDataset.demo('shapes8')
>>> self = COCO(basic.dataset)
>>> self.info()
>>> print('self.imgToAnns = {!r}'.format(self.imgToAnns[1]))
>>> print('self.catToImgs = {!r}'.format(self.catToImgs))
```

**createIndex()**

**info()**

Print information about the annotation file.

**property imgToAnns**

**property catToImgs**

unlike the name implies, this actually goes from category to image ids Name retained for backward compatibility

**getAnnIds(imgIds=[], catIds=[], areaRng=[], iscrowd=None)**

Get ann ids that satisfy given filter conditions. default skips that filter

#### Parameters

- **imgIds** (*List[int]*) – get anns for given imgs
- **catIds** (*List[int]*) – get anns for given cats
- **areaRng** (*List[float]*) – get anns for given area range (e.g. [0 inf])
- **iscrowd** (*bool | None*) – get anns for given crowd label (False or True)

#### Returns

integer array of ann ids

#### Return type

*List[int]*

## Example

```
>>> from kwcoco.compat_dataset import * # NOQA
>>> import kwcoco
>>> self = COCO(kwcoco.CocoDataset.demo('shapes8').dataset)
>>> self.getAnnIds()
>>> self.getAnnIds(imgIds=1)
>>> self.getAnnIds(imgIds=[1])
>>> self.getAnnIds(catIds=[3])
```

**getCatIds**(*catNms*=[], *supNms*=[], *catIds*=[])

filtering parameters. default skips that filter.

### Parameters

- **catNms** (*List[str]*) – get cats for given cat names
- **supNms** (*List[str]*) – get cats for given supercategory names
- **catIds** (*List[int]*) – get cats for given cat ids

### Returns

integer array of cat ids

### Return type

*List[int]*

## Example

```
>>> from kwcoco.compat_dataset import * # NOQA
>>> import kwcoco
>>> self = COCO(kwcoco.CocoDataset.demo('shapes8').dataset)
>>> self.getCatIds()
>>> self.getCatIds(catNms=['superstar'])
>>> self.getCatIds(supNms=['raster'])
>>> self.getCatIds(catIds=[3])
```

**getImgIds**(*imgIds*=[], *catIds*=[])

Get img ids that satisfy given filter conditions.

### Parameters

- **imgIds** (*List[int]*) – get imgs for given ids
- **catIds** (*List[int]*) – get imgs with all given cats

### Returns

integer array of img ids

### Return type

*List[int]*

## Example

```
>>> from kwcoco.compat_dataset import * # NOQA
>>> import kwcoco
>>> self = COCO(kwcoco.CocoDataset.demo('shapes8').dataset)
>>> self.getImgIds(imgIds=[1, 2])
>>> self.getImgIds(catIds=[3, 6, 7])
>>> self.getImgIds(catIds=[3, 6, 7], imgIds=[1, 2])
```

### `loadAnns(ids=[])`

Load anns with the specified ids.

#### Parameters

`ids (List[int])` – integer ids specifying anns

#### Returns

loaded ann objects

#### Return type

List[dict]

### `loadCats(ids=[])`

Load cats with the specified ids.

#### Parameters

`ids (List[int])` – integer ids specifying cats

#### Returns

loaded cat objects

#### Return type

List[dict]

### `loadImgs(ids=[])`

Load anns with the specified ids.

#### Parameters

`ids (List[int])` – integer ids specifying img

#### Returns

loaded img objects

#### Return type

List[dict]

### `showAnns(annts, draw_bbox=False)`

Display the specified annotations.

#### Parameters

`anntns (List[Dict])` – annotations to display

### `loadRes(resFile)`

Load result file and return a result api object.

#### Parameters

`resFile (str)` – file name of result file

#### Returns

res result api object

**Return type**

object

**download(tarDir=None, imgIds=[])**

Download COCO images from mscoco.org server.

**Parameters**

- **tarDir** (*str | PathLike | None*) – COCO results directory name
- **imgIds** (*list*) – images to be downloaded

**loadNumpyAnnotations(data)**

Convert result data from a numpy array [Nx7] where each row contains {imageID,x1,y1,w,h,score,class}

**Parameters**

**data** (*numpy.ndarray*)

**Returns**

annotations (python nested list)

**Return type**

List[Dict]

**annToRLE(ann)**

Convert annotation which can be polygons, uncompressed RLE to RLE.

**Returns**

kwimage.Mask

---

**Note:**

- This requires the C-extensions for kwimage to be installed (i.e.

`pip install kwimage_ext`) due to the need to interface with the bytes RLE format.

---

**Example**

```
>>> from kwcoco.compat_dataset import * # NOQA
>>> import kwcoco
>>> self = COCO(kwcoco.CocoDataset.demo('shapes8').dataset)
>>> try:
>>>     rle = self.annToRLE(self.anns[1])
>>> except NotImplementedError:
>>>     import pytest
>>>     pytest.skip('missing kwimage c-extensions')
>>> else:
>>>     assert len(rle['counts']) > 2
>>> # xdoctest: +REQUIRES(module:pycocotools)
>>> self.conform(legacy=True)
>>> orig = self._aspycoco().annToRLE(self.anns[1])
```

**annToMask(ann)**

Convert annotation which can be polygons, uncompressed RLE, or RLE to binary mask.

**Returns**

binary mask (numpy 2D array)

**Return type**  
ndarray

---

**Note:** The mask is returned as a fortran (F-style) array with the same dimensions as the parent image.

---

### 2.1.2.11 kwcoco.exceptions module

**exception kwcoco.exceptions.AddError**

Bases: `ValueError`

Generic error when trying to add a category/annotation/image

**exception kwcoco.exceptions.DuplicateAddError**

Bases: `ValueError`

Error when trying to add a duplicate item

**exception kwcoco.exceptions.InvalidAddError**

Bases: `ValueError`

Error when trying to invalid data

### 2.1.2.12 kwcoco.kpf module

WIP:

Conversions to and from KPF format.

`kwcoco.kpf.coco_to_kpf(coco_dset)`

```
import kwcoco coco_dset = kwcoco.CocoDataset.demo('shapes8')
```

`kwcoco.kpf.demo()`

### 2.1.2.13 kwcoco.kw18 module

A helper for converting COCO to / from KW18 format.

KW18 File Format <https://docs.google.com/spreadsheets/d/1DFCwoTKnDv8qfy3raM7QXtir2Fjfj9j8-z8px5Bu0q8/edit#gid=10>

The kw18.trk files are text files, space delimited; each row is one frame of one track and all rows have the same number of columns. The fields are:

01) <code>track_ID</code>	: identifies the track
02) <code>num_frames:</code>	number of frames <b>in</b> the track
03) <code>frame_id</code>	: frame number <b>for</b> this track sample
04) <code>loc_x</code>	: X-coordinate of the track (image/ground coords)
05) <code>loc_y</code>	: Y-coordinate of the track (image/ground coords)
06) <code>vel_x</code>	: X-velocity of the <b>object</b> (image/ground coords)
07) <code>vel_y</code>	: Y-velocity of the <b>object</b> (image/ground coords)
08) <code>obj_loc_x</code>	: X-coordinate of the <b>object</b> (image coords)
09) <code>obj_loc_y</code>	: Y-coordinate of the <b>object</b> (image coords)
10) <code>bbox_min_x</code>	: minimum X-coordinate of bounding box (image coords)
11) <code>bbox_min_y</code>	: minimum Y-coordinate of bounding box (image coords)

(continues on next page)

(continued from previous page)

```

12) bbox_max_x      : maximum X-coordinate of bounding box (image coords)
13) bbox_max_y      : maximum Y-coordinate of bounding box (image coords)
14) area            : area of object (pixels)
15) world_loc_x     : X-coordinate of object in world
16) world_loc_y     : Y-coordinate of object in world
17) world_loc_z     : Z-coordinate of object in world
18) timestamp        : timestamp of frame (frames)

```

For the location **and** velocity of **object** centroids, use fields 4-7.

Bounding box **is** specified using coordinates of the top-left **and** bottom right corners. Fields 15-17 may be ignored.

The kw19.trk **and** kw20.trk files, when present, add the following field(s):

```

19) object class: estimated class of the object, either 1 (person), 2
    (vehicle), or 3 (other).
20) Activity ID -- refer to activities.txt for index and list of activities.

```

**class** kwcoco.kw18(*data*)

Bases: **DataFrameArray**

A DataFrame like object that stores KW18 column data

### Example

```

>>> import kwcoco
>>> from kwcoco.kw18 import KW18
>>> coco_dset = kwcoco.CocoDataset.demo('shapes')
>>> kw18_dset = KW18.from_coco(coco_dset)
>>> print(kw18_dset.pandas())

```

```

DEFAULT_COLUMNS = ['track_id', 'track_length', 'frame_number',
                   'tracking_plane_loc_x', 'tracking_plane_loc_y', 'velocity_x', 'velocity_y',
                   'image_loc_x', 'image_loc_y', 'img_bbox_tl_x', 'img_bbox_tl_y', 'img_bbox_br_x',
                   'img_bbox_br_y', 'area', 'world_loc_x', 'world_loc_y', 'world_loc_z', 'timestamp',
                   'confidence', 'object_type_id', 'activity_type_id']

```

**classmethod** demo()

**classmethod** from\_coco(*coco\_dset*)

**to\_coco**(*image\_paths=None*, *video\_name=None*)

Translates a kw18 files to a CocoDataset.

---

**Note:** kw18 does not contain complete information, and as such the returned coco dataset may need to be augmented.

---

### Parameters

- **image\_paths** (*Dict[int, str] | None*) – if specified, maps frame numbers to image file paths.
- **video\_name** (*str | None*) – if specified records the name of the video this kw18 belongs to

---

**Todo:**

- [X] allow kwargs to specify path to frames / videos
- 

**Example**

```
>>> from kwcoco.kw18 import KW18
>>> from os.path import join
>>> import ubelt as ub
>>> import kwimage
>>> # Prep test data - autogen a demo kw18 and write it to disk
>>> dpath = ub.Path.appdir('kwcoco/kw18').ensuredir()
>>> kw18_fpath = join(dpath, 'test.kw18')
>>> KW18.demo().dump(kw18_fpath)
>>> #
>>> # Load the kw18 file
>>> self = KW18.load(kw18_fpath)
>>> # Pretend that these image correspond to kw18 frame numbers
>>> frame_names = [kwimage.grab_test_image_fpath(k) for k in kwimage.grab_test_
...image.keys()]
>>> frame_ids = sorted(set(self['frame_number']))
>>> image_paths = dict(zip(frame_ids, frame_names))
>>> #
>>> # Convert the kw18 to kw coco and specify paths to images
>>> coco_dset = self.to_coco(image_paths=image_paths, video_name='dummy.mp4')
>>> #
>>> # Now we can draw images
>>> canvas = coco_dset.draw_image(1)
>>> # xdoctest: +REQUIRES(--draw)
>>> kwimage.imwrite('foo.jpg', canvas)
>>> # Draw all images
>>> for gid in coco_dset.imgs.keys():
>>>     canvas = coco_dset.draw_image(gid)
>>>     fpath = join(dpath, 'gid_{}.jpg'.format(gid))
>>>     print('write fpath = {!r}'.format(fpath))
>>>     kwimage.imwrite(fpath, canvas)
```

**classmethod** `load(file)`

**Example**

```
>>> import kwcoco
>>> from kwcoco.kw18 import KW18
>>> coco_dset = kwcoco.CocoDataset.demo('shapes')
>>> kw18_dset = KW18.from_coco(coco_dset)
>>> print(kw18_dset.pandas())
```

**classmethod** `loads(text)`

### Example

```
>>> self = KW18.demo()  
>>> text = self.dumps()  
>>> self2 = KW18.loads(text)  
>>> empty = KW18.loads('')
```

**dump(file)**

**dumps()**

### Example

```
>>> self = KW18.demo()  
>>> text = self.dumps()  
>>> print(text)
```

## 2.1.2.14 kwcoco.sensorchan\_spec module

This functionality has been moved to “delayed\_image”

## 2.1.3 Module contents

The Kitware COCO module defines a variant of the Microsoft COCO format, originally developed for the “collected images in context” object detection challenge. We are backwards compatible with the original module, but we also have improved implementations in several places, including segmentations, keypoints, annotation tracks, multi-spectral images, and videos (which represents a generic sequence of images).

A kwcoco file is a “manifest” that serves as a single reference that points to all images, categories, and annotations in a computer vision dataset. Thus, when applying an algorithm to a dataset, it is sufficient to have the algorithm take one dataset parameter: the path to the kwcoco file. Generally a kwcoco file will live in a “bundle” directory along with the data that it references, and paths in the kwcoco file will be relative to the location of the kwcoco file itself.

The main data structure in this model is largely based on the implementation in <https://github.com/cocodataset/cocoapi>. It uses the same efficient core indexing data structures, but in our implementation the indexing can be optionally turned off, functions are silent by default (with the exception of long running processes, which optionally show progress by default). We support helper functions that add and remove images, categories, and annotations.

The `kwcoco.CocoDataset` class is capable of dynamic addition and removal of categories, images, and annotations. Has better support for keypoints and segmentation formats than the original COCO format. Despite being written in Python, this data structure is reasonably efficient.

```
>>> import kwcoco  
>>> import json  
>>> # Create demo data  
>>> demo = kwcoco.CocoDataset.demo()  
>>> # Reroot can switch between absolute / relative-paths  
>>> demo.reroot(absolute=True)  
>>> # could also use demo.dump / demo.dumps, but this is more explicit  
>>> text = json.dumps(demo.dataset)  
>>> with open('demo.json', 'w') as file:
```

(continues on next page)

(continued from previous page)

```

>>>     file.write(text)

>>> # Read from disk
>>> self = kwcoco.CocoDataset('demo.json')

>>> # Add data
>>> cid = self.add_category('Cat')
>>> gid = self.add_image('new-img.jpg')
>>> aid = self.add_annotation(image_id=gid, category_id=cid, bbox=[0, 0, 100, 100])

>>> # Remove data
>>> self.remove_annotations([aid])
>>> self.remove_images([gid])
>>> self.remove_categories([cid])

>>> # Look at data
>>> import ubelt as ub
>>> print(ub.repr2(self.basic_stats(), nl=1))
>>> print(ub.repr2(self.extended_stats(), nl=2))
>>> print(ub.repr2(self.boxsize_stats(), nl=3))
>>> print(ub.repr2(self.category_annotation_frequency()))

>>> # Inspect data
>>> # xdoctest: +REQUIRES(module:kwplot)
>>> import kwplot
>>> kwplot.autompl()
>>> self.show_image(gid=1)

>>> # Access single-item data via imgs, cats, anns
>>> cid = 1
>>> self.cats[cid]
{'id': 1, 'name': 'astronaut', 'supercategory': 'human'}

>>> gid = 1
>>> self.imgs[gid]
{'id': 1, 'file_name': '...astro.png', 'url': 'https://i.imgur.com/KXhKM72.png'}

>>> aid = 3
>>> self.anns[aid]
{'id': 3, 'image_id': 1, 'category_id': 3, 'line': [326, 369, 500, 500]}

>>> # Access multi-item data via the annots and images helper objects
>>> aids = self.index.gid_to_aids[2]
>>> annots = self.annots(aids)

>>> print('annots = {}'.format(ub.repr2(annots, nl=1, sv=1)))
annots = <Annots(num=2)>

>>> annots.lookup('category_id')
[6, 4]

```

(continues on next page)

(continued from previous page)

```
>>> annots.lookup('bbox')
[[37, 6, 230, 240], [124, 96, 45, 18]]

>>> # built in conversions to efficient kwimage array DataStructures
>>> print(ub.repr2(annots.detections.data, sv=1))
{
    'boxes': <Boxes( xywh,
                      array([[ 37.,   6., 230., 240.],
                             [124.,  96.,  45.,  18.]], dtype=float32))>,
    'class_idxs': [5, 3],
    'keypoints': <PointsList(n=2)>,
    'segmentations': <PolygonList(n=2)>,
}

>>> gids = list(self.imgs.keys())
>>> images = self.images(gids)
>>> print('images = {}'.format(ub.repr2(images, nl=1, sv=1)))
images = <Images(num=3)>

>>> images.lookup('file_name')
['...astro.png', '...carl.png', '...stars.png']

>>> print('images.annots = {}'.format(images.annots))
images.annots = <AnnotGroups(n=3, m=3.7, s=3.9)>

>>> print('images.annots.cids = {!r}'.format(images.annots.cids))
images.annots.cids = [[1, 2, 3, 4, 5, 5, 5, 5, 5], [6, 4], []]
```

### 2.1.3.1 CocoDataset API

The following is a logical grouping of the public kwcoco.CocoDataset API attributes and methods. See the in-code documentation for further details.

#### 2.1.3.1.1 CocoDataset classmethods (via MixinCocoExtras)

- `kwcoco.CocoDataset.coerce` - Attempt to transform the input into the intended CocoDataset.
- `kwcoco.CocoDataset.demo` - Create a toy coco dataset for testing and demo purposes
- `kwcoco.CocoDataset.random` - Creates a random CocoDataset according to distribution parameters

### 2.1.3.1.2 CocoDataset classmethods (via CocoDataset)

- `kwcoco.CocoDataset.from_coco_paths` - Constructor from multiple coco file paths.
- `kwcoco.CocoDataset.from_data` - Constructor from a json dictionary
- `kwcoco.CocoDataset.from_image_paths` - Constructor from a list of images paths.

### 2.1.3.1.3 CocoDataset slots

- `kwcoco.CocoDataset.index` - an efficient lookup index into the coco data structure. The index defines its own attributes like `anns`, `cats`, `imgs`, `gid_to_aids`, `file_name_to_img`, etc. See `CocoIndex` for more details on which attributes are available.
- `kwcoco.CocoDataset.hashid` - If computed, this will be a hash uniquely identifying the dataset. To ensure this is computed see `kwcoco.coco_dataset.MixinCocoExtras._build_hashid()`.
- `kwcoco.CocoDataset.hashid_parts` -
- `kwcoco.CocoDataset.tag` - A tag indicating the name of the dataset.
- `kwcoco.CocoDataset.dataset` - raw json data structure. This is the base dictionary that contains {‘annotations’: List, ‘images’: List, ‘categories’: List}
- `kwcoco.CocoDataset.bundle_dpath` - If known, this is the root path that all image file names are relative to. This can also be manually overwritten by the user.
- `kwcoco.CocoDataset.assets_dpath` -
- `kwcoco.CocoDataset.cache_dpath` -

### 2.1.3.1.4 CocoDataset properties

- `kwcoco.CocoDataset.anns` -
- `kwcoco.CocoDataset.cats` -
- `kwcoco.CocoDataset.cid_to_aids` -
- `kwcoco.CocoDataset.data_fpath` -
- `kwcoco.CocoDataset.data_root` -
- `kwcoco.CocoDataset.fpath` - if known, this stores the filepath the dataset was loaded from
- `kwcoco.CocoDataset.gid_to_aids` -
- `kwcoco.CocoDataset.img_root` -
- `kwcoco.CocoDataset.imgs` -
- `kwcoco.CocoDataset.n_annot` -
- `kwcoco.CocoDataset.n_cats` -
- `kwcoco.CocoDataset.n_images` -
- `kwcoco.CocoDataset.n_videos` -
- `kwcoco.CocoDataset.name_to_cat` -

### 2.1.3.1.5 CocoDataset methods (via MixinCocoAddRemove)

- `kwcoco.CocoDataset.add_annotation` - Add an annotation to the dataset (dynamically updates the index)
- `kwcoco.CocoDataset.add_annotations` - Faster less-safe multi-item alternative to add\_annotation.
- `kwcoco.CocoDataset.add_category` - Adds a category
- `kwcoco.CocoDataset.add_image` - Add an image to the dataset (dynamically updates the index)
- `kwcoco.CocoDataset.add_images` - Faster less-safe multi-item alternative
- `kwcoco.CocoDataset.add_video` - Add a video to the dataset (dynamically updates the index)
- `kwcoco.CocoDataset.clear_annotations` - Removes all annotations (but not images and categories)
- `kwcoco.CocoDataset.clear_images` - Removes all images and annotations (but not categories)
- `kwcoco.CocoDataset.ensure_category` - Like add\_category(), but returns the existing category id if it already exists instead of failing. In this case all metadata is ignored.
- `kwcoco.CocoDataset.ensure_image` - Like add\_image(), but returns the existing image id if it already exists instead of failing. In this case all metadata is ignored.
- `kwcoco.CocoDataset.remove_annotation` - Remove a single annotation from the dataset
- `kwcoco.CocoDataset.remove_annotation_keypoints` - Removes all keypoints with a particular category
- `kwcoco.CocoDataset.remove_annotations` - Remove multiple annotations from the dataset.
- `kwcoco.CocoDataset.remove_categories` - Remove categories and all annotations in those categories. Currently does not change any hierarchy information
- `kwcoco.CocoDataset.remove_images` - Remove images and any annotations contained by them
- `kwcoco.CocoDataset.remove_keypoint_categories` - Removes all keypoints of a particular category as well as all annotation keypoints with those ids.
- `kwcoco.CocoDataset.remove_videos` - Remove videos and any images / annotations contained by them
- `kwcoco.CocoDataset.set_annotation_category` - Sets the category of a single annotation

### 2.1.3.1.6 CocoDataset methods (via MixinCocoObjects)

- `kwcoco.CocoDataset.annots` - Return vectorized annotation objects
- `kwcoco.CocoDataset.categories` - Return vectorized category objects
- `kwcoco.CocoDataset.images` - Return vectorized image objects
- `kwcoco.CocoDataset.videos` - Return vectorized video objects

### 2.1.3.1.7 CocoDataset methods (via MixinCocoStats)

- `kwcoco.CocoDataset.basic_stats` - Reports number of images, annotations, and categories.
- `kwcoco.CocoDataset.boxsize_stats` - Compute statistics about bounding box sizes.
- `kwcoco.CocoDataset.category_annotation_frequency` - Reports the number of annotations of each category
- `kwcoco.CocoDataset.category_annotation_type_frequency` - Reports the number of annotations of each type for each category
- `kwcoco.CocoDataset.conform` - Make the COCO file conform a stricter spec, infers attributes where possible.
- `kwcoco.CocoDataset.extended_stats` - Reports number of images, annotations, and categories.
- `kwcoco.CocoDataset.find_representative_images` - Find images that have a wide array of categories. Attempt to find the fewest images that cover all categories using images that contain both a large and small number of annotations.
- `kwcoco.CocoDataset.keypoint_annotation_frequency` -
- `kwcoco.CocoDataset.stats` - This function corresponds to `kwcoco.cli.coco_stats`.
- `kwcoco.CocoDataset.validate` - Performs checks on this coco dataset.

### 2.1.3.1.8 CocoDataset methods (via MixinCocoAccessors)

- `kwcoco.CocoDataset.category_graph` - Construct a networkx category hierarchy
- `kwcoco.CocoDataset.delayed_load` - Experimental method
- `kwcoco.CocoDataset.get_auxiliary_fpath` - Returns the full path to auxiliary data for an image
- `kwcoco.CocoDataset.get_image_fpath` - Returns the full path to the image
- `kwcoco.CocoDataset.keypoint_categories` - Construct a consistent CategoryTree representation of key-point classes
- `kwcoco.CocoDataset.load_annot_sample` - Reads the chip of an annotation. Note this is much less efficient than using a sampler, but it doesn't require disk cache.
- `kwcoco.CocoDataset.load_image` - Reads an image from disk and
- `kwcoco.CocoDataset.object_categories` - Construct a consistent CategoryTree representation of object classes

### 2.1.3.1.9 CocoDataset methods (via CocoDataset)

- `kwcoco.CocoDataset.copy` - Deep copies this object
- `kwcoco.CocoDataset.dump` - Writes the dataset out to the json format
- `kwcoco.CocoDataset.dumps` - Writes the dataset out to the json format
- `kwcoco.CocoDataset.subset` - Return a subset of the larger coco dataset by specifying which images to port. All annotations in those images will be taken.
- `kwcoco.CocoDataset.union` - Merges multiple `CocoDataset` items into one. Names and associations are retained, but ids may be different.

- `kwcoco.CocoDataset.view_sql` - Create a cached SQL interface to this dataset suitable for large scale multiprocessing use cases.

### 2.1.3.1.10 CocoDataset methods (via MixinCocoExtras)

- `kwcoco.CocoDataset.corrupted_images` - Check for images that don't exist or can't be opened
- `kwcoco.CocoDataset.missing_images` - Check for images that don't exist
- `kwcoco.CocoDataset.rename_categories` - Rename categories with a potentially coarser categorization.
- `kwcoco.CocoDataset.reroot` - Rebase image/data paths onto a new image/data root.

### 2.1.3.1.11 CocoDataset methods (via MixinCocoDraw)

- `kwcoco.CocoDataset.draw_image` - Use kwimage to draw all annotations on an image and return the pixels as a numpy array.
- `kwcoco.CocoDataset.imread` - Loads a particular image
- `kwcoco.CocoDataset.show_image` - Use matplotlib to show an image with annotations overlaid

**class kwcoco.AbstractCocoDataset**

Bases: ABC

This is a common base for all variants of the Coco Dataset

At the time of writing there is `kwcoco.CocoDataset` (which is the dictionary-based backend), and the `kwcoco.coco_sql_dataset.CocoSqlDataset`, which is experimental.

**class kwcoco.CategoryTree(graph=None, checks=True)**

Bases: NiceRepr

Wrapper that maintains flat or hierarchical category information.

Helps compute softmaxes and probabilities for tree-based categories where a directed edge (A, B) represents that A is a superclass of B.

---

**Note:** There are three basic properties that this object maintains:

**node:**

Alphanumeric string names that should be generally descriptive. Using spaces and special characters in these names is discouraged, but can be done. This is the COCO category "name" attribute. For categories this may be denoted as (name, node, cname, catname).

**id:**

The integer id of a category should ideally remain consistent. These are often given by a dataset (e.g. a COCO dataset). This is the COCO category "id" attribute. For categories this is often denoted as (id, cid).

**index:**

Contiguous zero-based indices that indexes the list of categories. These should be used for the fastest access in

(continues on next page)

(continued from previous page)

backend computation tasks. Typically corresponds to the ordering of the channels `in` the final linear layer `in` an associated model. For categories this `is` often denoted as `(index, cidx, idx, or cx)`.

## Variables

- `idx_to_node` (`List[str]`) – a list of class names. Implicitly maps from index to category name.
- `id_to_node` (`Dict[int, str]`) – maps integer ids to category names
- `node_to_id` (`Dict[str, int]`) – maps category names to ids
- `node_to_idx` (`Dict[str, int]`) – maps category names to indexes
- `graph` (`networkx.Graph`) – a Graph that stores any hierarchy information. For standard mutually exclusive classes, this graph is edgeless. Nodes in this graph can maintain category attributes / properties.
- `idx_groups` (`List[List[int]]`) – groups of category indices that share the same parent category.

## Example

```
>>> from kwcoco.category_tree import *
>>> graph = nx.from_dict_of_lists({
>>>     'background': [],
>>>     'foreground': ['animal'],
>>>     'animal': ['mammal', 'fish', 'insect', 'reptile'],
>>>     'mammal': ['dog', 'cat', 'human', 'zebra'],
>>>     'zebra': ['grevys', 'plains'],
>>>     'grevys': ['fred'],
>>>     'dog': ['boxer', 'beagle', 'golden'],
>>>     'cat': ['maine coon', 'persian', 'sphynx'],
>>>     'reptile': ['bearded dragon', 't-rex'],
>>> }, nx.DiGraph)
>>> self = CategoryTree(graph)
>>> print(self)
<CategoryTree(nNodes=22, maxDepth=6, maxBreadth=4...)>
```

## Example

```
>>> # The coerce classmethod is the easiest way to create an instance
>>> import kwcoco
>>> kwcoco.CategoryTree.coerce(['a', 'b', 'c'])
<CategoryTree...nNodes=3, nodes='a', 'b', 'c'...
>>> kwcoco.CategoryTree.coerce(4)
<CategoryTree...nNodes=4, nodes='class_1', 'class_2', 'class_3', ...
>>> kwcoco.CategoryTree.coerce(4)
```

`copy()`

`classmethod from_mutex(nodes, bg_hack=True)`

**Parameters**

`nodes` (`List[str]`) – or a list of class names (in which case they will all be assumed to be mutually exclusive)

**Example**

```
>>> print(CategoryTree.from_mutex(['a', 'b', 'c']))
<CategoryTree(nNodes=3, ...)>
```

`classmethod from_json(state)`

**Parameters**

`state` (`Dict`) – see `__getstate__` / `__json__` for details

`classmethod from_coco(categories)`

Create a CategoryTree object from coco categories

**Parameters**

`List[Dict]` – list of coco-style categories

`classmethod coerce(data, **kw)`

Attempt to coerce data as a CategoryTree object.

This is primarily useful for when the software stack depends on categories being represented.

This will work if the input data is a specially formatted json dict, a list of mutually exclusive classes, or if it is already a CategoryTree. Otherwise an error will be thrown.

**Parameters**

- `data (object)` – a known representation of a category tree.
- `**kwargs` – input type specific arguments

**Returns**

`self`

**Return type**

`CategoryTree`

**Raises**

- `TypeError` – if the input format is unknown –
- `ValueError` – if kwargs are not compatible with the input format –

## Example

```
>>> import kwCOCO
>>> classes1 = kwCOCO.CategoryTree.coerce(3) # integer
>>> classes2 = kwCOCO.CategoryTree.coerce(classes1.__json__()) # graph dict
>>> classes3 = kwCOCO.CategoryTree.coerce(['class_1', 'class_2', 'class_3']) #_
    ~mutex list
>>> classes4 = kwCOCO.CategoryTree.coerce(classes1.graph) # nx Graph
>>> classes5 = kwCOCO.CategoryTree.coerce(classes1) # cls
>>> # xdoctest: +REQUIRES(module:nd sampler)
>>> import nd sampler
>>> classes6 = nd sampler.CategoryTree.coerce(3)
>>> classes7 = nd sampler.CategoryTree.coerce(classes1)
>>> classes8 = kwCOCO.CategoryTree.coerce(classes6)
```

**classmethod demo(key='coco', \*\*kwargs)**

### Parameters

**key (str)** – specify which demo dataset to use. Can be ‘coco’ (which uses the default coco demo data). Can be ‘btree’ which creates a binary tree and accepts kwargs ‘r’ and ‘h’ for branching-factor and height. Can be ‘btree2’, which is the same as btree but returns strings

## CommandLine

```
xdoctest -m ~/code/kwCOCO/kwCOCO/category_tree.py CategoryTree.demo
```

## Example

```
>>> from kwCOCO.category_tree import *
>>> self = CategoryTree.demo()
>>> print('self = {}'.format(self))
self = <CategoryTree(nNodes=10, maxDepth=2, maxBreadth=4...)>
```

**to\_coco()**

Converts to a coco-style data structure

### Yields

*Dict* – coco category dictionaries

**property id\_to\_idx**

**Example:**

```
>>> import kwCOCO
>>> self = kwCOCO.CategoryTree.demo()
>>> self.id_to_idx[1]
```

**property idx\_to\_id**

**Example:**

```
>>> import kwCOCO
>>> self = kwCOCO.CategoryTree.demo()
>>> self.idx_to_id[0]
```

**idx\_to\_ancestor\_idxs**(*include\_self=True*)

Mapping from a class index to its ancestors

**Parameters**

**include\_self** (*bool, default=True*) – if True includes each node as its own ancestor.

**idx\_to\_descendants\_idxs**(*include\_self=False*)

Mapping from a class index to its descendants (including itself)

**Parameters**

**include\_self** (*bool, default=False*) – if True includes each node as its own descendant.

**idx\_pairwise\_distance()**

Get a matrix encoding the distance from one class to another.

**Distances**

- from parents to children are positive (descendants),
- from children to parents are negative (ancestors),
- between unreachable nodes (wrt to forward and reverse graph) are nan.

**is\_mutex()**

Returns True if all categories are mutually exclusive (i.e. flat)

If true, then the classes may be represented as a simple list of class names without any loss of information, otherwise the underlying category graph is necessary to preserve all knowledge.

---

**Todo:**

- [ ] what happens when we have a dummy root?
- 

**property num\_classes****property class\_names****property category\_names****property cats**

Returns a mapping from category names to category attributes.

If this category tree was constructed from a coco-dataset, then this will contain the coco category attributes.

**Returns**

Dict[str, Dict[str, object]]

**Example**

```
>>> from kwcoco.category_tree import *
>>> self = CategoryTree.demo()
>>> print('self.cats = {!r}'.format(self.cats))
```

**index(node)**

Return the index that corresponds to the category name

**show()**

**forest\_str()****normalize()**

Applies a normalization scheme to the categories.

Note: this may break other tasks that depend on exact category names.

**Returns**

CategoryTree

**Example**

```
>>> from kwcoco.category_tree import * # NOQA
>>> import kwcoco
>>> orig = kwcoco.CategoryTree.demo('animals_v1')
>>> self = kwcoco.CategoryTree(nx.relabel_nodes(orig.graph, str.upper))
>>> norm = self.normalize()
```

**class kwcoco.ChannelSpec(spec, parsed=None)**

Bases: BaseChannelSpec

Parse and extract information about network input channel specs for early or late fusion networks.

Behaves like a dictionary of FusedChannelSpec objects

**Todo:**

- [ ] Rename to something that indicates this is a collection of FusedChannelSpec? MultiChannelSpec?

**Note:** This class name and API is in flux and subject to change.

**Note:** The pipe ('|') character represents an early-fused input stream, and order matters (it is non-commutative).

The comma (',') character separates different inputs streams/branches for a multi-stream/branch network which will be later fused. Order does not matter

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> # Integer spec
>>> ChannelSpec.coerce(3)
<ChannelSpec(u0|u1|u2) ...>
```

```
>>> # single mode spec
>>> ChannelSpec.coerce('rgb')
<ChannelSpec(rgb) ...>
```

```
>>> # early fused input spec
>>> ChannelSpec.coerce('rgb|disparity')
<ChannelSpec(rgb|disparity) ...>
```

```
>>> # late fused input spec
>>> ChannelSpec.coerce('rgb,disparity')
<ChannelSpec(rgb,disparity) ...>
```

```
>>> # early and late fused input spec
>>> ChannelSpec.coerce('rgb|ir,disparity')
<ChannelSpec(rgb|ir,disparity) ...>
```

## Example

```
>>> self = ChannelSpec('gray')
>>> print('self.info = {}'.format(ub.repr2(self.info, nl=1)))
>>> self = ChannelSpec('rgb')
>>> print('self.info = {}'.format(ub.repr2(self.info, nl=1)))
>>> self = ChannelSpec('rgb|disparity')
>>> print('self.info = {}'.format(ub.repr2(self.info, nl=1)))
>>> self = ChannelSpec('rgb|disparity,disparity')
>>> print('self.info = {}'.format(ub.repr2(self.info, nl=1)))
>>> self = ChannelSpec('rgb,disparity,flowx|flowy')
>>> print('self.info = {}'.format(ub.repr2(self.info, nl=1)))
```

## Example

```
>>> specs = [
>>>     'rgb',           # and rgb input
>>>     'rgb|disparity', # rgb early fused with disparity
>>>     'rgb,disparity', # rgb early late with disparity
>>>     'rgb|ir,disparity', # rgb early fused with ir and late fused with disparity
>>>     3,               # 3 unknown channels
>>> ]
>>> for spec in specs:
>>>     print('===== ')
>>>     print('spec = {!r}'.format(spec))
>>>     #
>>>     self = ChannelSpec.coerce(spec)
>>>     print('self = {!r}'.format(self))
>>>     sizes = self.sizes()
>>>     print('sizes = {!r}'.format(sizes))
>>>     print('self.info = {}'.format(ub.repr2(self.info, nl=1)))
>>>     #
>>>     item = self._demo_item((1, 1), rng=0)
>>>     inputs = self.encode(item)
>>>     components = self.decode(inputs)
>>>     input_shapes = ub.map_vals(lambda x: x.shape, inputs)
>>>     component_shapes = ub.map_vals(lambda x: x.shape, components)
```

(continues on next page)

(continued from previous page)

```
>>> print('item = {}'.format(ub.repr2(item, precision=1)))
>>> print('inputs = {}'.format(ub.repr2(inputs, precision=1)))
>>> print('input_shapes = {}'.format(ub.repr2(input_shapes)))
>>> print('components = {}'.format(ub.repr2(components, precision=1)))
>>> print('component_shapes = {}'.format(ub.repr2(component_shapes, nl=1)))
```

**property spec****property info****classmethod coerce(data)**

Attempt to interpret the data as a channel specification

**Returns**

ChannelSpec

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> data = FusedChannelSpec.coerce(3)
>>> assert ChannelSpec.coerce(data).spec == 'u0|u1|u2'
>>> data = ChannelSpec.coerce(3)
>>> assert data.spec == 'u0|u1|u2'
>>> assert ChannelSpec.coerce(data).spec == 'u0|u1|u2'
>>> data = ChannelSpec.coerce('u:3')
>>> assert data.normalize().spec == 'u.0|u.1|u.2'
```

**parse()**

Build internal representation

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> self = ChannelSpec('b1|b2|b3|rgb,B:3')
>>> print(self.parse())
>>> print(self.normalize().parse())
>>> ChannelSpec('').parse()
```

**Example**

```
>>> base = ChannelSpec('rgb|disparity,flowx|r|flowy')
>>> other = ChannelSpec('rgb')
>>> self = base.intersection(other)
>>> assert self.numel() == 4
```

**concise()**

**Example**

```
>>> self = ChannelSpec('b1|b2,b3|rgb|B.0,B.1|B.2')
>>> print(self.concise().spec)
b1|b2,b3|r|g|b|B.0,B.1:3
```

**normalize()**

Replace aliases with explicit single-band-per-code specs

**Returns**

normalized spec

**Return type**

*ChannelSpec*

**Example**

```
>>> self = ChannelSpec('b1|b2,b3|rgb,B:3')
>>> normed = self.normalize()
>>> print('self  = {}'.format(self))
>>> print('normed = {}'.format(normed))
self   = <ChannelSpec(b1|b2,b3|rgb,B:3)>
normed = <ChannelSpec(b1|b2,b3|r|g|b,B.0|B.1|B.2)>
```

**keys()****values()****items()****fuse()**

Fuse all parts into an early fused channel spec

**Returns**

FusedChannelSpec

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> self = ChannelSpec.coerce('b1|b2,b3|rgb,B:3')
>>> fused = self.fuse()
>>> print('self  = {}'.format(self))
>>> print('fused = {}'.format(fused))
self   = <ChannelSpec(b1|b2,b3|rgb,B:3)>
fused = <FusedChannelSpec(b1|b2|b3|rgb|B:3)>
```

**streams()**

Breaks this spec up into one spec for each early-fused input stream

**Example**

```
self = ChannelSpec.coerce('r|g,B1|B2,fx|fy') list(map(len, self.streams()))
code_list()
as_path()
```

Returns a string suitable for use in a path.

Note, this may no longer be a valid channel spec

**difference(*other*)**

Set difference. Remove all instances of other channels from this set of channels.

**Example**

```
>>> from delayed_image.channel_spec import *
>>> self = ChannelSpec('rgb|disparity,flowx|r|flowy')
>>> other = ChannelSpec('rgb')
>>> print(self.difference(other))
>>> other = ChannelSpec('flowx')
>>> print(self.difference(other))
<ChannelSpec(disparity,flowx|flowy)>
<ChannelSpec(r|g|b|disparity,r|flowy)>
```

**Example**

```
>>> from delayed_image.channel_spec import *
>>> self = ChannelSpec('a|b,c|d')
>>> new = self - {'a', 'b'}
>>> len(new.sizes()) == 1
>>> empty = new - 'c|d'
>>> assert empty.numel() == 0
```

**intersection(*other*)**

Set difference. Remove all instances of other channels from this set of channels.

**Example**

```
>>> from delayed_image.channel_spec import *
>>> self = ChannelSpec('rgb|disparity,flowx|r|flowy')
>>> other = ChannelSpec('rgb')
>>> new = self.intersection(other)
>>> print(new)
>>> print(new.numel())
>>> other = ChannelSpec('flowx')
>>> new = self.intersection(other)
>>> print(new)
>>> print(new.numel())
<ChannelSpec(r|g|b,r)>
4
```

(continues on next page)

(continued from previous page)

```
<ChannelSpec(flowx)>
1
```

**union(*other*)**

Union simply tags on a second channel spec onto this one. Duplicates are maintained.

**Example**

```
>>> from delayed_image.channel_spec import *
>>> self = ChannelSpec('rgb|disparity,flowx|r|flowy')
>>> other = ChannelSpec('rgb')
>>> new = self.union(other)
>>> print(new)
>>> print(new.numel())
>>> other = ChannelSpec('flowx')
>>> new = self.union(other)
>>> print(new)
>>> print(new.numel())
<ChannelSpec(r|g|b|disparity,flowx|r|flowy,r|g|b)>
10
<ChannelSpec(r|g|b|disparity,flowx|r|flowy,flowx)>
8
```

**issubset(*other*)****issuperset(*other*)****numel()**

Total number of channels in this spec

**sizes()**

Number of dimensions for each fused stream channel

IE: The EARLY-FUSED channel sizes

**Example**

```
>>> self = ChannelSpec('rgb|disparity,flowx|flowy,B:10')
>>> self.normalize().concise()
>>> self.sizes()
```

**unique(*normalize=False*)**

Returns the unique channels that will need to be given or loaded

**encode(*item, axis=0, mode=1*)**

Given a dictionary containing preloaded components of the network inputs, build a concatenated (fused) network representations of each input stream.

**Parameters**

- **item** (*Dict[str, Tensor]*) – a batch item containing unfused parts. each key should be a single-stream (optionally early fused) channel key.

- **axis** (*int, default=0*) – concatenation dimension

**Returns**

mapping between input stream and its early fused tensor input.

**Return type**

Dict[str, Tensor]

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> import numpy as np
>>> dims = (4, 4)
>>> item = {
>>>     'rgb': np.random.rand(3, *dims),
>>>     'disparity': np.random.rand(1, *dims),
>>>     'flowx': np.random.rand(1, *dims),
>>>     'flowy': np.random.rand(1, *dims),
>>> }
>>> # Complex Case
>>> self = ChannelSpec('rgb,disparity,rgb|disparity|flowx|flowy,flowx|flowy')
>>> fused = self.encode(item)
>>> input_shapes = ub.map_vals(lambda x: x.shape, fused)
>>> print('input_shapes = {}'.format(ub.repr2(input_shapes, nl=1)))
>>> # Simpler case
>>> self = ChannelSpec('rgb|disparity')
>>> fused = self.encode(item)
>>> input_shapes = ub.map_vals(lambda x: x.shape, fused)
>>> print('input_shapes = {}'.format(ub.repr2(input_shapes, nl=1)))
```

**Example**

```
>>> # Case where we have to break up early fused data
>>> import numpy as np
>>> dims = (40, 40)
>>> item = {
>>>     'rgb|disparity': np.random.rand(4, *dims),
>>>     'flowx': np.random.rand(1, *dims),
>>>     'flowy': np.random.rand(1, *dims),
>>> }
>>> # Complex Case
>>> self = ChannelSpec('rgb,disparity,rgb|disparity,rgb|disparity|flowx|flowy,
>>> ~flowx|flowy,flowx,disparity')
>>> inputs = self.encode(item)
>>> input_shapes = ub.map_vals(lambda x: x.shape, inputs)
>>> print('input_shapes = {}'.format(ub.repr2(input_shapes, nl=1)))
```

```
>>> # xdoctest: +REQUIRES(--bench)
>>> #self = ChannelSpec('rgb/disparity,flowx/flowy')
>>> import timerit
>>> ti = timerit.Timerit(100, bestof=10, verbose=2)
```

(continues on next page)

(continued from previous page)

```
>>> for timer in ti.reset('mode=simple'):
>>>     with timer:
>>>         inputs = self.encode(item, mode=0)
>>> for timer in ti.reset('mode=minimize-concat'):
>>>     with timer:
>>>         inputs = self.encode(item, mode=1)
```

**decode(inputs, axis=1)**

break an early fused item into its components

**Parameters**

- **inputs** (*Dict[str, Tensor]*) – dictionary of components
- **axis** (*int, default=1*) – channel dimension

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> import numpy as np
>>> dims = (4, 4)
>>> item_components = {
>>>     'rgb': np.random.rand(3, *dims),
>>>     'ir': np.random.rand(1, *dims),
>>> }
>>> self = ChannelSpec('rgb|ir')
>>> item_encoded = self.encode(item_components)
>>> batch = {k: np.concatenate([v[None, :], v[None, :]]), axis=0}
>>>     for k, v in item_encoded.items()
>>> components = self.decode(batch)
```

**Example**

```
>>> # xdoctest: +REQUIRES(module:netharn, module:torch)
>>> import torch
>>> import numpy as np
>>> dims = (4, 4)
>>> components = {
>>>     'rgb': np.random.rand(3, *dims),
>>>     'ir': np.random.rand(1, *dims),
>>> }
>>> components = ub.map_vals(torch.from_numpy, components)
>>> self = ChannelSpec('rgb|ir')
>>> encoded = self.encode(components)
>>> from netharn.data import data_containers
>>> item = {k: data_containers.ItemContainer(v, stack=True)}
>>>     for k, v in encoded.items()
>>> batch = data_containers.container_collate([item, item])
>>> components = self.decode(batch)
```

**component\_indices(axis=2)**

Look up component indices within fused streams

## Example

```
>>> dims = (4, 4)
>>> inputs = ['flowx', 'flowy', 'disparity']
>>> self = ChannelSpec('disparity,flowx|flowy')
>>> component_indices = self.component_indices()
>>> print('component_indices = {}'.format(ub.repr2(component_indices, nl=1)))
component_indices =
    'disparity': ('disparity', (slice(None, None, None), slice(None, None, None), slice(0, 1, None))),
    'flowx': ('flowx|flowy', (slice(None, None, None), slice(None, None, None), slice(0, 1, None))),
    'flowy': ('flowx|flowy', (slice(None, None, None), slice(None, None, None), slice(1, 2, None))),
}
```

`class kwcoco.CocoDataset(data=None, tag=None, bundle_dpath=None, img_root=None, fname=None, autobuild=True)`

Bases: `AbstractCocoDataset, MixinCocoAddRemove, MixinCocoStats, MixinCocoObjects, MixinCocoDraw, MixinCocoAccessors, MixinCocoExtras, MixinCocoIndex, MixinCocoDepricate, NiceRepr`

The main coco dataset class with a json dataset backend.

### Variables

- **dataset** (`Dict`) – raw json data structure. This is the base dictionary that contains {‘annotations’: List, ‘images’: List, ‘categories’: List}
- **index** (`CocoIndex`) – an efficient lookup index into the coco data structure. The index defines its own attributes like `anns`, `cats`, `imgs`, `gid_to_aids`, `file_name_to_img`, etc. See `CocoIndex` for more details on which attributes are available.
- **fpath** (`PathLike` / `None`) – if known, this stores the filepath the dataset was loaded from
- **tag** (`str` / `None`) – A tag indicating the name of the dataset.
- **bundle\_dpath** (`PathLike` / `None`) – If known, this is the root path that all image file names are relative to. This can also be manually overwritten by the user.
- **hashid** (`str` / `None`) – If computed, this will be a hash uniquely identifying the dataset. To ensure this is computed see `kwcoco.coco_dataset.MixinCocoExtras._build_hashid()`.

### References

<http://cocodataset.org/#format> <http://cocodataset.org/#download>

## CommandLine

```
python -m kwCOCO.coco_dataset CocoDataset --show
```


## Example

```
>>> from kwCOCO.coco_dataset import demo_coco_data
>>> import kwCOCO
>>> import ubelt as ub
>>> # Returns a coco json structure
>>> dataset = demo_coco_data()
>>> # Pass the coco json structure to the API
>>> self = kwCOCO.CocoDataset(dataset, tag='demo')
>>> # Now you can access the data using the index and helper methods
>>> #
>>> # Start by looking up an image by its COCO id.
>>> image_id = 1
>>> img = self.index.imgs[image_id]
>>> print(ub.repr2(img, nl=1, sort=1))
{
    'file_name': 'astro.png',
    'id': 1,
    'url': 'https://i.imgur.com/KXhKM72.png',
}
>>> #
>>> # Use the (gid_to_aids) index to lookup annotations in the image
>>> annotation_id = sorted(self.index.gid_to_aids[image_id])[0]
>>> ann = self.index.anns[annotation_id]
>>> print(ub.repr2(ub.dict_diff(ann, {'segmentation'}), nl=1))
{
    'bbox': [10, 10, 360, 490],
    'category_id': 1,
    'id': 1,
    'image_id': 1,
    'keypoints': [247, 101, 2, 202, 100, 2],
}
>>> #
>>> # Use annotation category id to look up that information
>>> category_id = ann['category_id']
>>> cat = self.index.cats[category_id]
>>> print('cat = {}'.format(ub.repr2(cat, nl=1, sort=1)))
cat = {
    'id': 1,
    'name': 'astronaut',
    'supercategory': 'human',
}
>>> #
>>> # Now play with some helper functions, like extended statistics
>>> extended_stats = self.extended_stats()
>>> # xdoctest: +IGNORE_WANT
>>> print('extended_stats = {}'.format(ub.repr2(extended_stats, nl=1, precision=2, u
```

(continues on next page)

(continued from previous page)

```
↳ sort=1)))
extended_stats = {
    'annots_per_img': {'mean': 3.67, 'std': 3.86, 'min': 0.00, 'max': 9.00, 'nMin': 1,
    ↳ 1, 'nMax': 1, 'shape': (3,)},
    'imgs_per_cat': {'mean': 0.88, 'std': 0.60, 'min': 0.00, 'max': 2.00, 'nMin': 2,
    ↳ 2, 'nMax': 1, 'shape': (8,)},
    'cats_per_img': {'mean': 2.33, 'std': 2.05, 'min': 0.00, 'max': 5.00, 'nMin': 1,
    ↳ 1, 'nMax': 1, 'shape': (3,)},
    'annots_per_cat': {'mean': 1.38, 'std': 1.49, 'min': 0.00, 'max': 5.00, 'nMin': 2,
    ↳ 2, 'nMax': 1, 'shape': (8,)},
    'imgs_per_video': {'empty_list': True},
}
>>> # You can "draw" a raster of the annotated image with cv2
>>> canvas = self.draw_image(2)
>>> # Or if you have matplotlib you can "show" the image with mpl objects
>>> # xdoctest: +REQUIRES(--show)
>>> from matplotlib import pyplot as plt
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(1, 2, 1)
>>> self.show_image(gid=2)
>>> ax2 = fig.add_subplot(1, 2, 2)
>>> ax2.imshow(canvas)
>>> ax1.set_title('show with matplotlib')
>>> ax2.set_title('draw with cv2')
>>> plt.show()
```



### property fpath

In the future we will deprecate img\_root for bundle\_dpath

### classmethod from\_data(data, bundle\_dpath=None, img\_root=None)

Constructor from a json dictionary

### classmethod from\_image\_paths(gpaths, bundle\_dpath=None, img\_root=None)

Constructor from a list of images paths.

This is a convinience method.

#### Parameters

gpaths (*List[str]*) – list of image paths

### Example

```
>>> import kwCOCO  
>>> coco_dset = kwCOCO.CocoDataset.from_image_paths(['a.png', 'b.png'])  
>>> assert coco_dset.n_images == 2
```

### classmethod from\_coco\_paths(fpaths, max\_workers=0, verbose=1, mode='thread', union='try')

Constructor from multiple coco file paths.

Loads multiple coco datasets and unions the result

---

**Note:** if the union operation fails, the list of individually loaded files is returned instead.

---

### Parameters

- **fpaths** (*List[str]*) – list of paths to multiple coco files to be loaded and unioned.
- **max\_workers** (*int*) – number of worker threads / processes
- **verbose** (*int*) – verbosity level
- **mode** (*str*) – thread, process, or serial
- **union** (*str | bool*) – If True, unions the result datasets after loading. If False, just returns the result list. If ‘try’, then try to preform the union, but return the result list if it fails. Default=’try’

### copy()

Deep copies this object

### Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> new = self.copy()
>>> assert new.imgs[1] is new.dataset['images'][0]
>>> assert new.imgs[1] == self.dataset['images'][0]
>>> assert new.imgs[1] is not self.dataset['images'][0]
```

### dumps(*indent=None, newlines=False*)

Writes the dataset out to the json format

### Parameters

- **newlines** (*bool*) – if True, each annotation, image, category gets its own line
- **indent** (*int | str | None*) – indentation for the json file. See [json.dump\(\)](#) for details.
- **newlines** (*bool*) – if True, each annotation, image, category gets its own line.

---

**Note:**

**Using newlines=True is similar to:**

`print(ub.repr2(dset.dataset, nl=2, trailsep=False))` However, the above may not output valid json if it contains ndarrays.

---

## Example

```
>>> import kwcoco
>>> import json
>>> self = kwcoco.CocoDataset.demo()
>>> text = self.dumps(newlines=True)
>>> print(text)
>>> self2 = kwcoco.CocoDataset(json.loads(text), tag='demo2')
>>> assert self2.dataset == self.dataset
>>> assert self2.dataset is not self.dataset
```

```
>>> text = self.dumps(newlines=True)
>>> print(text)
>>> self2 = kwcoco.CocoDataset(json.loads(text), tag='demo2')
>>> assert self2.dataset == self.dataset
>>> assert self2.dataset is not self.dataset
```

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.coerce('vidshapes1-msi-multisensor', verbose=3)
>>> self.remove_annotations(self.annots())
>>> text = self.dumps(newlines=0, indent=' ')
>>> print(text)
>>> text = self.dumps(newlines=True, indent=' ')
>>> print(text)
```

`dump(file=None, indent=None, newlines=False, temp_file=True, compress='auto')`

Writes the dataset out to the json format

### Parameters

- `file (PathLike | IO | None)` – Where to write the data. Can either be a path to a file or an open file pointer / stream. If unspecified, it will be written to the current `fpath` property.
- `indent (int | str | None)` – indentation for the json file. See `json.dump()` for details.
- `newlines (bool)` – if True, each annotation, image, category gets its own line.
- `temp_file (bool | str)` – Argument to `safer.open()`. Ignored if `file` is not a PathLike object. Defaults to True.
- `compress (bool | str)` – if True, dumps the kwcoco file as a compressed zipfile. In this case a literal IO file object must be opened in binary write mode. If auto, then it will default to False unless it can introspect the file name and the name ends with .zip

## Example

```
>>> import kwcoco
>>> import ubelt as ub
>>> dpath = ub.Path.appdir('kwcoco/demo/dump').ensuredir()
>>> dset = kwcoco.CocoDataset.demo()
>>> dset.fpath = dpath / 'my_coco_file.json'
>>> # Calling dump writes to the current fpath attribute.
>>> dset.dump()
>>> assert dset.dataset == kwcoco.CocoDataset(dset.fpath).dataset
>>> assert dset.dumps() == dset.fpath.read_text()
>>> #
>>> # Using compress=True can save a lot of space and it
>>> # is transparent when reading files via CocoDataset
>>> dset.dump(compress=True)
>>> assert dset.dataset == kwcoco.CocoDataset(dset.fpath).dataset
>>> assert dset.dumps() != dset.fpath.read_text(errors='replace')
```

## Example

```
>>> import kwcoco
>>> import ubelt as ub
>>> # Compression auto-defaults based on the file name.
>>> dpath = ub.Path.appdir('kwcoco/demo/dump').ensuredir()
>>> dset = kwcoco.CocoDataset.demo()
>>> fpath1 = dset.fpath = dpath / 'my_coco_file.zip'
>>> dset.dump()
>>> fpath2 = dset.fpath = dpath / 'my_coco_file.json'
>>> dset.dump()
>>> assert fpath1.read_bytes()[0:8] != fpath2.read_bytes()[0:8]
```

### `union(*, disjoint_tracks=True, **kwargs)`

Merges multiple `CocoDataset` items into one. Names and associations are retained, but ids may be different.

#### Parameters

- **\*others** – a series of CocoDatasets that we will merge. Note, if called as an instance method, the “self” instance will be the first item in the “others” list. But if called like a classmethod, “others” will be empty by default.
- **disjoint\_tracks (bool)** – if True, we will assume track-ids are disjoint and if two datasets share the same track-id, we will disambiguate them. Otherwise they will be copied over as-is. Defaults to True.
- **\*\*kwargs** – constructor options for the new merged CocoDataset

#### Returns

a new merged coco dataset

#### Return type

`kwcoco.CocoDataset`

## CommandLine

```
xdoctest -m kwCOCO.coco_dataset CocoDataset.union
```

## Example

```
>>> import kwCOCO
>>> # Test union works with different keypoint categories
>>> dset1 = kwCOCO.CocoDataset.demo('shapes1')
>>> dset2 = kwCOCO.CocoDataset.demo('shapes2')
>>> dset1.remove_keypoint_categories(['bot_tip', 'mid_tip', 'right_eye'])
>>> dset2.remove_keypoint_categories(['top_tip', 'left_eye'])
>>> dset_12a = kwCOCO.CocoDataset.union(dset1, dset2)
>>> dset_12b = dset1.union(dset2)
>>> dset_21 = dset2.union(dset1)
>>> def add_hist(h1, h2):
>>>     return {k: h1.get(k, 0) + h2.get(k, 0) for k in set(h1) | set(h2)}
>>> kpfreq1 = dset1.keypoint_annotation_frequency()
>>> kpfreq2 = dset2.keypoint_annotation_frequency()
>>> kpfreq_want = add_hist(kpfreq1, kpfreq2)
>>> kpfreq_got1 = dset_12a.keypoint_annotation_frequency()
>>> kpfreq_got2 = dset_12b.keypoint_annotation_frequency()
>>> assert kpfreq_want == kpfreq_got1
>>> assert kpfreq_want == kpfreq_got2
```

```
>>> # Test disjoint gid datasets
>>> dset1 = kwCOCO.CocoDataset.demo('shapes3')
>>> for new_gid, img in enumerate(dset1.dataset['images'], start=10):
>>>     for aid in dset1.gid_to_aids[img['id']]:
>>>         dset1.anns[aid]['image_id'] = new_gid
>>>     img['id'] = new_gid
>>> dset1.index.clear()
>>> dset1._build_index()
>>> # -----
>>> dset2 = kwCOCO.CocoDataset.demo('shapes2')
>>> for new_gid, img in enumerate(dset2.dataset['images'], start=100):
>>>     for aid in dset2.gid_to_aids[img['id']]:
>>>         dset2.anns[aid]['image_id'] = new_gid
>>>     img['id'] = new_gid
>>> dset1.index.clear()
>>> dset2._build_index()
>>> others = [dset1, dset2]
>>> merged = kwCOCO.CocoDataset.union(*others)
>>> print('merged = {!r}'.format(merged))
>>> print('merged imgs = {}'.format(ub.repr2(merged.imgs, nl=1)))
>>> assert set(merged.imgs) & set([10, 11, 12, 100, 101]) == set(merged.imgs)
```

```
>>> # Test data is not preserved
>>> dset2 = kwCOCO.CocoDataset.demo('shapes2')
>>> dset1 = kwCOCO.CocoDataset.demo('shapes3')
>>> others = (dset1, dset2)
```

(continues on next page)

(continued from previous page)

```
>>> cls = self = kwcoco.CocoDataset
>>> merged = cls.union(*others)
>>> print('merged = {!r}'.format(merged))
>>> print('merged imgs = {}'.format(ub.repr2(merged.imgs, nl=1)))
>>> assert set(merged.imgs) & set([1, 2, 3, 4, 5]) == set(merged.imgs)
```

```
>>> # Test track-ids are mapped correctly
>>> dset1 = kwcoco.CocoDataset.demo('vidshapes1')
>>> dset2 = kwcoco.CocoDataset.demo('vidshapes2')
>>> dset3 = kwcoco.CocoDataset.demo('vidshapes3')
>>> others = (dset1, dset2, dset3)
>>> for dset in others:
>>>     [a.pop('segmentation', None) for a in dset.index.anns.values()]
>>>     [a.pop('keypoints', None) for a in dset.index.anns.values()]
>>> cls = self = kwcoco.CocoDataset
>>> merged = cls.union(*others, disjoint_tracks=1)
>>> print('dset1.anns = {}'.format(ub.repr2(dset1.anns, nl=1)))
>>> print('dset2.anns = {}'.format(ub.repr2(dset2.anns, nl=1)))
>>> print('dset3.anns = {}'.format(ub.repr2(dset3.anns, nl=1)))
>>> print('merged.anns = {}'.format(ub.repr2(merged.anns, nl=1)))
```

## Example

```
>>> import kwcoco
>>> # Test empty union
>>> empty_union = kwcoco.CocoDataset.union()
>>> assert len(empty_union.index.imgs) == 0
```

---

### **Todo:**

- [ ] are supercategories broken?
  - [ ] reuse image ids where possible
  - [ ] reuse annotation / category ids where possible
  - [X] handle case where no inputs are given
  - [x] disambiguate track-ids
  - [x] disambiguate video-ids
- 

### **subset(gids, copy=False, autobuild=True)**

Return a subset of the larger coco dataset by specifying which images to port. All annotations in those images will be taken.

#### Parameters

- **gids** (*List[int]*) – image-ids to copy into a new dataset
- **copy** (*bool*) – if True, makes a deep copy of all nested attributes, otherwise makes a shallow copy. Defaults to True.
- **autobuild** (*bool*) – if True will automatically build the fast lookup index. Defaults to True.

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> gids = [1, 3]
>>> sub_dset = self.subset(gids)
>>> assert len(self.index.gid_to_aids) == 3
>>> assert len(sub_dset.gid_to_aids) == 2
```

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo('vidshapes2')
>>> gids = [1, 2]
>>> sub_dset = self.subset(gids, copy=True)
>>> assert len(sub_dset.index.videos) == 1
>>> assert len(self.index.videos) == 2
```

## Example

```
>>> import kwcoco
>>> self = kwcoco.CocoDataset.demo()
>>> sub1 = self.subset([1])
>>> sub2 = self.subset([2])
>>> sub3 = self.subset([3])
>>> others = [sub1, sub2, sub3]
>>> rejoined = kwcoco.CocoDataset.union(*others)
>>> assert len(sub1.anns) == 9
>>> assert len(sub2.anns) == 2
>>> assert len(sub3.anns) == 0
>>> assert rejoined.basic_stats() == self.basic_stats()
```

**view\_sql**(*force\_rewrite=False*, *memory=False*, *backend='sqlite'*, *sql\_db\_fpath=None*)

Create a cached SQL interface to this dataset suitable for large scale multiprocessing use cases.

### Parameters

- **force\_rewrite** (*bool*) – if True, forces an update to any existing cache file on disk
- **memory** (*bool*) – if True, the database is constructed in memory.
- **backend** (*str*) – sqlite or postgresql
- **sql\_db\_fpath** (*str* | *PathLike* | *None*) – overrides the database uri

---

**Note:** This view cache is experimental and currently depends on the timestamp of the file pointed to by `self.fpath`. In other words dont use this on in-memory datasets.

---

## CommandLine

```
KWCOCO_WITH_POSTGRESQL=1 xdoctest -m /home/joncrall/code/kwcoco/kwcoco/coco_~dataset.py CocoDataset.view_sql
```

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> # xdoctest: +REQUIRES(env:KWCOCO_WITH_POSTGRESQL)
>>> # xdoctest: +REQUIRES(module:psycopg2)
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes32')
>>> postgres_dset = dset.view_sql(backend='postgresql', force_rewrite=True)
>>> sqlite_dset = dset.view_sql(backend='sqlite', force_rewrite=True)
>>> list(dset.anns.keys())
>>> list(postgres_dset.anns.keys())
>>> list(sqlite_dset.anns.keys())
```

```
import timerit
ti = timerit.Timerit(100, bestof=10, verbose=2)
for timer in ti.reset('dct_dset'):
    dset.annots().detections
    for timer in ti.reset('postgresql'):
        postgres_dset.annots().detections
    for timer in ti.reset('sqlite'):
        sqlite_dset.annots().detections
    ub.udict(sql_dset.annots().objs[0]) - {'segmentation'}
    ub.udict(dct_dset.annots().objs[0]) - {'segmentation'}
```

**class** `kwcoco.CocoImage(img, dset=None)`

Bases: `NiceRepr`

An object-oriented representation of a coco image.

It provides helper methods that are specific to a single image.

This operates directly on a single coco image dictionary, but it can optionally be connected to a parent dataset, which allows it to use CocoDataset methods to query about relationships and resolve pointers.

This is different than the Images class in `coco_object1d`, which is just a vectorized interface to multiple objects.

## Example

```
>>> import kwcoco
>>> dset1 = kwcoco.CocoDataset.demo('shapes8')
>>> dset2 = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
```

```
>>> self = CocoImage(dset1.imgs[1], dset1)
>>> print('self = {!r}'.format(self))
>>> print('self.channels = {}'.format(ub.repr2(self.channels, nl=1)))
```

```
>>> self = CocoImage(dset2.imgs[1], dset2)
>>> print('self.channels = {}'.format(ub.repr2(self.channels, nl=1)))
>>> self.primary_asset()
```

**classmethod from\_gid(dset, gid)**

**property bundle\_dpath**

**property video**

Helper to grab the video for this image if it exists

**detach()**

Removes references to the underlying coco dataset, but keeps special information such that it wont be needed.

**property assets**

**annots()**

**Returns**

a 1d annotations object referencing annotations in this image

**Return type**

*Annots*

**stats()**

**keys()**

Proxy getter attribute for underlying *self.img* dictionary

**get(key, default=NoParam)**

Proxy getter attribute for underlying *self.img* dictionary

## Example

```
>>> import pytest
>>> # without extra populated
>>> import kwcoco
>>> self = kwcoco.CocoImage({'foo': 1})
>>> assert self.get('foo') == 1
>>> assert self.get('foo', None) == 1
>>> # with extra populated
>>> self = kwcoco.CocoImage({'extra': {'foo': 1}})
>>> assert self.get('foo') == 1
>>> assert self.get('foo', None) == 1
>>> # without extra empty
>>> self = kwcoco.CocoImage({})
>>> with pytest.raises(KeyError):
>>>     self.get('foo')
>>> assert self.get('foo', None) is None
>>> # with extra empty
>>> self = kwcoco.CocoImage({'extra': {'bar': 1}})
>>> with pytest.raises(KeyError):
>>>     self.get('foo')
>>> assert self.get('foo', None) is None
```

---

```
property channels
property num_channels
property dsize
primary_image_filepath(requires=None)
primary_asset(requires=None)
```

Compute a “main” image asset.

## Notes

Uses a heuristic.

- First, try to find the auxiliary image that has with the smallest distortion to the base image (if known via warp\_aux\_to\_img)
- Second, break ties by using the largest image if w / h is known
- Last, if previous information not available use the first auxiliary image.

## Parameters

**requires** (*List[str] | None*) – list of attribute that must be non-None to consider an object as the primary one.

## Returns

the asset dict or None if it is not found

## Return type

*None | dict*

---

## Todo:

- [ ] Add in primary heuristics
- 

## Example

```
>>> import kwarray
>>> from kwcoco.coco_image import *  # NOQA
>>> rng = kwarray.ensure_rng(0)
>>> def random_auxiliary(name, w=None, h=None):
>>>     return {'file_name': name, 'width': w, 'height': h}
>>> self = CocoImage({
>>>     'auxiliary': [
>>>         random_auxiliary('1'),
>>>         random_auxiliary('2'),
>>>         random_auxiliary('3'),
>>>     ]
>>> })
>>> assert self.primary_asset()['file_name'] == '1'
>>> self = CocoImage({
>>>     'auxiliary': [
```

(continues on next page)

(continued from previous page)

```
>>>         random_auxiliary('1'),
>>>         random_auxiliary('2', 3, 3),
>>>         random_auxiliary('3'),
>>>     ]
>>> }
>>> assert self.primary_asset()['file_name'] == '2'
```

### `iter_image_filepaths`(*with\_bundle=True*)

Could rename to `iter_asset_filepaths`

#### Parameters

`with_bundle (bool)` – If True, prepends the bundle dpath to fully specify the path. Otherwise, just returns the registered string in the file\_name attribute of each asset. Defaults to True.

### `iter_asset_objs()`

Iterate through base + auxiliary dicts that have file paths

#### Yields

`dict` – an image or auxiliary dictionary

### `find_asset_obj`(*channels*)

Find the asset dictionary with the specified channels

### Example

```
>>> import kwcoco
>>> coco_img = kwcoco.CocoImage({'width': 128, 'height': 128})
>>> coco_img.add_auxiliary_item(
    'rgb.png', channels='red|green|blue', width=32, height=32)
>>> assert coco_img.find_asset_obj('red') is not None
>>> assert coco_img.find_asset_obj('green') is not None
>>> assert coco_img.find_asset_obj('blue') is not None
>>> assert coco_img.find_asset_obj('red|blue') is not None
>>> assert coco_img.find_asset_obj('red|green|blue') is not None
>>> assert coco_img.find_asset_obj('red|green|blue') is not None
>>> assert coco_img.find_asset_obj('black') is None
>>> assert coco_img.find_asset_obj('r') is None
```

### Example

```
>>> # Test with concise channel code
>>> import kwcoco
>>> coco_img = kwcoco.CocoImage({'width': 128, 'height': 128})
>>> coco_img.add_auxiliary_item(
    'msi.png', channels='foo.0:128', width=32, height=32)
>>> assert coco_img.find_asset_obj('foo') is None
>>> assert coco_img.find_asset_obj('foo.3') is not None
>>> assert coco_img.find_asset_obj('foo.3:5') is not None
>>> assert coco_img.find_asset_obj('foo.3000') is None
```

**add\_annotation(\*\*ann)**

Adds an annotation to this image.

This is a convinience method, and requires that this CocoImage is still connected to a parent dataset.

**Parameters**

\*\*ann – annotation attributes (e.g. bbox, category\_id)

**Returns**

the new annotation id

**Return type**

int

**SeeAlso:**

`kwcoco.CocoDataset.add_annotation()`

**add\_asset(file\_name=None, channels=None, imdata=None, warp\_aux\_to\_img=None, width=None, height=None, imwrite=False)**

Adds an auxiliary / asset item to the image dictionary.

This operation can be done purely in-memory (the default), or the image data can be written to a file on disk (via the imwrite=True flag).

**Parameters**

- **file\_name** (str | PathLike | None) – The name of the file relative to the bundle directory. If unspecified, imdata must be given.
- **channels** (str | `kwcoco.FusedChannelSpec` | None) – The channel code indicating what each of the bands represents. These channels should be disjoint wrt to the existing data in this image (this is not checked).
- **imdata** (ndarray | None) – The underlying image data this auxiliary item represents. If unspecified, it is assumed file\_name points to a path on disk that will eventually exist. If imdata, file\_name, and the special imwrite=True flag are specified, this function will write the data to disk.
- **warp\_aux\_to\_img** (`kwimage.Affine` | None) – The transformation from this auxiliary space to image space. If unspecified, assumes this item is related to image space by only a scale factor.
- **width** (int | None) – Width of the data in auxiliary space (inferred if unspecified)
- **height** (int | None) – Height of the data in auxiliary space (inferred if unspecified)
- **imwrite** (bool) – If specified, both imdata and file\_name must be specified, and this will write the data to disk. Note: it is recommended that you simply call imwrite yourself before or after calling this function. This lets you better control imwrite parameters.

---

**Todo:**

- [ ] Allow imwrite to specify an executor that is used to return a Future so the imwrite call does not block.
-

## Example

```
>>> from kwcoco.coco_image import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> coco_img = dset.coco_image(1)
>>> imdata = np.random.rand(32, 32, 5)
>>> channels = kwcoco.FusedChannelSpec.coerce('Aux:5')
>>> coco_img.add_asset(imdata=imdata, channels=channels)
```

## Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset()
>>> gid = dset.add_image(name='my_image_name', width=200, height=200)
>>> coco_img = dset.coco_image(gid)
>>> coco_img.add_asset('path/img1_B0.tif', channels='B0', width=200, height=200)
>>> coco_img.add_asset('path/img1_B1.tif', channels='B1', width=200, height=200)
>>> coco_img.add_asset('path/img1_B2.tif', channels='B2', width=200, height=200)
>>> coco_img.add_asset('path/img1_TCI.tif', channels='rgb', width=200, height=200)
```

`imdelay(channels=None, space='image', resolution=None, bundle_dpath=None, interpolation='linear', antialias=True, nodata_method=None, RESOLUTION_KEY=None)`

Perform a delayed load on the data in this image.

The delayed load can load a subset of channels, and perform lazy warping operations. If the underlying data is in a tiled format this can reduce the amount of disk IO needed to read the data if only a small crop or lower resolution view of the data is needed.

---

**Note:** This method is experimental and relies on the delayed load proof-of-concept.

---

### Parameters

- **gid** (*int*) – image id to load
- **channels** (*kwcoco.FusedChannelSpec*) – specific channels to load. if unspecified, all channels are loaded.
- **space** (*str*) – can either be “image” for loading in image space, or “video” for loading in video space.
- **resolution** (*None | str | float*) – If specified, applies an additional scale factor to the result such that the data is loaded at this specified resolution. This requires that the image / video has a registered resolution attribute and that its units agree with this request.

---

### Todo:

- [ ] This function could stand to have a better name. Maybe `imread` with a `delayed=True` flag? Or maybe just `delayed_load`?
-

## Example

```
>>> from kwcoco.coco_image import * # NOQA
>>> import kwcoco
>>> gid = 1
>>> #
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> self = CocoImage(dset.imgs[gid], dset)
>>> delayed = self.imdelay()
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> #
>>> dset = kwcoco.CocoDataset.demo('shapes8')
>>> delayed = dset.coco_image(gid).imdelay()
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
```

```
>>> crop = delayed.crop((slice(0, 3), slice(0, 3)))
>>> crop.finalize()
```

```
>>> # TODO: should only select the "red" channel
>>> dset = kwcoco.CocoDataset.demo('shapes8')
>>> delayed = CocoImage(dset.imgs[gid], dset).imdelay(channels='r')
```

```
>>> import kwcoco
>>> gid = 1
>>> #
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> delayed = dset.coco_image(gid).imdelay(channels='B1|B2', space='image')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> delayed = dset.coco_image(gid).imdelay(channels='B1|B2|B11', space='image')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
>>> delayed = dset.coco_image(gid).imdelay(channels='B8|B1', space='video')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed))
```

```
>>> delayed = dset.coco_image(gid).imdelay(channels='B8|foo|bar|B1', space=
    <--> 'video')
>>> print('delayed = {!r}'.format(delayed))
>>> print('delayed.finalize() = {!r}'.format(delayed.finalize()))
```

### Example

```
>>> import kwCOCO
>>> dset = kwCOCO.CocoDataset.demo()
>>> coco_img = dset.coco_image(1)
>>> # Test case where nothing is registered in the dataset
>>> delayed = coco_img.imdelay()
>>> final = delayed.finalize()
>>> assert final.shape == (512, 512, 3)
```

```
>>> delayed = coco_img.imdelay()
>>> final = delayed.finalize()
>>> print('final.shape = {}'.format(ub.repr2(final.shape, nl=1)))
>>> assert final.shape == (512, 512, 3)
```

### Example

```
>>> # Test that delay works when imdata is stored in the image
>>> # dictionary itself.
>>> from kwCOCO.coco_image import * # NOQA
>>> import kwCOCO
>>> dset = kwCOCO.CocoDataset.demo('vidshapes8-multispectral')
>>> coco_img = dset.coco_image(1)
>>> imdata = np.random.rand(6, 6, 5)
>>> imdata[:] = np.arange(5)[None, None, :]
>>> channels = kwCOCO.FusedChannelSpec.coerce('Aux:5')
>>> coco_img.add_auxiliary_item(imdata=imdata, channels=channels)
>>> delayed = coco_img.imdelay(channels='B1|Aux:2:4')
>>> final = delayed.finalize()
```

### Example

```
>>> # Test delay when loading in asset space
>>> from kwCOCO.coco_image import * # NOQA
>>> import kwCOCO
>>> dset = kwCOCO.CocoDataset.demo('vidshapes8-msi-multisensor')
>>> coco_img = dset.coco_image(1)
>>> stream1 = coco_img.channels.streams()[0]
>>> stream2 = coco_img.channels.streams()[1]
>>> asset_delayed = coco_img.imdelay(stream1, space='asset')
>>> img_delayed = coco_img.imdelay(stream1, space='image')
>>> vid_delayed = coco_img.imdelay(stream1, space='video')
>>> #
>>> aux_imdata = asset_delayed.as_xarray().finalize()
>>> img_imdata = img_delayed.as_xarray().finalize()
>>> assert aux_imdata.shape != img_imdata.shape
>>> # Cannot load multiple asset items at the same time in
>>> # asset space
>>> import pytest
>>> fused_channels = stream1 | stream2
```

(continues on next page)

(continued from previous page)

```
>>> from delayed_image.delayed_nodes import CoordinateCompatibilityError
>>> with pytest.raises(CoordinateCompatibilityError):
>>>     aux_delayed2 = coco_img.imdelay(fused_channels, space='asset')
```

## Example

```
>>> # Test loading at a specific resolution.
>>> from kwcoco.coco_image import * # NOQA
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-msi-multisensor')
>>> coco_img = dset.coco_image(1)
>>> coco_img.img['resolution'] = '1 meter'
>>> img_delayed1 = coco_img.imdelay(space='image')
>>> vid_delayed1 = coco_img.imdelay(space='video')
>>> # test with unitless request
>>> img_delayed2 = coco_img.imdelay(space='image', resolution=3.1)
>>> vid_delayed2 = coco_img.imdelay(space='video', resolution='3.1 meter')
>>> np.ceil(img_delayed1.shape[0] / 3.1) == img_delayed2.shape[0]
>>> np.ceil(vid_delayed1.shape[0] / 3.1) == vid_delayed2.shape[0]
>>> # test with unitless data
>>> coco_img.img['resolution'] = 1
>>> img_delayed2 = coco_img.imdelay(space='image', resolution=3.1)
>>> vid_delayed2 = coco_img.imdelay(space='video', resolution='3.1 meter')
>>> np.ceil(img_delayed1.shape[0] / 3.1) == img_delayed2.shape[0]
>>> np.ceil(vid_delayed1.shape[0] / 3.1) == vid_delayed2.shape[0]
```

### `valid_region(space='image')`

If this image has a valid polygon, return it in image, or video space

### `property warp_vid_from_img`

Affine transformation that warps image space -> video space.

### `property warp_img_from_vid`

Affine transformation that warps video space -> image space.

### `resolution(space='image', channel=None, RESOLUTION_KEY=None)`

Returns the resolution of this CocoImage in the requested space if known. Errors if this information is not registered.

#### Parameters

- **space** (str) – the space to the resolution of. Can be either “image”, “video”, or “asset”.
- **channel** (str | kwcoco.FusedChannelSpec | None) – a channel that identifies a single asset, only relevant if asking for asset space

#### Returns

has items mag (with the magnitude of the resolution) and unit, which is a convinience and only loosely enforced.

#### Return type

Dict

## Example

```
>>> import kwcoco
>>> dset = kwcoco.CocoDataset.demo('vidshapes8-multispectral')
>>> self = dset.coco_image(1)
>>> self.img['resolution'] = 1
>>> self.resolution()
>>> self.img['resolution'] = '1 meter'
>>> self.resolution(space='video')
{'mag': (1.0, 1.0), 'unit': 'meter'}
>>> self.resolution(space='asset', channel='B11')
>>> self.resolution(space='asset', channel='B1')
```

```
add_auxiliary_item(**kwargs)

delay(**kwargs)

class kwcoco.CocoSqlDatabase(uri=None, tag=None, img_root=None)
Bases: AbstractCocoDataset, MixinCocoAccessors, MixinCocoObjects, MixinCocoStats,
MixinCocoDraw, NiceRepr
```

Provides an API nearly identical to `kwcoco.CocoDatabase`, but uses an SQL backend data store. This makes it robust to copy-on-write memory issues that arise when forking, as discussed in<sup>1</sup>.

---

**Note:** By default constructing an instance of the `CocoSqlDatabase` does not create a connection to the database. Use the `connect()` method to open a connection.

---

## References

### Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> sql_dset, dct_dset = demo()
>>> dset1, dset2 = sql_dset, dct_dset
>>> tag1, tag2 = 'dset1', 'dset2'
>>> assert_dsets_allclose(sql_dset, dct_dset)
```

```
MEMORY_URI = 'sqlite:///memory:'
```

```
classmethod coerce(data, backend=None)
```

Create an SQL CocoDataset from the input pointer.

---

<sup>1</sup> <https://github.com/pytorch/pytorch/issues/13246>

## Example

```

import kwcoco dset = kwcoco.CocoDataset.demo('shapes8') data = dset.fpath self = CocoSql-
Database.coerce(data)

from kwcoco.coco_sql_dataset import CocoSqlDatabase import kwcoco dset = kw-
coco.CocoDataset.coerce('spacenet7.kwcoco.json')

self = CocoSqlDatabase.coerce(dset)

from kwcoco.coco_sql_dataset import CocoSqlDatabase sql_dset = CocoSql-
Database.coerce('spacenet7.kwcoco.json')

# from kwcoco.coco_sql_dataset import CocoSqlDatabase import kwcoco sql_dset = kw-
coco.CocoDataset.coerce('_spacenet7.kwcoco.view.v006.sqlite')

disconnect()
Drop references to any SQL or cache objects

connect(readonly=False, verbose=0)
Connects this instance to the underlying database.

```

## References

# details on read only mode, some of these didnt seem to work <https://github.com/sqlalchemy/sqlalchemy/blob/master/lib/sqlalchemy/dialects/sqlite/pysqlite.py#L71> <https://github.com/pudo/dataset/issues/136>  
<https://writeonly.wordpress.com/2009/07/16/simple-read-only-sqlalchemy-sessions/>

## CommandLine

```
KWCOCO_WITH_POSTGRESQL=1 xdoctest -m /home/joncrall/code/kwcoco/kwcoco/coco_sql_-
dataset.py CocoSqlDatabase.connect
```

## Example

```

>>> # xdoctest: +REQUIRES(env:KWCOCO_WITH_POSTGRESQL)
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> # xdoctest: +REQUIRES(module:psycopg2)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> dset = CocoSqlDatabase('postgresql+psycopg2://kwcoco:kwcoco_-
>>> pw@localhost:5432/mydb')
>>> self = dset
>>> dset.connect(verbose=1)

```

**property fpath**

**delete(verbose=0)**

**populate\_from(dset, verbose=1)**

Copy the information in a `CocoDataset` into this SQL database.

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwCOCO.coco_sql_dataset import _benchmark_dset_readtime # NOQA
>>> import kwCOCO
>>> from kwCOCO.coco_sql_dataset import *
>>> dset2 = dset = kwCOCO.CocoDataset.demo()
>>> dset2.clear_annotations()
>>> dset1 = self = CocoSqlDatabase('sqlite:///memory:')
>>> self.connect()
>>> self.populate_from(dset)
>>> dset1_images = list(dset1.dataset['images'])
>>> print('dset1_images = {}'.format(ub.repr(dset1_images, nl=1)))
>>> print(dset2.dumps(newlines=True))
>>> assert_dsets_allclose(dset1, dset2, tag1='sql', tag2='dct')
>>> ti_sql = _benchmark_dset_readtime(dset1, 'sql')
>>> ti_dct = _benchmark_dset_readtime(dset2, 'dct')
>>> print('ti_sql.rankings = {}'.format(ub.repr2(ti_sql.rankings, nl=2,
... -precision=6, align=':')))
>>> print('ti_dct.rankings = {}'.format(ub.repr2(ti_dct.rankings, nl=2,
... -precision=6, align=':')))
```

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwCOCO.coco_sql_dataset import _benchmark_dset_readtime # NOQA
>>> import kwCOCO
>>> from kwCOCO.coco_sql_dataset import *
>>> dset2 = dset = kwCOCO.CocoDataset.demo()
>>> dset1 = self = CocoSqlDatabase('sqlite:///memory:')
>>> self.connect()
>>> self.populate_from(dset)
>>> assert_dsets_allclose(dset1, dset2, tag1='sql', tag2='dct')
>>> ti_sql = _benchmark_dset_readtime(dset1, 'sql')
>>> ti_dct = _benchmark_dset_readtime(dset2, 'dct')
>>> print('ti_sql.rankings = {}'.format(ub.repr2(ti_sql.rankings, nl=2,
... -precision=6, align=':')))
>>> print('ti_dct.rankings = {}'.format(ub.repr2(ti_dct.rankings, nl=2,
... -precision=6, align=':')))
```

## CommandLine

```
KWCOCO_WITH_POSTGRESQL=1 xdoctest -m /home/joncrall/code/kwCOCO/kwCOCO/coco_sql_
...dataset.py CocoSqlDatabase.populate_from:1
```

**Example**

```
>>> # xdoctest: +REQUIRES(env:KWCOCO_WITH_POSTGRESQL)
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> # xdoctest: +REQUIRES(module:psycopg2)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> import kwcoco
>>> dset = dset2 = kwcoco.CocoDataset.demo()
>>> self = dset1 = CocoSqlDatabase('postgresql+psycopg2://kwcoco:kwcoco_'
->>> pw@localhost:5432/test_populate')
>>> self.delete(verbose=1)
>>> self.connect(verbose=1)
>>> #self.populate_from(dset)
```

**property dataset****property anns****property cats****property imgs****property name\_to\_cat****raw\_table(table\_name)**

Loads an entire SQL table as a pandas DataFrame

**Parameters**

**table\_name** (*str*) – name of the table

**Returns**

pandas.DataFrame

**Example**

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> self, dset = demo()
>>> table_df = self.raw_table('annotations')
>>> print(table_df)
```

**tabular\_targets()**

Convinience method to create an in-memory summary of basic annotation properties with minimal SQL overhead.

## Example

```
>>> # xdoctest: +REQUIRES(module:sqlalchemy)
>>> from kwcoco.coco_sql_dataset import * # NOQA
>>> self, dset = demo()
>>> targets = self.tabular_targets()
>>> print(targets.pandas())
```

**property bundle\_dpath**

**property data\_fpath**

data\_fpath is an alias of fpath

**class kwcoco.FusedChannelSpec(parsed, \_is\_normalized=False)**

Bases: BaseChannelSpec

A specific type of channel spec with only one early fused stream.

The channels in this stream are non-commutative

Behaves like a list of atomic-channel codes (which may represent more than 1 channel), normalized codes always represent exactly 1 channel.

---

**Note:** This class name and API is in flux and subject to change.

---

---

**Todo:** A special code indicating a name and some number of bands that that names contains, this would primarily be used for large numbers of channels produced by a network. Like:

resnet\_d35d060\_L5:512

or

resnet\_d35d060\_L5[:512]

might refer to a very specific (hashed) set of resnet parameters with 512 bands

maybe we can do something slicly like:

resnet\_d35d060\_L5[A:B] resnet\_d35d060\_L5:A:B

Do we want to “just store the code” and allow for parsing later?

Or do we want to ensure the serialization is parsed before we construct the data structure?

---

## Example

```
>>> from delayed_image.channel_spec import * # NOQA
>>> import pickle
>>> self = FusedChannelSpec.coerce(3)
>>> recon = pickle.loads(pickle.dumps(self))
>>> self = ChannelSpec.coerce('a|b,c|d')
>>> recon = pickle.loads(pickle.dumps(self))
```

**classmethod concat(items)**

```
property spec
unique()
classmethod parse(spec)
classmethod coerce(data)
```

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> FusedChannelSpec.coerce(['a', 'b', 'c'])
>>> FusedChannelSpec.coerce('a|b|c')
>>> FusedChannelSpec.coerce(3)
>>> FusedChannelSpec.coerce(FusedChannelSpec(['a']))
>>> assert FusedChannelSpec.coerce('') .numel() == 0
```

**concise()**

Shorted the channel spec by de-normaliz slice syntax

**Returns**

concise spec

**Return type**

*FusedChannelSpec*

**Example**

```
>>> from delayed_image.channel_spec import * # NOQA
>>> self = FusedChannelSpec.coerce(
>>>     'b|a|a.0|a.1|a.2|a.5|c|a.8|a.9|b.0:3|c.0')
>>> short = self.concise()
>>> long = short.normalize()
>>> numels = [c.numel() for c in [self, short, long]]
>>> print('self.spec = {!r}'.format(self.spec))
>>> print('short.spec = {!r}'.format(short.spec))
>>> print('long.spec = {!r}'.format(long.spec))
>>> print('numels = {!r}'.format(numels))
self.spec = 'b|a|a.0|a.1|a.2|a.5|c|a.8|a.9|b.0:3|c.0'
short.spec = 'b|a|a:3|a.5|c|a.8:10|b:3|c.0'
long.spec = 'b|a|a.0|a.1|a.2|a.5|c|a.8|a.9|b.0|b.1|b.2|c.0'
numels = [13, 13, 13]
>>> assert long.concise().spec == short.spec
```

**normalize()**

Replace aliases with explicit single-band-per-code specs

**Returns**

normalize spec

**Return type**

*FusedChannelSpec*

## Example

```
>>> from delayed_image.channel_spec import * # NOQA
>>> self = FusedChannelSpec.coerce('b1|b2|b3|rgb')
>>> normed = self.normalize()
>>> print('self = {}'.format(self))
>>> print('normed = {}'.format(normed))
self = <FusedChannelSpec(b1|b2|b3|rgb)>
normed = <FusedChannelSpec(b1|b2|b3|r|g|b)>
>>> self = FusedChannelSpec.coerce('B:1:11')
>>> normed = self.normalize()
>>> print('self = {}'.format(self))
>>> print('normed = {}'.format(normed))
self = <FusedChannelSpec(B:1:11)>
normed = <FusedChannelSpec(B.1|B.2|B.3|B.4|B.5|B.6|B.7|B.8|B.9|B.10)>
>>> self = FusedChannelSpec.coerce('B.1:11')
>>> normed = self.normalize()
>>> print('self = {}'.format(self))
>>> print('normed = {}'.format(normed))
self = <FusedChannelSpec(B.1:11)>
normed = <FusedChannelSpec(B.1|B.2|B.3|B.4|B.5|B.6|B.7|B.8|B.9|B.10)>
```

### `numel()`

Total number of channels in this spec

### `sizes()`

Returns a list indicating the size of each atomic code

#### Returns

List[int]

## Example

```
>>> from delayed_image.channel_spec import * # NOQA
>>> self = FusedChannelSpec.coerce('b1|Z:3|b2|b3|rgb')
>>> self.sizes()
[1, 3, 1, 1, 3]
>>> assert(FusedChannelSpec.parse('a.0').numel() == 1
>>> assert(FusedChannelSpec.parse('a:0').numel() == 0
>>> assert(FusedChannelSpec.parse('a:1').numel() == 1
```

### `code_list()`

Return the expanded code list

### `as_list()`

### `as_oerset()`

### `as_set()`

### `to_set()`

### `to_oerset()`

**to\_list()****as\_path()**

Returns a string suitable for use in a path.

Note, this may no longer be a valid channel spec

**difference(*other*)**

Set difference

### Example

```
>>> FCS = FusedChannelSpec.coerce
>>> self = FCS('rgb|disparity|flowx|flowy')
>>> other = FCS('r|b')
>>> self.difference(other)
>>> other = FCS('flowx')
>>> self.difference(other)
>>> FCS = FusedChannelSpec.coerce
>>> assert len((FCS('a') - {'a'}).parsed) == 0
>>> assert len((FCS('a.0:3') - {'a.0'}).parsed) == 2
```

**intersection(*other*)**

### Example

```
>>> FCS = FusedChannelSpec.coerce
>>> self = FCS('rgb|disparity|flowx|flowy')
>>> other = FCS('r|b|XX')
>>> self.intersection(other)
```

**union(*other*)**

### Example

```
>>> from delayed_image.channel_spec import * # NOQA
>>> FCS = FusedChannelSpec.coerce
>>> self = FCS('rgb|disparity|flowx|flowy')
>>> other = FCS('r|b|XX')
>>> self.union(other)
```

**issubset(*other*)****issuperset(*other*)****component\_indices(*axis*=2)**

Look up component indices within this stream

## Example

```
>>> FCS = FusedChannelSpec.coerce
>>> self = FCS('disparity|rgb|flowx|flowy')
>>> component_indices = self.component_indices()
>>> print('component_indices = {}'.format(ub.repr2(component_indices, nl=1)))
component_indices =
    'disparity': (slice(...), slice(...), slice(0, 1, None)),
    'flowx': (slice(...), slice(...), slice(4, 5, None)),
    'flowy': (slice(...), slice(...), slice(5, 6, None)),
    'rgb': (slice(...), slice(...), slice(1, 4, None)),
}
```

### streams()

Idempotence with `ChannelSpec.streams()`

### fuse()

Idempotence with `ChannelSpec.streams()`

## class kwcoc.SensorChanSpec(spec: str)

Bases: `NiceRepr`

The public facing API for the sensor / channel specification

## Example

```
>>> # xdoctest: +REQUIRES(module:lark)
>>> from delayed_image.sensorchan_spec import SensorChanSpec
>>> self = SensorChanSpec('(L8,S2):BGR,WV:BGR,S2:nir,L8:land.0:4')
>>> s1 = self.normalize()
>>> s2 = self.concise()
>>> streams = self.streams()
>>> print(s1)
>>> print(s2)
>>> print('streams = {}'.format(ub.repr2(streams, sv=1, nl=1)))
L8:BGR,S2:BGR,WV:BGR,S2:nir,L8:land.0|land.1|land.2|land.3
(L8,S2,WV):BGR,L8:land:4,S2:nir
streams = [
    L8:BGR,
    S2:BGR,
    WV:BGR,
    S2:nir,
    L8:land.0|land.1|land.2|land.3,
]
```

## Example

```
>>> # Check with generic sensors
>>> # xdoctest: +REQUIRES(module:lark)
>>> from delayed_image.sensorchan_spec import SensorChanSpec
>>> import delayed_image
>>> self = SensorChanSpec('(*):BGR,:BGR,:nir,:land.0:4')
>>> self.concise().normalize()
>>> s1 = self.normalize()
>>> s2 = self.concise()
>>> print(s1)
>>> print(s2)
*:BGR,:BGR,:nir,:land.0|land.1|land.2|land.3
(*):BGR,:nir,land:4
>>> import delayed_image
>>> c = delayed_image.ChannelSpec.coerce('BGR,BGR,nir,land.0:8')
>>> c1 = c.normalize()
>>> c2 = c.concise()
>>> print(c1)
>>> print(c2)
```

## Example

```
>>> # Check empty channels
>>> # xdoctest: +REQUIRES(module:lark)
>>> from delayed_image.sensorchan_spec import SensorChanSpec
>>> import delayed_image
>>> print(SensorChanSpec('*:').normalize())
*:
>>> print(SensorChanSpec('sen:').normalize())
sen:
>>> print(SensorChanSpec('sen:').normalize().concise())
sen:
>>> print(SensorChanSpec('sen:').concise().normalize().concise())
sen:
```

### `classmethod coerce(data)`

Attempt to interpret the data as a channel specification

#### Returns

SensorChanSpec

## Example

```
>>> # xdoctest: +REQUIRES(module:lark)
>>> from delayed_image.sensorchan_spec import * # NOQA
>>> from delayed_image.sensorchan_spec import SensorChanSpec
>>> data = SensorChanSpec.coerce(3)
>>> assert SensorChanSpec.coerce(data).normalize().spec == '*:u0|u1|u2'
>>> data = SensorChanSpec.coerce(3)
>>> assert data.spec == 'u0|u1|u2'
>>> assert SensorChanSpec.coerce(data).spec == 'u0|u1|u2'
>>> data = SensorChanSpec.coerce('u:3')
>>> assert data.normalize().spec == '*:u.0|u.1|u.2'
```

`normalize()`

`concise()`

## Example

```
>>> # xdoctest: +REQUIRES(module:lark)
>>> from delayed_image import SensorChanSpec
>>> a = SensorChanSpec.coerce('Cam1:(red,blue)')
>>> b = SensorChanSpec.coerce('Cam2:(blue,green)')
>>> c = (a + b).concise()
>>> print(c)
(Cam1,Cam2):blue,Cam1:red,Cam2:green
>>> # Note the importance of parenthesis in the previous example
>>> # otherwise channels will be assigned to `*` the generic sensor.
>>> a = SensorChanSpec.coerce('Cam1:red,blue')
>>> b = SensorChanSpec.coerce('Cam2:blue,green')
>>> c = (a + b).concise()
>>> print(c)
(*,Cam2):blue,*:green,Cam1:red
```

`streams()`

### Returns

List of sensor-names and fused channel specs

### Return type

List[FusedSensorChanSpec]

`late_fuse(*others)`

## Example

```
>>> # xdoctest: +REQUIRES(module:lark)
>>> import delayed_image
>>> from delayed_image import sensorchan_spec
>>> import delayed_image
>>> delayed_image.SensorChanSpec = sensorchan_spec.SensorChanSpec # hack for 3.
>~6
>>> a = delayed_image.SensorChanSpec.coerce('A|B|C,edf')
>>> b = delayed_image.SensorChanSpec.coerce('A12')
>>> c = delayed_image.SensorChanSpec.coerce('')
>>> d = delayed_image.SensorChanSpec.coerce('rgb')
>>> print(a.late_fuse(b).spec)
>>> print((a + b).spec)
>>> print((b + a).spec)
>>> print((a + b + c).spec)
>>> print(sum([a, b, c, d]).spec)
A|B|C,edf,A12
A|B|C,edf,A12
A12,A|B|C,edf
A|B|C,edf,A12
A|B|C,edf,A12,rgb
>>> import delayed_image
>>> a = delayed_image.SensorChanSpec.coerce('A|B|C,edf').normalize()
>>> b = delayed_image.SensorChanSpec.coerce('A12').normalize()
>>> c = delayed_image.SensorChanSpec.coerce('').normalize()
>>> d = delayed_image.SensorChanSpec.coerce('rgb').normalize()
>>> print(a.late_fuse(b).spec)
>>> print((a + b).spec)
>>> print((b + a).spec)
>>> print((a + b + c).spec)
>>> print(sum([a, b, c, d]).spec)
*:A|B|C,:edf,:A12
*:A|B|C,:edf,:A12
*:A12,:A|B|C,:edf
*:A|B|C,:edf,:A12,:
*:A|B|C,:edf,:A12,*,*:rgb
>>> print((a.late_fuse(b)).concise())
>>> print(((a + b)).concise())
>>> print(((b + a)).concise())
>>> print(((a + b + c)).concise())
>>> print((sum([a, b, c, d])).concise())
*: (A|B|C,edf,A12)
*: (A|B|C,edf,A12)
*: (A12,A|B|C,edf)
*: (A|B|C,edf,A12,)
*: (A|B|C,edf,A12,,r|g|b)
```

**Example**

```
>>> # Test multi-arg case
>>> import delayed_image
>>> a = delayed_image.SensorChanSpec.coerce('A|B|C,edf')
>>> b = delayed_image.SensorChanSpec.coerce('A12')
>>> c = delayed_image.SensorChanSpec.coerce('')
>>> d = delayed_image.SensorChanSpec.coerce('rgb')
>>> others = [b, c, d]
>>> print(a.late_fuse(*others).spec)
>>> print(delayed_image.SensorChanSpec.late_fuse(a, b, c, d).spec)
A|B|C,edf,A12,rgb
A|B|C,edf,A12,rgb
```

**matching\_sensor(*sensor*)**

Get the components corresponding to a specific sensor

**Parameters**

**sensor** (*str*) – the name of the sensor to match

**Example**

```
>>> # xdoctest: +REQUIRES(module:lark)
>>> import delayed_image
>>> self = delayed_image.SensorChanSpec.coerce('(S1,S2):(a|b|c),S2:c|d|e')
>>> sensor = 'S2'
>>> new = self.matching_sensor(sensor)
>>> print(f'new={new}')
new=S2:a|b|c,S2:c|d|e
>>> print(self.matching_sensor('S1'))
S1:a|b|c
>>> print(self.matching_sensor('S3'))
S3:
```

**property chans**

Returns the channel-only spec, ONLY if all of the sensors are the same

**Example**

```
>>> # xdoctest: +REQUIRES(module:lark)
>>> import delayed_image
>>> self = delayed_image.SensorChanSpec.coerce('(S1,S2):(a|b|c),S2:c|d|e')
>>> import pytest
>>> with pytest.raises(Exception):
>>>     self.chans
>>> print(self.matching_sensor('S1').chans.spec)
>>> print(self.matching_sensor('S2').chans.spec)
a|b|c
a|b|c,c|d|e
```

## BIBLIOGRAPHY

- [PowersMetrics] <https://csem.flinders.edu.au/research/techreps/SIE07001.pdf>
- [MatlabBM] <https://www.mathworks.com/matlabcentral/fileexchange/5648-bm-cm?requestedDomain=www.mathworks.com>
- [MulticlassMCC] Jurman, Riccadonna, Furlanello, (2012). A Comparison of MCC and CEN Error Measures in MultiClass Prediction
- [CocoFormat] <http://cocodataset.org/#format-data>
- [PyCocoToolsMask] <https://github.com/nightrome/cocostuffapi/blob/master/PythonAPI/pycocotools/mask.py>
- [CocoTutorial] <https://www.immersivelimit.com/tutorials/create-coco-annotations-from-scratch/#coco-dataset-format>



## PYTHON MODULE INDEX

### k

kwcoco, 292  
kwcoco.\_\_init\_\_, 1  
kwcoco.abstract\_coco\_dataset, 200  
kwcoco.category\_tree, 200  
kwcoco.channel\_spec, 205  
kwcoco.cli, 20  
kwcoco.cli.coco\_conform, 9  
kwcoco.cli.coco\_eval, 10  
kwcoco.cli.coco\_grab, 12  
kwcoco.cli.coco\_modify\_categories, 12  
kwcoco.cli.coco\_reroot, 13  
kwcoco.cli.coco\_show, 14  
kwcoco.cli.coco\_split, 14  
kwcoco.cli.coco\_stats, 15  
kwcoco.cli.coco\_subset, 16  
kwcoco.cli.coco\_toydata, 18  
kwcoco.cli.coco\_union, 18  
kwcoco.cli.coco\_validate, 19  
kwcoco.coco\_dataset, 205  
kwcoco.coco\_evaluator, 249  
kwcoco.coco\_image, 254  
kwcoco.coco\_objects1d, 263  
kwcoco.coco\_schema, 273  
kwcoco.coco\_sql\_dataset, 274  
kwcoco.compat\_dataset, 285  
kwcoco.data, 23  
kwcoco.data.grab\_camvid, 20  
kwcoco.data.grab\_datasets, 21  
kwcoco.data.grab\_domainnet, 22  
kwcoco.data.grab\_spacenet, 22  
kwcoco.data.grab\_voc, 23  
kwcoco.demo, 66  
kwcoco.demo.boids, 23  
kwcoco.demo.perterb, 28  
kwcoco.demo.toydata, 29  
kwcoco.demo.toydata\_image, 42  
kwcoco.demo.toydata\_video, 48  
kwcoco.demo.toypatterns, 63  
kwcoco.examples, 69  
kwcoco.examples.draw\_gt\_and\_predicted\_boxes,  
    66

    kwcoco.examples.faq, 67  
    kwcoco.examples.getting\_started\_existing\_dataset,  
        67  
    kwcoco.examples.loading\_multispectral\_data,  
        68  
    kwcoco.examples.modification\_example, 68  
    kwcoco.examples.simple\_kwcoco\_torch\_dataset,  
        68  
    kwcoco.examples.vectorized\_interface, 69  
    kwcoco.exceptions, 289  
    kwcoco.kpf, 289  
    kwcoco.kw18, 289  
    kwcoco.metrics, 111  
    kwcoco.metrics.assignment, 69  
    kwcoco.metrics.clf\_report, 70  
    kwcoco.metrics.confusion\_measures, 72  
    kwcoco.metrics.confusion\_vectors, 83  
    kwcoco.metrics.detect\_metrics, 91  
    kwcoco.metrics.drawing, 101  
    kwcoco.metrics.functional, 108  
    kwcoco.metrics.sklearn\_alts, 108  
    kwcoco.metrics.voc\_metrics, 109  
    kwcoco.sensorchan\_spec, 292  
    kwcoco.util, 182  
    kwcoco.util.delayed\_ops, 137  
    kwcoco.util.dict\_like, 164  
    kwcoco.util.jsonschema\_elements, 166  
    kwcoco.util.lazy\_frame\_backends, 172  
    kwcoco.util.util\_archive, 172  
    kwcoco.util.util\_futures, 173  
    kwcoco.util.util\_json, 177  
    kwcoco.util.util\_monkey, 179  
    kwcoco.util.util\_reroot, 180  
    kwcoco.util.util\_sklearn, 182  
    kwcoco.util.util\_truncate, 182



# INDEX

## A

`AbstractCocoDataset` (*class in kwcoco*), 298  
`AbstractCocoDataset` (*class in kwcoco.abstract\_coco\_dataset*), 200  
`add()` (*kwcoco.util.Archive method*), 184  
`add()` (*kwcoco.util.util\_archive.Archive method*), 173  
`add_annotation()` (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 228  
`add_annotation()` (*kwcoco.coco\_image.CocoImage method*), 257  
`add_annotation()` (*kwcoco.CocoImage method*), 324  
`add_annotations()` (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 232  
`add_asset()` (*kwcoco.coco\_image.CocoImage method*), 257  
`add_asset()` (*kwcoco.CocoImage method*), 325  
`add_auxiliary_item()` (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 228  
`add_auxiliary_item()` (*kwcoco.coco\_image.CocoImage method*), 262  
`add_auxiliary_item()` (*kwcoco.CocoImage method*), 330  
`add_category()` (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 230  
`add_image()` (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 227  
`add_images()` (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 232  
`add_metaclass()` (*kwcoco.util.util\_monkey.Reloadable class method*), 180  
`add_predictions()` (*kwcoco.metrics.detect\_metrics.DetectionMetrics method*), 92  
`add_predictions()` (*kwcoco.metrics.DetectionMetrics method*), 119  
`add_predictions()` (*kwcoco.metrics.voc\_metrics.VOC\_Metrics method*), 109  
`add_truth()` (*kwcoco.metrics.detect\_metrics.DetectionMetrics method*), 92  
`add_truth()` (*kwcoco.metrics.DetectionMetrics method*), 119  
`add_truth()` (*kwcoco.metrics.voc\_metrics.VOC\_Metrics method*), 109  
`add_video()` (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 226  
`AddError`, 289  
`aids` (*kwcoco.coco\_objects1d.Annots property*), 270  
`aids` (*kwcoco.coco\_objects1d.Images property*), 269  
`alias` (*kwcoco.coco\_sql\_dataset.Category attribute*), 275  
`alias` (*kwcoco.coco\_sql\_dataset.KeypointCategory attribute*), 275  
`allclose()` (*kwcoco.util.IndexableWalker method*), 190  
`ALLOF()` (*in module kwcoco.util*), 182  
`ALLOF()` (*in module kwcoco.util.jsonschema\_elements*), 170  
`ALLOF()` (*kwcoco.util.jsonschema\_elements.QuantifierElements method*), 168  
`ALLOF()` (*kwcoco.util.QuantifierElements method*), 194  
`Annotation` (*class in kwcoco.coco\_sql\_dataset*), 276  
`AnnotGroups` (*class in kwcoco.coco\_objects1d*), 271  
`Annots` (*class in kwcoco.coco\_objects1d*), 269  
`annots` (*kwcoco.coco\_objects1d.Images property*), 269  
`annots()` (*kwcoco.coco\_dataset.MixinCocoObjects method*), 217  
`annots()` (*kwcoco.coco\_image.CocoImage method*), 254  
`annots()` (*kwcoco.CocoImage method*), 322  
`anns` (*kwcoco.coco\_dataset.MixinCocoIndex property*), 238  
`anns` (*kwcoco.coco\_sql\_dataset.CocoSqlDatabase property*), 283  
`anns` (*kwcoco.CocoSqlDatabase property*), 333  
`annToMask()` (*kwcoco.compat\_dataset.COCO method*), 288  
`annToRLE()` (*kwcoco.compat\_dataset.COCO method*), 288  
`ANY` (*kwcoco.util.jsonschema\_elements.QuantifierElements property*), 168  
`ANY` (*kwcoco.util.QuantifierElements property*), 194  
`ANYOF()` (*in module kwcoco.util*), 182

ANYOF() (*in module kwcoco.util.jsonschema\_elements*), 170  
 ANYOF() (*kwcoco.util.jsonschema\_elements.QuantifierElements method*), 168  
 ANYOF() (*kwcoco.util.QuantifierElements method*), 194  
**Archive** (*class in kwcoco.util*), 183  
**Archive** (*class in kwcoco.util.util\_archive*), 172  
**area** (*kwcoco.coco\_objects1d.Images property*), 269  
**ARRAY()** (*in module kwcoco.util*), 182  
**ARRAY()** (*in module kwcoco.util.jsonschema\_elements*), 170  
**ARRAY()** (*kwcoco.util.ContainerElements method*), 184  
**ARRAY()** (*kwcoco.util.jsonschema\_elements.ContainerElements method*), 168  
**as\_completed()** (*kwcoco.util.util\_futures.JobPool method*), 175  
**as\_graph()** (*kwcoco.util.delayed\_ops.DelayedOperation method*), 155  
**as\_list()** (*kwcoco.FusedChannelSpec method*), 336  
**as\_oset()** (*kwcoco.FusedChannelSpec method*), 336  
**as\_path()** (*kwcoco.ChannelSpec method*), 307  
**as\_path()** (*kwcoco.FusedChannelSpec method*), 337  
**as\_set()** (*kwcoco.FusedChannelSpec method*), 336  
**as\_xarray()** (*kwcoco.util.delayed\_ops.DelayedChannelConcat method*), 141  
**as\_xarray()** (*kwcoco.util.delayed\_ops.ImageOpsMixin method*), 163  
**asdict()** (*kwcoco.util.dict\_like.DictLike method*), 165  
**asdict()** (*kwcoco.util.DictLike method*), 186  
**assert\_dsets\_allclose()** (*in module kwcoco.coco\_sql\_dataset*), 284  
**assets** (*kwcoco.coco\_image.CocoImage property*), 254  
**assets** (*kwcoco.CocoImage property*), 322  
**attribute\_frequency()** (*kwcoco.coco\_objects1d.ObjectList1D method*), 266  
**auxiliary** (*kwcoco.coco\_sql\_dataset.Image attribute*), 276

**B**

**basic\_stats()** (*kwcoco.coco\_dataset.MixinCocoStats method*), 222  
**bbox** (*kwcoco.coco\_sql\_dataset.Annotation attribute*), 276  
**binarize\_classless()** (*kwcoco.metrics.confusion\_vectors.ConfusionVectors method*), 86  
**binarize\_classless()** (*kwcoco.metrics.ConfusionVectors method*), 117  
**binarize\_ovr()** (*kwcoco.metrics.confusion\_vectors.ConfusionVectors method*), 87  
**binarize\_ovr()** (*kwcoco.metrics.ConfusionVectors method*), 117

**BinaryConfusionVectors** (*class in kwcoco.metrics*), 111  
**BinaryConfusionVectors** (*class in kwcoco.metrics.confusion\_vectors*), 89  
**Boids** (*class in kwcoco.demo.boids*), 23  
**BOOLEAN** (*kwcoco.util.jsonschema\_elements.ScalarElements property*), 167  
**BOOLEAN** (*kwcoco.util.ScalarElements property*), 194  
**boundary\_conditions()** (*kwcoco.demo.boids.Boids method*), 26  
**boxes** (*kwcoco.coco\_objects1d.Annots property*), 271  
**boxsize\_stats()** (*kwcoco.coco\_dataset.MixinCocoStats method*), 223  
**build()** (*kwcoco.coco\_dataset.CocoIndex method*), 237  
**build()** (*kwcoco.coco\_sql\_dataset.CocoSqlIndex method*), 280  
**bundle\_dpath** (*kwcoco.coco\_image.CocoImage property*), 254  
**bundle\_dpath** (*kwcoco.coco\_sql\_dataset.CocoSqlDatabase property*), 284  
**bundle\_dpath** (*kwcoco.CocoImage property*), 322  
**bundle\_dpath** (*kwcoco.CocoSqlDatabase property*), 334

**C**

**cached\_sql\_coco\_view()** (*in module kwcoco.coco\_sql\_dataset*), 284  
**caption** (*kwcoco.coco\_sql\_dataset.Annotation attribute*), 277  
**caption** (*kwcoco.coco\_sql\_dataset.Video attribute*), 276  
**Categories** (*class in kwcoco.coco\_objects1d*), 267  
**categories()** (*kwcoco.coco\_dataset.MixinCocoObjects method*), 219  
**Category** (*class in kwcoco.coco\_sql\_dataset*), 275  
**category\_annotation\_frequency()** (*kwcoco.coco\_dataset.MixinCocoStats method*), 220  
**category\_annotation\_type\_frequency()** (*kwcoco.coco\_dataset.MixinCocoDeprecate method*), 206  
**category\_graph()** (*kwcoco.coco\_dataset.MixinCocoAccessors method*), 210  
**category\_id** (*kwcoco.coco\_objects1d.Annots property*), 270  
**category\_id** (*kwcoco.coco\_sql\_dataset.Annotation attribute*), 276  
**category\_names** (*kwcoco.category\_tree.CategoryTree property*), 204  
**category\_names** (*kwcoco.CategoryTree property*), 302  
**category\_names** (*kwcoco.coco\_objects1d.Annots property*), 270

**CategoryPatterns** (*class in kwcoco.demo.toypatterns*), 63  
**CategoryTree** (*class in kwcoco*), 298  
**CategoryTree** (*class in kwcoco.category\_tree*), 200  
**catname** (*kwcoco.metrics.BinaryConfusionVectors property*), 112  
**catname** (*kwcoco.metrics.confusion\_measures.Measures property*), 73  
**catname** (*kwcoco.metrics.confusion\_vectors.BinaryConfusionVectors property*), 90  
**catname** (*kwcoco.metrics.Measures property*), 128  
**cats** (*kwcoco.category\_tree.CategoryTree property*), 204  
**cats** (*kwcoco.CategoryTree property*), 302  
**cats** (*kwcoco.coco\_dataset.MixinCocoIndex property*), 238  
**cats** (*kwcoco.coco\_sql\_dataset.CocoSqlDatabase property*), 283  
**cats** (*kwcoco.CocoSqlDatabase property*), 333  
**catToImgs** (*kwcoco.compat\_dataset.COCO property*), 285  
**channels** (*kwcoco.coco\_image.CocoImage property*), 255  
**channels** (*kwcoco.coco\_sql\_dataset.Image attribute*), 276  
**channels** (*kwcoco.CocoImage property*), 322  
**channels** (*kwcoco.util.delayed\_ops.DelayedChannelConcat property*), 139  
**channels** (*kwcoco.util.delayed\_ops.DelayedImage property*), 146  
**ChannelSpec** (*class in kwcoco*), 303  
**chans** (*kwcoco.SensorChanSpec property*), 342  
**children()** (*kwcoco.util.delayed\_ops.DelayedNaryOperation method*), 154  
**children()** (*kwcoco.util.delayed\_ops.DelayedOperation method*), 155  
**children()** (*kwcoco.util.delayed\_ops.DelayedUnaryOperation method*), 157  
**cid\_to\_aids** (*kwcoco.coco\_dataset.MixinCocoIndex property*), 238  
**cid\_to\_gids** (*kwcoco.coco\_dataset.CocoIndex property*), 237  
**cid\_to\_rgb()** (*in module kwcoco.data.grab\_camvid*), 20  
**cids** (*kwcoco.coco\_objects1d.AnnotGroups property*), 272  
**cids** (*kwcoco.coco\_objects1d.Annots property*), 270  
**cids** (*kwcoco.coco\_objects1d.Categories property*), 267  
**clamp\_mag()** (*in module kwcoco.demo.boids*), 26  
**class\_accuracy\_from\_confusion()** (*in module kwcoco.metrics.sklearn\_alts*), 109  
**class\_names** (*kwcoco.category\_tree.CategoryTree property*), 204  
**class\_names** (*kwcoco.CategoryTree property*), 302  
**classification\_report()** (*in module kwcoco.metrics.clf\_report*), 70  
**classification\_report()** (*kw-coco.metrics.confusion\_vectors.ConfusionVectors method*), 87  
**classification\_report()** (*kw-coco.metrics.ConfusionVectors method*), 118  
**clear()** (*kwcoco.coco\_dataset.CocoIndex method*), 237  
**clearAnnotations()** (*kwcoco.metrics.detect\_metrics.DetectionMetrics method*), 91  
**clear()** (*kwcoco.metrics.DetectionMetrics method*), 118  
**clear\_annotations()** (*kw-coco.coco\_dataset.MixinCocoAddRemove method*), 233  
**clear\_images()** (*kwcoco.coco\_dataset.MixinCocoAddRemove method*), 233  
**CLIConfig** (*kwcoco.cli.coco\_eval.CocoEvalCLI attribute*), 10  
**close()** (*kwcoco.util.Archive method*), 184  
**close()** (*kwcoco.util.util\_archive.Archive method*), 173  
**closest\_point\_on\_line\_segment()** (*in module kwcoco.demo.boids*), 27  
**cls** (*in module kwcoco.coco\_sql\_dataset*), 277  
**cnames** (*kwcoco.coco\_objects1d.AnnotGroups property*), 272  
**cnames** (*kwcoco.coco\_objects1d.Annots property*), 270  
**coarsen()** (*kwcoco.metrics.confusion\_vectors.ConfusionVectors method*), 86  
**coarsen()** (*kwcoco.metrics.ConfusionVectors method*), 117  
**COCO** (*class in kwcoco.compat\_dataset*), 285  
**coco\_image()** (*kwcoco.coco\_dataset.MixinCocoAccessors method*), 211  
**coco\_images** (*kwcoco.coco\_objects1d.Images property*), 268  
**coco\_to\_kpf()** (*in module kwcoco.kpf*), 289  
**CocoAsset** (*class in kwcoco.coco\_image*), 262  
**CocoConformCLI** (*class in kwcoco.cli.coco\_conform*), 9  
**CocoConformCLI.CLICConfig** (*class in kw-coco.cli.coco\_conform*), 9  
**CocoDataset** (*class in kwcoco*), 311  
**CocoDataset** (*class in kwcoco.coco\_dataset*), 238  
**CocoEvalCLI** (*class in kwcoco.cli.coco\_eval*), 10  
**CocoEvalCLIConfig** (*class in kwcoco.cli.coco\_eval*), 10  
**CocoEvalConfig** (*class in kwcoco.coco\_evaluator*), 250  
**CocoEvaluator** (*class in kwcoco.coco\_evaluator*), 251  
**CocoGrabCLI** (*class in kwcoco.cli.coco\_grab*), 12  
**CocoGrabCLI.CLICConfig** (*class in kw-coco.cli.coco\_grab*), 12  
**CocoImage** (*class in kwcoco*), 321  
**CocoImage** (*class in kwcoco.coco\_image*), 254  
**CocoIndex** (*class in kwcoco.coco\_dataset*), 236  
**CocoModifyCatsCLI** (*class in kw-coco.cli.coco\_modify\_categories*), 12

CocoModifyCatsCLI.CLIConfig (class in kw-  
coco.cli.coco\_modify\_categories), 12  
CocoRerootCLI (class in kwcoco.cli.coco\_reroot), 13  
CocoRerootCLI.CLIConfig (class in kw-  
coco.cli.coco\_reroot), 13  
CocoResults (class in kwcoco.coco\_evaluator), 252  
CocoShowCLI (class in kwcoco.cli.coco\_show), 14  
CocoShowCLI.CLIConfig (class in kw-  
coco.cli.coco\_show), 14  
CocoSingleResult (class in kwcoco.coco\_evaluator),  
253  
CocoSplitCLI (class in kwcoco.cli.coco\_split), 14  
CocoSplitCLI.CLIConfig (class in kw-  
coco.cli.coco\_split), 14  
CocoSqlDatabase (class in kwcoco), 330  
CocoSqlDatabase (class in kwcoco.coco\_sql\_dataset),  
280  
CocoSqlIndex (class in kwcoco.coco\_sql\_dataset), 280  
CocoStatsCLI (class in kwcoco.cli.coco\_stats), 15  
CocoStatsCLI.CLIConfig (class in kw-  
coco.cli.coco\_stats), 15  
CocoSubsetCLI (class in kwcoco.cli.coco\_subset), 16  
CocoSubsetCLI.CLIConfig (class in kw-  
coco.cli.coco\_subset), 16  
CocoToyDataCLI (class in kwcoco.cli.coco\_toydata), 18  
CocoToyDataCLI.CLIConfig (class in kw-  
coco.cli.coco\_toydata), 18  
CocoUnionCLI (class in kwcoco.cli.coco\_union), 18  
CocoUnionCLI.CLIConfig (class in kw-  
coco.cli.coco\_union), 18  
CocoValidateCLI (class in kwcoco.cli.coco\_validate),  
19  
CocoValidateCLI.CLIConfig (class in kw-  
coco.cli.coco\_validate), 19  
code\_list() (kwcoco.ChannelSpec method), 307  
code\_list() (kwcoco.FusedChannelSpec method), 336  
coerce() (kwcoco.category\_tree.CategoryTree class  
method), 202  
coerce() (kwcoco.CategoryTree class method), 300  
coerce() (kwcoco.ChannelSpec class method), 305  
coerce() (kwcoco.coco\_dataset.MixinCocoExtras class  
method), 211  
coerce() (kwcoco.coco\_sql\_dataset.CocoSqlDatabase  
class method), 281  
coerce() (kwcoco.CocoSqlDatabase class method), 330  
coerce() (kwcoco.demo.toypatterns.CategoryPatterns  
class method), 64  
coerce() (kwcoco.FusedChannelSpec class method),  
335  
coerce() (kwcoco.SensorChanSpec class method), 339  
coerce() (kwcoco.util.Archive class method), 184  
coerce() (kwcoco.util.util\_archive.Archive class  
method), 173  
coerce\_indent() (in module kwcoco.util.util\_json),  
179  
coerce\_resolution() (in module kw-  
coco.coco\_image), 262  
combine() (kwcoco.metrics.confusion\_measures.MeasureCombiner  
method), 82  
combine() (kwcoco.metrics.confusion\_measures.Measures  
class method), 75  
combine() (kwcoco.metrics.confusion\_measures.OneVersusRestMeasureCom-  
biner method), 82  
combine() (kwcoco.metrics.Measures class method),  
129  
component\_indices() (kwcoco.ChannelSpec method),  
310  
component\_indices() (kwcoco.FusedChannelSpec  
method), 337  
compress() (kwcoco.coco\_objects1d.ObjectList1D  
method), 264  
compute\_forces() (kwcoco.demo.boids.Boids method),  
26  
concat() (kwcoco.FusedChannelSpec class method),  
334  
concise\_si\_display() (in module kw-  
coco.metrics.drawing), 101  
concise() (kwcoco.ChannelSpec method), 305  
concise() (kwcoco.FusedChannelSpec method), 335  
concise() (kwcoco.SensorChanSpec method), 340  
Config (kwcoco.coco\_evaluator.CocoEvaluator at-  
tribute), 251  
conform() (kwcoco.coco\_dataset.MixinCocoStats  
method), 220  
confusion\_matrix() (in module kw-  
coco.metrics.sklearn\_alts), 108  
confusion\_matrix() (kw-  
coco.metrics.confusion\_vectors.ConfusionVectors  
method), 85  
confusion\_matrix() (kw-  
coco.metrics.ConfusionVectors method),  
116  
confusion\_vectors() (kw-  
coco.metrics.detect\_metrics.DetectionMetrics  
method), 92  
confusion\_vectors() (kw-  
coco.metrics.DetectionMetrics method),  
119  
ConfusionVectors (class in kwcoco.metrics), 113  
ConfusionVectors (class in kw-  
coco.metrics.confusion\_vectors), 83  
connect() (kwcoco.coco\_sql\_dataset.CocoSqlDatabase  
method), 281  
connect() (kwcoco.CocoSqlDatabase method), 331  
ContainerElements (class in kwcoco.util), 184  
ContainerElements (class in kw-  
coco.util.jsonschema\_elements), 168  
convert\_camvid\_raw\_to\_coco() (in module kw-

coco.data.grab\_camvid), 20  
`convert_spacenet_to_kwcoco()` (in module `kwcoco.data.spacenet`), 22  
`convert_voc_to_coco()` (in module `kwcoco.data.grab_voc`), 23  
`copy()` (`kwcoco.category_tree.CategoryTree` method), 201  
`copy()` (`kwcoco.CategoryTree` method), 299  
`copy()` (`kwcoco.coco_dataset.CocoDataset` method), 242  
`copy()` (`kwcoco.CocoDataset` method), 315  
`copy()` (`kwcoco.util.dict_like.DictLike` method), 165  
`copy()` (`kwcoco.util.DictLike` method), 186  
`corrupted_images()` (kwcoco.coco\_dataset.MixinCocoExtras method), 215  
`counts()` (`kwcoco.metrics.confusion_measures.Measures` method), 73  
`counts()` (`kwcoco.metrics.Measures` method), 128  
`createIndex()` (kwcoco.compat\_dataset.COCO method), 285  
`crop()` (kwcoco.util.delayed\_ops.ImageOpsMixin method), 159

**D**

`data_fpath` (kwcoco.coco\_dataset.MixinCocoExtras property), 217  
`data_fpath` (kwcoco.coco\_sql\_dataset.CocoSqlDatabase property), 284  
`data_fpath` (`kwcoco.CocoSqlDatabase` property), 334  
`data_root` (kwcoco.coco\_dataset.MixinCocoExtras property), 217  
`dataset` (kwcoco.coco\_sql\_dataset.CocoSqlDatabase property), 283  
`dataset` (`kwcoco.CocoSqlDatabase` property), 333  
`dataset_modification_example_via_construction()` (in module `kwcoco.examples.modification_example`), 68  
`dataset_modification_example_via_copy()` (in module `kwcoco.examples.modification_example`), 68  
`decode()` (`kwcoco.ChannelSpec` method), 310  
`default` (`kwcoco.cli.coco_conform.CocoConformCLI`.`CLICConfig` attribute), 9  
`default` (`kwcoco.cli.coco_eval.CocoEvalCLI`.`CLICConfig` attribute), 10  
`default` (`kwcoco.cli.coco_grab.CocoGrabCLI`.`CLICConfig` attribute), 12  
`default` (`kwcoco.cli.coco_modify_categories.CocoModifyCatsCLI`.`CLICConfig` attribute), 12  
`default` (`kwcoco.cli.coco_reroot.CocoRerootCLI`.`CLICConfig` attribute), 13  
`default` (`kwcoco.cli.coco_show.CocoShowCLI`.`CLICConfig` attribute), 14  
`default` (`kwcoco.cli.coco_split.CocoSplitCLI`.`CLICConfig` attribute), 14  
`default` (`kwcoco.cli.coco_stats.CocoStatsCLI`.`CLICConfig` attribute), 15  
`default` (`kwcoco.cli.coco_subset.CocoSubsetCLI`.`CLICConfig` attribute), 16  
`default` (`kwcoco.cli.coco_toydata.CocoToyDataCLI`.`CLICConfig` attribute), 18  
`default` (`kwcoco.cli.coco_union.CocoUnionCLI`.`CLICConfig` attribute), 18  
`default` (`kwcoco.cli.coco_validate.CocoValidateCLI`.`CLICConfig` attribute), 19  
`default` (`kwcoco.coco_evaluator.CocoEvalConfig` attribute), 251  
`DEFAULT_COLUMNS` (`kwcoco.kw18.KW18` attribute), 290  
`delay()` (`kwcoco.coco_image.CocoImage` method), 262  
`delay()` (`kwcoco.CocoImage` method), 330  
`delayed_load()` (kwcoco.coco\_dataset.MixinCocoAccessors method), 206  
`DelayedArray` (class in `kwcoco.util.delayed_ops`), 137  
`DelayedAsXarray` (class in `kwcoco.util.delayed_ops`), 137  
`DelayedChannelConcat` (class in `kwcoco.util.delayed_ops`), 138  
`DelayedConcat` (class in `kwcoco.util.delayed_ops`), 144  
`DelayedCrop` (class in `kwcoco.util.delayed_ops`), 144  
`DelayedDequantize` (class in `kwcoco.util.delayed_ops`), 145  
`DelayedFrameStack` (class in `kwcoco.util.delayed_ops`), 146  
`DelayedIdentity` (class in `kwcoco.util.delayed_ops`), 146  
`DelayedImage` (class in `kwcoco.util.delayed_ops`), 146  
`DelayedImageLeaf` (class in `kwcoco.util.delayed_ops`), 150  
`DelayedLoad` (class in `kwcoco.util.delayed_ops`), 150  
`DelayedNans` (class in `kwcoco.util.delayed_ops`), 154  
`DelayedNaryOperation` (class in `kwcoco.util.delayed_ops`), 154  
`DelayedOperation` (class in `kwcoco.util.delayed_ops`), 154  
`DelayedOverview` (class in `kwcoco.util.delayed_ops`), 156  
`DelayedStack` (class in `kwcoco.util.delayed_ops`), 157  
`DelayedUnaryOperation` (class in `kwcoco.util.delayed_ops`), 157  
`DelayedWarp` (class in `kwcoco.util.delayed_ops`), 157  
`delete()` (kwcoco.coco\_sql\_dataset.CocoSqlDatabase method), 282  
`delete()` (`kwcoco.CocoSqlDatabase` method), 331  
`delitem()` (`kwcoco.util.dict_like.DictLike` method), 165  
`delitem()` (`kwcoco.util.DictLike` method), 186  
`demo()` (in module `kwcoco.coco_sql_dataset`), 284  
`demo()` (in module `kwcoco.kpf`), 289

```
demo() (kwcoco.category_tree.CategoryTree      class      coco.metrics.detect_metrics), 91
       method), 202
demo() (kwcoco.CategoryTree class method), 301
demo() (kwcoco.coco_dataset.MixinCocoExtras    class      detections (kwcoco.coco_objects1d.Annots property),
       method), 212                                         270
demo() (kwcoco.kw18.KW18 class method), 290
demo() (kwcoco.metrics.BinaryConfusionVectors  class      deterministic_colors() (in module kw-
       method), 111                                         coco.metrics.drawing), 107
demo() (kwcoco.metrics.confusion_measures.Measures   class      devcheck() (in module kwcoco.coco_sql_dataset), 284
       class method), 75
demo() (kwcoco.metrics.confusion_vectors.BinaryConfusionVectors  class      developing() (kwcoco.util.util_monkey.Reloadable
       class method), 89
       class method), 85
       class method), 85
       class method), 88
       class method), 115
       class method), 96
       class method), 123
       class method), 129
       class method), 134
       class method), 153
       (in module kwcoco.coco_dataset), 248
       (in module kwcoco.metrics.drawing), 101
       (in module kwcoco.examples.loading_multispectral_data), 68
       (in module kwcoco.examples.getting_started_existing_dataset), 67
       (in module kwcoco.examples.vectorized_interface), 69
       (in module kwcoco.demo.toydata), 29
       (in module kwcoco.demo.toydata_image), 42
       (in module kwcoco.demo.toydata), 39
       (in module kwcoco.demo.toydata_image), 44
       (in module kwcoco.coco_schema), 274
       (in module kwcoco.util.delayed_ops.ImageOpsMixin
       method), 163
       (kwcoco.coco_image.CocoImage method), 254
       (kwcoco.CocoImage method), 322
       (class in kwcoco.metrics), 118
       (class in kwcoco.metrics), 118
       class      detections (kwcoco.coco_objects1d.Annots property),
       class      deterministic_colors() (in module kw-
       coco.metrics.drawing), 107
       class      devcheck() (in module kwcoco.coco_sql_dataset), 284
       class      developing() (kwcoco.util.util_monkey.Reloadable
       class method), 180
       class      dict_restructure() (in module kw-
       coco.coco_sql_dataset), 277
       DictLike (class in kwcoco.util.dict_like), 185
       DictProxy (class in kwcoco.util.dict_like), 165
       difference() (kwcoco.ChannelSpec method), 307
       difference() (kwcoco.FusedChannelSpec method),
       337
       disconnect() (kwcoco.coco_sql_dataset.CocoSqlDatabase
       method), 281
       disconnect() (kwcoco.CocoSqlDatabase method), 331
       dmet_area_weights() (in module kw-
       coco.coco_evaluator), 252
       download() (kwcoco.compat_dataset.COCO method),
       288
       draw() (kwcoco.metrics.confusion_measures.Measures
       method), 74
       draw() (kwcoco.metrics.confusion_measures.PerClass_Measures
       method), 79
       draw() (kwcoco.metrics.Measures method), 128
       draw() (kwcoco.metrics.PerClass_Measures method),
       135
       draw_distribution() (kw-
       coco.metrics.BinaryConfusionVectors method),
       113
       draw_distribution() (kw-
       coco.metrics.confusion_vectors.BinaryConfusionVectors
       method), 91
       draw_image() (kwcoco.coco_dataset.MixinCocoDraw
       method), 224
       draw_perclass_prcurve() (in module kw-
       coco.metrics.drawing), 102
       draw_perclass_roc() (in module kw-
       coco.metrics.drawing), 101
       draw_perclass_thresholds() (in module kw-
       coco.metrics.drawing), 103
       draw_pr() (kwcoco.metrics.confusion_measures.PerClass_Measures
       method), 80
       draw_pr() (kwcoco.metrics.PerClass_Measures
       method), 135
       draw_prcurve() (in module kwcoco.metrics.drawing),
       105
       draw_roc() (in module kwcoco.metrics.drawing), 104
       draw_roc() (kwcoco.metrics.confusion_measures.PerClass_Measures
       method), 80
       draw_roc() (kwcoco.metrics.PerClass_Measures
```

*method), 135*  
**draw\_threshold\_curves()** (in module *kw-*  
*coco.metrics.drawing), 106*  
**draw\_true\_and\_pred\_boxes()** (in module *kw-*  
*coco.examples.draw\_gt\_and\_predicted\_boxes),*  
*66*  
**dsize** (*kwcoco.coco\_image.CocoImage* property), 255  
**dsize** (*kwcoco.CocoImage* property), 323  
**dsize** (*kwcoco.util.delayed\_ops.DelayedImage* prop-  
*erty), 146*  
**dump()** (*kwcoco.coco\_dataset.CocoDataset* method),  
*243*  
**dump()** (*kwcoco.coco\_evaluator.CocoResults* method),  
*253*  
**dump()** (*kwcoco.coco\_evaluator.CocoSingleResult*  
*method), 253*  
**dump()** (*kwcoco.CocoDataset* method), 316  
**dump()** (*kwcoco.kw18.KW18* method), 292  
**dump\_figures()** (*kwcoco.coco\_evaluator.CocoResults*  
*method), 253*  
**dump\_figures()** (*kwcoco.coco\_evaluator.CocoSingleResult*  
*method), 253*  
**.dumps()** (*kwcoco.coco\_dataset.CocoDataset* method),  
*242*  
**.dumps()** (*kwcoco.CocoDataset* method), 315  
**.dumps()** (*kwcoco.kw18.KW18* method), 292  
**DuplicateAddError**, 289

**E**

**eff()** (*kwcoco.demo.toypatterns.Rasters* static method),  
*65*  
**Element** (class in *kwcoco.util*), 187  
**Element** (class in *kwcoco.util.jsonschema\_elements*),  
*166*  
**encode()** (*kwcoco.ChannelSpec* method), 308  
**enrich\_confusion\_vectors()** (*kw-*  
*coco.metrics.detect\_metrics.DetectionMetrics*  
*method), 91*  
**enrich\_confusion\_vectors()** (*kw-*  
*coco.metrics.DetectionMetrics* method),  
*118*  
**ensure\_category()** (*kw-*  
*coco.coco\_dataset.MixinCocoAddRemove*  
*method), 231*  
**ensure\_image()** (*kwcoco.coco\_dataset.MixinCocoAddRemove*  
*method), 231*  
**ensure\_json\_serializable()** (in module *kw-*  
*coco.util*), 196  
**ensure\_json\_serializable()** (in module *kw-*  
*coco.util.util\_json*), 177  
**ensure\_sql\_coco\_view()** (in module *kw-*  
*coco.coco\_sql\_dataset*), 284  
**ensure\_voc\_coco()** (in module *kw-*  
*coco.data.grab\_voc*), 23

**ensure\_voc\_data()** (in module *kw-*  
*coco.data.grab\_voc*), 23  
**epilog** (*kwcoco.cli.coco\_conform.CocoConformCLI*.*CLIConfig*  
*attribute), 9*  
**epilog** (*kwcoco.cli.coco\_modify\_categories.CocoModifyCatsCLI*.*CLIConfig*  
*attribute), 12*  
**epilog** (*kwcoco.cli.coco\_reroot.CocoRerootCLI*.*CLIConfig*  
*attribute), 13*  
**epilog** (*kwcoco.cli.coco\_show.CocoShowCLI*.*CLIConfig*  
*attribute), 14*  
**epilog** (*kwcoco.cli.coco\_split.CocoSplitCLI*.*CLIConfig*  
*attribute), 15*  
**epilog** (*kwcoco.cli.coco\_stats.CocoStatsCLI*.*CLIConfig*  
*attribute), 15*  
**epilog** (*kwcoco.cli.coco\_subset.CocoSubsetCLI*.*CLIConfig*  
*attribute), 16*  
**epilog** (*kwcoco.cli.coco\_toydata.CocoToyDataCLI*.*CLIConfig*  
*attribute), 18*  
**epilog** (*kwcoco.cli.coco\_union.CocoUnionCLI*.*CLIConfig*  
*attribute), 18*  
**epilog** (*kwcoco.cli.coco\_validate.CocoValidateCLI*.*CLIConfig*  
*attribute), 19*  
**eval\_detections\_cli()** (in module *kwcoco.metrics*),  
*137*  
**eval\_detections\_cli()** (in module *kw-*  
*coco.metrics.detect\_metrics*), 100  
**evaluate()** (*kwcoco.coco\_evaluator.CocoEvaluator*  
*method), 251*  
**evaluate()** (*kwcoco.util.delayed\_ops.DelayedImage*  
*method), 148*  
**Executor** (class in *kwcoco.util.util\_futures*), 173  
**extended\_stats()** (*kw-*  
*coco.coco\_dataset.MixinCocoStats* method),  
*223*  
**extractall()** (*kwcoco.util.Archive* method), 184  
**extractall()** (*kwcoco.util.util\_archive.Archive*  
*method), 173*

**F**

**FallbackCocoBase** (class in *kwcoco.coco\_sql\_dataset*),  
*275*  
**false\_color()** (in module *kw-*  
*coco.demo.toydata\_video*), 60  
**fast\_confusion\_matrix()** (in module *kw-*  
*coco.metrics.functional*), 108  
**file\_name** (*kwcoco.coco\_sql\_dataset.Image* attribute),  
*276*  
**finalize()** (*kwcoco.metrics.confusion\_measures.MeasureCombiner*  
*method), 82*  
**finalize()** (*kwcoco.metrics.confusion\_measures.OneVersusRestMeasure*  
*method), 82*  
**finalize()** (*kwcoco.util.delayed\_ops.DelayedOperation*  
*method), 155*

`find_asset_obj()` (`kwcoco.coco_image.CocoImage method`), 256  
`find_asset_obj()` (`kwcoco.CocoImage method`), 324  
`find_json_unserializable()` (`in module kwcoco.util`), 196  
`find_json_unserializable()` (`in module kwcoco.util.util_json`), 177  
`find_representative_images()` (`kwcoco.coco_dataset.MixinCocoStats method`), 224  
`find_reroot_autofix()` (`in module kwcoco.cli.coco_reroot`), 13  
`forest_str()` (`kwcoco.category_tree.CategoryTree method`), 204  
`forest_str()` (`kwcoco.CategoryTree method`), 302  
`fpAth` (`kwcoco.coco_dataset.CocoDataset property`), 241  
`fpAth` (`kwcoco.coco_sql_dataset.CocoSqlDatabase property`), 282  
`fpAth` (`kwcoco.CocoDataset property`), 314  
`fpAth` (`kwcoco.CocoSqlDatabase property`), 331  
`fpAth` (`kwcoco.util.DelayedOps.DelayedLoad property`), 153  
`frame_index` (`kwcoco.coco_sql_dataset.Image attribute`), 276  
`from_arrays()` (`kwcoco.metrics.confusion_vectors.ConfusionVectors class method`), 85  
`from_arrays()` (`kwcoco.metrics.ConfusionVectors class method`), 115  
`from_coco()` (`kwcoco.category_tree.CategoryTree class method`), 202  
`from_coco()` (`kwcoco.CategoryTree class method`), 300  
`from_coco()` (`kwcoco.kw18.KW18 class method`), 290  
`from_coco()` (`kwcoco.metrics.detect_metrics.DetectionMetrics class method`), 92  
`from_coco()` (`kwcoco.metrics.DetectionMetrics class method`), 119  
`from_coco_paths()` (`kwcoco.coco_dataset.CocoDataset class method`), 241  
`from_coco_paths()` (`kwcoco.CocoDataset class method`), 314  
`from_data()` (`kwcoco.coco_dataset.CocoDataset class method`), 241  
`from_data()` (`kwcoco.CocoDataset class method`), 314  
`from_gid()` (`kwcoco.coco_image.CocoImage class method`), 254  
`from_gid()` (`kwcoco.CocoImage class method`), 322  
`from_image_paths()` (`kwcoco.coco_dataset.CocoDataset class method`), 241  
`from_image_paths()` (`kwcoco.CocoDataset class method`), 314  
`from_json()` (`kwcoco.category_tree.CategoryTree class method`), 202  
`from_json()` (`kwcoco.CategoryTree class method`), 300  
`from_json()` (`kwcoco.coco_evaluator.CocoResults class method`), 253  
`from_json()` (`kwcoco.coco_evaluator.CocoSingleResult class method`), 253  
`from_json()` (`kwcoco.metrics.confusion_measures.Measures class method`), 73  
`from_json()` (`kwcoco.metrics.confusion_measures.PerClass_Measures class method`), 79  
`from_json()` (`kwcoco.metrics.confusion_vectors.ConfusionVectors class method`), 84  
`from_json()` (`kwcoco.metrics.ConfusionVectors class method`), 115  
`from_json()` (`kwcoco.metrics.Measures class method`), 128  
`from_json()` (`kwcoco.metrics.PerClass_Measures class method`), 135  
`from_mutex()` (`kwcoco.category_tree.CategoryTree class method`), 201  
`from_mutex()` (`kwcoco.CategoryTree class method`), 300  
`fuse()` (`kwcoco.ChannelSpec method`), 306  
`fuse()` (`kwcoco.FusedChannelSpec method`), 338  
`FusedChannelSpec` (`class in kwcoco`), 334

## G

`get()` (`kwcoco.coco_image.CocoAsset method`), 262  
`get()` (`kwcoco.coco_image.CocoImage method`), 255  
`get()` (`kwcoco.coco_objects1d.ObjectList1D method`), 265  
`get()` (`kwcoco.CocoImage method`), 322  
`get()` (`kwcoco.demo.toypatterns.CategoryPatterns method`), 64  
`get()` (`kwcoco.util.dict_like.DictLike method`), 165  
`get()` (`kwcoco.util.DictLike method`), 187  
`get_all_channels_in_dataset()` (`in module kwcoco.examples.faq`), 67  
`get_auxiliary_fpAth()` (`kwcoco.coco_dataset.MixinCocoAccessors method`), 208  
`get_image_fpAth()` (`kwcoco.coco_dataset.MixinCocoAccessors method`), 208  
`get_images_with_videoid()` (`in module kwcoco.examples.faq`), 67  
`get_overview()` (`kwcoco.util.DelayedOps.ImageOpsMixin method`), 163  
`get_transform_from()` (`kwcoco.util.DelayedOps.ImageOpsMixin method`), 163  
`get_transform_from_leaf()` (`kwcoco.util.DelayedOps.DelayedImage method`), 148

get\_transform\_from\_leaf() (kw-  
     coco.util.delayed\_ops.DelayedImageLeaf  
         method), 150

getAnnIds() (kwcoco.compat\_dataset.COCO method),  
     285

getCatIds() (kwcoco.compat\_dataset.COCO method),  
     286

getImgIds() (kwcoco.compat\_dataset.COCO method),  
     286

getitem() (kwcoco.util.dict\_like.DictLike method), 164

getitem() (kwcoco.util.DictLike method), 186

getting\_started\_existing\_dataset()  
     (in module coco.examples.getting\_started\_existing\_dataset), 67

gid\_to\_aids (kwcoco.coco\_dataset.MixinCocoIndex  
     property), 238

gids (kwcoco.coco\_objects1d.Annots property), 270

gids (kwcoco.coco\_objects1d.Images property), 268

global\_accuracy\_from\_confusion() (in module kw-  
     coco.metrics.sklearn\_alts), 109

gname (kwcoco.coco\_objects1d.Images property), 268

gpath (kwcoco.coco\_objects1d.Images property), 268

grab\_camvid\_sampler() (in module kw-  
     coco.data.grab\_camvid), 20

grab\_camvid\_train\_test\_val\_splits() (in module  
     kwcoco.data.grab\_camvid), 20

grab\_coco\_camvid() (in module  
     coco.data.grab\_camvid), 20

grab\_domain\_net() (in module  
     coco.data.grab\_domainnet), 22

grab\_raw\_camvid() (in module  
     coco.data.grab\_camvid), 20

grab\_spacenet7() (in module  
     coco.data.grab\_spacenet), 22

**H**

height (kwcoco.coco\_objects1d.Images property), 268

height (kwcoco.coco\_sql\_dataset.Image attribute), 276

height (kwcoco.coco\_sql\_dataset.Video attribute), 276

**I**

id (kwcoco.coco\_sql\_dataset.Annotation attribute), 276

id (kwcoco.coco\_sql\_dataset.Category attribute), 275

id (kwcoco.coco\_sql\_dataset.Image attribute), 276

id (kwcoco.coco\_sql\_dataset.KeypointCategory at-  
     tribute), 275

id (kwcoco.coco\_sql\_dataset.Video attribute), 276

id\_to\_idx (kwcoco.category\_tree.CategoryTree prop-  
     erty), 203

id\_to\_idx (kwcoco.CategoryTree property), 301

idx\_pairwise\_distance() (kw-  
     coco.category\_tree.CategoryTree method), 203

idx\_pairwise\_distance() (kwcoco.CategoryTree  
     method), 302

idx\_to\_ancestor\_idxs() (kw-  
     coco.category\_tree.CategoryTree method),  
     203

idx\_to\_ancestor\_idxs() (kwcoco.CategoryTree  
     method), 301

idx\_to\_descendants\_idxs() (kw-  
     coco.category\_tree.CategoryTree method),  
     203

idx\_to\_descendants\_idxs() (kwcoco.CategoryTree  
     method), 302

idx\_to\_id (kwcoco.category\_tree.CategoryTree prop-  
     erty), 203

idx\_to\_id (kwcoco.CategoryTree property), 301

Image (class in kwcoco.coco\_sql\_dataset), 276

image\_id (kwcoco.coco\_objects1d.Annots property),  
     270

image\_id (kwcoco.coco\_sql\_dataset.Annotation at-  
     tribute), 276

ImageGroups (class in kwcoco.coco\_objects1d), 272

ImageOpsMixin (class in kwcoco.util.delayed\_ops), 159

Images (class in kwcoco.coco\_objects1d), 268

images (kwcoco.coco\_objects1d.Annots property), 270

images (kwcoco.coco\_objects1d.Videos property), 268

images() (kwcoco.coco\_dataset.MixinCocoObjects  
     method), 218

imdelay() (kwcoco.coco\_image.CocoImage method),  
     258

imdelay() (kwcoco.CocoImage method), 326

img\_root (kwcoco.coco\_dataset.MixinCocoExtras prop-  
     erty), 217

imgs (kwcoco.coco\_dataset.MixinCocoIndex property),  
     238

imgs (kwcoco.coco\_sql\_dataset.CocoSqlDatabase prop-  
     erty), 283

imgs (kwcoco.CocoSqlDatabase property), 333

imgToAnns (kwcoco.compat\_dataset.COCO property),  
     285

imread() (kwcoco.coco\_dataset.MixinCocoDeprecate  
     method), 206

index() (kwcoco.category\_tree.CategoryTree method),  
     204

index() (kwcoco.CategoryTree method), 302

index() (kwcoco.demo.toypatterns.CategoryPatterns  
     method), 64

indexable\_allclose() (in module kwcoco.util), 197

indexable\_allclose() (in module  
     coco.util.util\_json), 178

IndexableWalker (class in kwcoco.util), 188

info (kwcoco.ChannelSpec property), 305

info() (kwcoco.compat\_dataset.COCO method), 285

initialize() (kwcoco.demo.boids.Boids method), 25

INTEGER (kwcoco.util.jsonschema\_elements.ScalarElements

*property), 167*  
INTEGER (*kwcoco.util.ScalarElements property*), 194  
intersection() (*kwcoco.ChannelSpec method*), 307  
intersection() (*kwcoco.FusedChannelSpec method*),  
    337  
InvalidAddError, 289  
is\_mutex() (*kwcoco.category\_tree.CategoryTree  
method*), 204  
is\_mutex() (*kwcoco.CategoryTree method*), 302  
iscrowd (*kwcoco.coco\_sql\_dataset.Annotation  
attribute*), 277  
issubset() (*kwcoco.ChannelSpec method*), 308  
issubset() (*kwcoco.FusedChannelSpec method*), 337  
issuperset() (*kwcoco.ChannelSpec method*), 308  
issuperset() (*kwcoco.FusedChannelSpec method*),  
    337  
items() (*kwcoco.ChannelSpec method*), 306  
items() (*kwcoco.coco\_sql\_dataset.SqlDictProxy  
method*), 279  
items() (*kwcoco.coco\_sql\_dataset.SqlIdGroupDictProxy  
method*), 280  
items() (*kwcoco.util.dict\_like.DictLike method*), 165  
items() (*kwcoco.util.DictLike method*), 186  
iter\_asset\_objs() (*kwcoco.coco\_image.CocoImage  
method*), 256  
iter\_asset\_objs() (*kwcoco.CocoImage method*), 324  
iter\_image\_filepaths() (*kw-  
coco.coco\_image.CocoImage method*), 256  
iter\_image\_filepaths() (*kwcoco.CocoImage  
method*), 324

**J**

JobPool (*class in kwcoco.util.util\_futures*), 174  
join() (*kwcoco.util.util\_futures.JobPool method*), 176

**K**

keypoint\_annotation\_frequency() (*kw-  
coco.coco\_dataset.MixinCocoDeprecate  
method*), 206  
keypoint\_categories() (*kw-  
coco.coco\_dataset.MixinCocoAccessors  
method*), 211  
KeypointCategory (*class in kwcoco.coco\_sql\_dataset*),  
    275  
keypoints (*kwcoco.coco\_sql\_dataset.Annotation  
attribute*), 276  
keys() (*kwcoco.ChannelSpec method*), 306  
keys() (*kwcoco.coco\_image.CocoAsset method*), 262  
keys() (*kwcoco.coco\_image.CocoImage method*), 254  
keys() (*kwcoco.coco\_sql\_dataset.SqlDictProxy  
method*), 279  
keys() (*kwcoco.coco\_sql\_dataset.SqlIdGroupDictProxy  
method*), 280  
keys() (*kwcoco.CocoImage method*), 322

keys() (*kwcoco.metrics.confusion\_vectors.OneVsRestConfusionVectors  
method*), 88  
keys() (*kwcoco.metrics.OneVsRestConfusionVectors  
method*), 134  
keys() (*kwcoco.util.dict\_like.DictLike method*), 165  
keys() (*kwcoco.util.dict\_like.DictProxy method*), 165  
keys() (*kwcoco.util.DictLike method*), 186  
KW18 (*class in kwcoco.kw18*), 290  
kwcoco  
    module, 292  
kwcoco.\_\_init\_\_  
    module, 1  
kwcoco.abstract\_coco\_dataset  
    module, 200  
kwcoco.category\_tree  
    module, 200  
kwcoco.channel\_spec  
    module, 205  
kwcoco.cli  
    module, 20  
kwcoco.cli.coco\_conform  
    module, 9  
kwcoco.cli.coco\_eval  
    module, 10  
kwcoco.cli.coco\_grab  
    module, 12  
kwcoco.cli.coco\_modify\_categories  
    module, 12  
kwcoco.cli.coco\_reroot  
    module, 13  
kwcoco.cli.coco\_show  
    module, 14  
kwcoco.cli.coco\_split  
    module, 14  
kwcoco.cli.coco\_stats  
    module, 15  
kwcoco.cli.coco\_subset  
    module, 16  
kwcoco.cli.coco\_toydata  
    module, 18  
kwcoco.cli.coco\_union  
    module, 18  
kwcoco.cli.coco\_validate  
    module, 19  
kwcoco.coco\_dataset  
    module, 205  
kwcoco.coco\_evaluator  
    module, 249  
kwcoco.coco\_image  
    module, 254  
kwcoco.coco\_objects1d  
    module, 263  
kwcoco.coco\_schema  
    module, 273

```

kwcoco.coco_sql_dataset
    module, 274
kwcoco.compat_dataset
    module, 285
kwcoco.data
    module, 23
kwcoco.data.grab_camvid
    module, 20
kwcoco.data.grab_datasets
    module, 21
kwcoco.data.grab_domainnet
    module, 22
kwcoco.data.grab_spacenet
    module, 22
kwcoco.data.grab_voc
    module, 23
kwcoco.demo
    module, 66
kwcoco.demo.boids
    module, 23
kwcoco.demo.perterb
    module, 28
kwcoco.demo.toydata
    module, 29
kwcoco.demo.toydata_image
    module, 42
kwcoco.demo.toydata_video
    module, 48
kwcoco.demo.toypatterns
    module, 63
kwcoco.examples
    module, 69
kwcoco.examples.draw_gt_and_predicted_boxes
    module, 66
kwcoco.examples.faq
    module, 67
kwcoco.examples.getting_started_existing_dataset
    module, 67
kwcoco.examples.loading_multispectral_data
    module, 68
kwcoco.examples.modification_example
    module, 68
kwcoco.examples.simple_kwkcoco_torch_dataset
    module, 68
kwcoco.examples.vectorized_interface
    module, 69
kwcoco.exceptions
    module, 289
kwcoco.kpf
    module, 289
kwcoco.kw18
    module, 289
kwcoco.metrics
    module, 111
kwcoco.metrics.assignment
    module, 69
kwcoco.metrics.clf_report
    module, 70
kwcoco.metrics.confusion_measures
    module, 72
kwcoco.metrics.confusion_vectors
    module, 83
kwcoco.metrics.detect_metrics
    module, 91
kwcoco.metrics.drawing
    module, 101
kwcoco.metrics.functional
    module, 108
kwcoco.metrics.sklearn_alts
    module, 108
kwcoco.metrics.voc_metrics
    module, 109
kwcoco.sensorchan_spec
    module, 292
kwcoco.util
    module, 182
kwcoco.util.delayed_ops
    module, 137
kwcoco.util.dict_like
    module, 164
kwcoco.util.jsonschema_elements
    module, 166
kwcoco.util.lazy_frame_backends
    module, 172
kwcoco.util.util_archive
    module, 172
kwcoco.util.util_futures
    module, 173
kwcoco.util.util_json
    module, 177
kwcoco.util.util_monkey
    module, 179
kwcoco.util.util_reroot
    module, 180
kwcoco.util.util_sklearn
    module, 182
kwcoco.util.util_truncate
    module, 182
KW CocoSimpleTorchDataset (class in kwcoco.examples.simple_kwkcoco_torch_dataset), 68
L
late_fuse() (kwcoco.SensorChanSpec method), 340
load() (kwcoco.kw18.KW18 class method), 291
load_annot_sample() (kwcoco.coco_dataset.MixinCocoAccessors method), 209

```

load\_image() (*kwCOCO.coco\_dataset.MixinCocoAccessors method*), 208  
loadAnns() (*kwCOCO.compat\_dataset.COCO method*), 287  
loadCats() (*kwCOCO.compat\_dataset.COCO method*), 287  
loadImgs() (*kwCOCO.compat\_dataset.COCO method*), 287  
loadNumpyAnnotations() (*kwCOCO.compat\_dataset.COCO method*), 288  
loadRes() (*kwCOCO.compat\_dataset.COCO method*), 287  
loads() (*kwCOCO.kw18.KW18 class method*), 291  
log() (*kwCOCO.coco\_evaluator.CocoEvaluator method*), 251  
lookup() (*kwCOCO.coco\_objects1d.ObjectGroups method*), 267  
lookup() (*kwCOCO.coco\_objects1d.ObjectList1D method*), 264

**M**

main() (*in module kwCOCO.cli.coco\_eval*), 11  
main() (*in module kwCOCO.data.grab\_camvid*), 21  
main() (*in module kwCOCO.data.grab\_spacenet*), 22  
main() (*in module kwCOCO.data.grab\_voc*), 23  
main() (*kwCOCO.cli.coco\_conform.CocoConformCLI class method*), 9  
main() (*kwCOCO.cli.coco\_eval.CocoEvalCLI class method*), 10  
main() (*kwCOCO.cli.coco\_grab.CocoGrabCLI class method*), 12  
main() (*kwCOCO.cli.coco\_modify\_categories.CocoModifyCategories class method*), 12  
main() (*kwCOCO.cli.coco\_reroot.CocoRerootCLI class method*), 13  
main() (*kwCOCO.cli.coco\_show.CocoShowCLI class method*), 14  
main() (*kwCOCO.cli.coco\_split.CocoSplitCLI class method*), 15  
main() (*kwCOCO.cli.coco\_stats.CocoStatsCLI class method*), 15  
main() (*kwCOCO.cli.coco\_subset.CocoSubsetCLI class method*), 16  
main() (*kwCOCO.cli.coco\_toydata.CocoToyDataCLI class method*), 18  
main() (*kwCOCO.cli.coco\_union.CocoUnionCLI class method*), 18  
main() (*kwCOCO.cli.coco\_validate.CocoValidateCLI class method*), 19  
map() (*kwCOCO.util.util\_futures.Executor method*), 174  
matching\_sensor() (*kwCOCO.SensorChanSpec method*), 342  
maximized\_thresholds() (*kwCOCO.metrics.confusion\_measures.Measures method*), 73  
maximized\_thresholds() (*kwCOCO.metrics.Measures method*), 128  
MeasureCombiner (*class in kwCOCO.metrics.confusion\_measures*), 81  
Measures (*class in kwCOCO.metrics*), 127  
Measures (*class in kwCOCO.metrics.confusion\_measures*), 72  
measures() (*kwCOCO.metrics.BinaryConfusionVectors method*), 112  
measures() (*kwCOCO.metrics.confusion\_vectors.BinaryConfusionVectors method*), 90  
measures() (*kwCOCO.metrics.confusion\_vectors.OneVsRestConfusionVector method*), 88  
measures() (*kwCOCO.metrics.OneVsRestConfusionVectors method*), 134  
MEMORY\_URI (*kwCOCO.coco\_sql\_dataset.CocoSqlDatabase attribute*), 281  
MEMORY\_URI (*kwCOCO.CocoSqlDatabase attribute*), 330  
missing\_images() (*kwCOCO.coco\_dataset.MixinCocoExtras method*), 215  
MixinCocoAccessors (*class in kwCOCO.coco\_dataset*), 206  
MixinCocoAddRemove (*class in kwCOCO.coco\_dataset*), 226  
MixinCocoDeprecate (*class in kwCOCO.coco\_dataset*), 206  
MixinCocoDraw (*class in kwCOCO.coco\_dataset*), 224  
MixinCocoExtras (*class in kwCOCO.coco\_dataset*), 211  
MixinCocoIndex (*class in kwCOCO.coco\_dataset*), 238  
MixinCocoObjects (*class in kwCOCO.coco\_dataset*), 217  
MixinCocoStats (*class in kwCOCO.coco\_dataset*), 220  
module  
    kwCOCO, 292  
    kwCOCO.\_\_init\_\_, 1  
    kwCOCO.abstract\_coco\_dataset, 200  
    kwCOCO.category\_tree, 200  
    kwCOCO.channel\_spec, 205  
    kwCOCO.cli, 20  
    kwCOCO.cli.coco\_conform, 9  
    kwCOCO.cli.coco\_eval, 10  
    kwCOCO.cli.coco\_grab, 12  
    kwCOCO.cli.coco\_modify\_categories, 12  
    kwCOCO.cli.coco\_reroot, 13  
    kwCOCO.cli.coco\_show, 14  
    kwCOCO.cli.coco\_split, 14  
    kwCOCO.cli.coco\_stats, 15  
    kwCOCO.cli.coco\_subset, 16  
    kwCOCO.cli.coco\_toydata, 18  
    kwCOCO.cli.coco\_union, 18  
    kwCOCO.cli.coco\_validate, 19  
    kwCOCO.coco\_dataset, 205  
    kwCOCO.coco\_evaluator, 249

kwcoco.coco\_image, 254  
 kwcoco.coco\_objects1d, 263  
 kwcoco.coco\_schema, 273  
 kwcoco.coco\_sql\_dataset, 274  
 kwcoco.compat\_dataset, 285  
 kwcoco.data, 23  
 kwcoco.data.grab\_camvid, 20  
 kwcoco.data.grab\_datasets, 21  
 kwcoco.data.grab\_domainnet, 22  
 kwcoco.data.grab\_spacenet, 22  
 kwcoco.data.grab\_voc, 23  
 kwcoco.demo, 66  
 kwcoco.demo.boids, 23  
 kwcoco.demo.perterb, 28  
 kwcoco.demo.toydata, 29  
 kwcoco.demo.toydata\_image, 42  
 kwcoco.demo.toydata\_video, 48  
 kwcoco.demo.toypatterns, 63  
 kwcoco.examples, 69  
 kwcoco.examples.draw\_gt\_and\_predicted\_boxes, 66  
 kwcoco.examples.faq, 67  
 kwcoco.examples.getting\_started\_existing\_dataset, 67  
 kwcoco.examples.loading\_multispectral\_data, 68  
 kwcoco.examples.modification\_example, 68  
 kwcoco.examples.simple\_kwccoco\_torch\_dataset, 68  
 kwcoco.examples.vectorized\_interface, 69  
 kwcoco.exceptions, 289  
 kwcoco.kpf, 289  
 kwcoco.kw18, 289  
 kwcoco.metrics, 111  
 kwcoco.metrics.assignment, 69  
 kwcoco.metrics.clf\_report, 70  
 kwcoco.metrics.confusion\_measures, 72  
 kwcoco.metrics.confusion\_vectors, 83  
 kwcoco.metrics.detect\_metrics, 91  
 kwcoco.metrics.drawing, 101  
 kwcoco.metrics.functional, 108  
 kwcoco.metrics.sklearn\_alts, 108  
 kwcoco.metrics.voc\_metrics, 109  
 kwcoco.sensorchan\_spec, 292  
 kwcoco.util, 182  
 kwcoco.util.delayed\_ops, 137  
 kwcoco.util.dict\_like, 164  
 kwcoco.util.jsonschema\_elements, 166  
 kwcoco.util.lazy\_frame\_backends, 172  
 kwcoco.util.util\_archive, 172  
 kwcoco.util.util\_futures, 173  
 kwcoco.util.util\_json, 177  
 kwcoco.util.util\_monkey, 179  
 kwcoco.util.util\_reroot, 180  
 kwcoco.util.util\_sklearn, 182  
 kwcoco.util.util\_truncate, 182

## N

n\_annotss (*kwcoco.coco\_dataset.MixinCocoStats property*), 220  
 n\_annotss (*kwcoco.coco\_objects1d.Images property*), 269  
 n\_cats (*kwcoco.coco\_dataset.MixinCocoStats property*), 220  
 n\_images (*kwcoco.coco\_dataset.MixinCocoStats property*), 220  
 n\_videos (*kwcoco.coco\_dataset.MixinCocoStats property*), 220  
 name (*kwcoco.cli.coco\_conform.CocoConformCLI attribute*), 9  
 name (*kwcoco.cli.coco\_eval.CocoEvalCLI attribute*), 10  
 name (*kwcoco.cli.coco\_grab.CocoGrabCLI attribute*), 12  
 name (*kwcoco.cli.coco\_modify\_categories.CocoModifyCatsCLI attribute*), 12  
 name (*kwcoco.cli.coco\_reroot.CocoRerootCLI attribute*), 13  
 name (*kwcoco.cli.coco\_show.CocoShowCLI attribute*), 14  
 name (*kwcoco.cli.coco\_split.CocoSplitCLI attribute*), 14  
 name (*kwcoco.cli.coco\_stats.CocoStatsCLI attribute*), 15  
 name (*kwcoco.cli.coco\_subset.CocoSubsetCLI attribute*), 16  
 name (*kwcoco.cli.coco\_toydata.CocoToyDataCLI attribute*), 18  
 name (*kwcoco.cli.coco\_union.CocoUnionCLI attribute*), 18  
 name (*kwcoco.cli.coco\_validate.CocoValidateCLI attribute*), 19  
 name (*kwcoco.coco\_objects1d.Categories property*), 267  
 name (*kwcoco.coco\_sql\_dataset.Category attribute*), 275  
 name (*kwcoco.coco\_sql\_dataset.Image attribute*), 276  
 name (*kwcoco.coco\_sql\_dataset.KeypointCategory attribute*), 275  
 name (*kwcoco.coco\_sql\_dataset.Video attribute*), 276  
 name\_to\_cat (*kwcoco.coco\_dataset.MixinCocoIndex property*), 238  
 name\_to\_cat (*kwcoco.coco\_sql\_dataset.CocoSqlDatabase property*), 283  
 name\_to\_cat (*kwcoco.CocoSqlDatabase property*), 333  
 names() (*kwcoco.util.Archive method*), 184  
 names() (*kwcoco.util.util\_archive.Archive method*), 173  
 nesting() (*kwcoco.util.delayed\_ops.DelayedOperation method*), 154  
 normalize() (*kwcoco.category\_tree.CategoryTree method*), 204  
 normalize() (*kwcoco.CategoryTree method*), 303  
 normalize() (*kwcoco.ChannelSpec method*), 306  
 normalize() (*kwcoco.coco\_evaluator.CocoEvalConfig method*), 251

normalize() (*kwcoco.FusedChannelSpec method*), 335  
 normalize() (*kwcoco.SensorChanSpec method*), 340  
 NOT() (*in module kwcoco.util*), 193  
 NOT() (*in module kwcoco.util.jsonschema\_elements*), 171  
 NOT() (*kwcoco.util.jsonschema\_elements.QuantifierElements method*), 168  
 NOT() (*kwcoco.util.QuantifierElements method*), 194  
 NULL (*kwcoco.util.jsonschema\_elements.ScalarElements property*), 167  
 NULL (*kwcoco.util.ScalarElements property*), 194  
 num\_channels (*kwcoco.coco\_image.CocoImage property*), 255  
 num\_channels (*kwcoco.CocoImage property*), 323  
 num\_channels (*kwcoco.util.delayed\_ops.DelayedImage property*), 146  
 num\_classes (*kwcoco.category\_tree.CategoryTree property*), 204  
 num\_classes (*kwcoco.CategoryTree property*), 302  
 num\_overviews (*kwcoco.util.delayed\_ops.DelayedChannel property*), 141  
 num\_overviews (*kwcoco.util.delayed\_ops.DelayedImage property*), 146  
 num\_overviews (*kwcoco.util.delayed\_ops.DelayedOverview property*), 157  
 NUMBER (*kwcoco.util.jsonschema\_elements.ScalarElements property*), 167  
 NUMBER (*kwcoco.util.ScalarElements property*), 194  
 numel() (*kwcoco.ChannelSpec method*), 308  
 numel() (*kwcoco.FusedChannelSpec method*), 336

**O**

OBJECT() (*in module kwcoco.util*), 193  
 OBJECT() (*in module kwcoco.util.jsonschema\_elements*), 171  
 OBJECT() (*kwcoco.util.ContainerElements method*), 185  
 OBJECT() (*kwcoco.util.jsonschema\_elements.ContainerElements method*), 168  
 object\_categories() (*kwcoco.coco\_dataset.MixinCocoAccessors method*), 210  
 ObjectGroups (*class in kwcoco.coco\_objects1d*), 267  
 ObjectList1D (*class in kwcoco.coco\_objects1d*), 263  
 objs (*kwcoco.coco\_objects1d.ObjectList1D property*), 263  
 ONEOF() (*in module kwcoco.util*), 193  
 ONEOF() (*in module kwcoco.util.jsonschema\_elements*), 171  
 ONEOF() (*kwcoco.util.jsonschema\_elements.QuantifierElements method*), 168  
 ONEOF() (*kwcoco.util.QuantifierElements method*), 194  
 OneVersusRestMeasureCombiner (*class in kwcoco.metrics.confusion\_measures*), 82  
 OneVsRestConfusionVectors (*class in kwcoco.metrics*), 134

OneVsRestConfusionVectors (*class in kwcoco.metrics.confusion\_vectors*), 88  
 optimize() (*kwcoco.util.delayed\_ops.DelayedAsXarray method*), 138  
 optimize() (*kwcoco.util.delayed\_ops.DelayedChannelConcat method*), 139  
 optimize() (*kwcoco.util.delayed\_ops.DelayedCrop method*), 145  
 optimize() (*kwcoco.util.delayed\_ops.DelayedDequantize method*), 145  
 optimize() (*kwcoco.util.delayed\_ops.DelayedImageLeaf method*), 150  
 optimize() (*kwcoco.util.delayed\_ops.DelayedOperation method*), 156  
 optimize() (*kwcoco.util.delayed\_ops.DelayedOverview method*), 157  
 optimize() (*kwcoco.util.delayed\_ops.DelayedWarp method*), 158

orm\_to\_dict() (*in module kwcoco.coco\_sql\_dataset*), 277  
 ovr\_classification\_report() (*in module kwcoco.metrics.clf\_report*), 71  
 ovr\_classification\_report() (*kwcoco.metrics.confusion\_vectors.OneVsRestConfusionVectors method*), 89  
 ovr\_classification\_report() (*kwcoco.metrics.OneVsRestConfusionVectors method*), 135

**P**

parse() (*kwcoco.ChannelSpec method*), 305  
 parse() (*kwcoco.FusedChannelSpec class method*), 335  
 parse\_quantity() (*in module kwcoco.coco\_image*), 262  
 paths() (*kwcoco.demo.boids.Boids method*), 26  
 petrify() (*in module kwcoco.metrics.detect\_metrics*), 101  
 peek() (*kwcoco.coco\_objects1d.ObjectList1D method*), 264  
 PerClass\_Measures (*class in kwcoco.metrics*), 135  
 PerClass\_Measures (*class in kwcoco.metrics.confusion\_measures*), 79  
 perterb\_coco() (*in module kwcoco.demo.perterb*), 28  
 populate\_from() (*kwcoco.coco\_sql\_dataset.CocoSqlDatabase method*), 282  
 populate\_from() (*kwcoco.CocoSqlDatabase method*), 331  
 populate\_info() (*in module kwcoco.metrics.confusion\_measures*), 82  
 pred\_detections() (*kwcoco.metrics.detect\_metrics.DetectionMetrics method*), 92

<code>pred_detections()</code> ( <code>kwcoco.metrics.DetectionMetrics method</code> ), 119	<code>reconstruct()</code> ( <code>kwcoco.metrics.confusion_measures.Measures method</code> ), 73
<code>prepare()</code> ( <code>kwcoco.util.delayed_ops.DelayedLoad method</code> ), 154	<code>reconstruct()</code> ( <code>kwcoco.metrics.Measures method</code> ), 128
<code>prepare()</code> ( <code>kwcoco.util.delayed_ops.DelayedOperation method</code> ), 155	<code>reflection_id()</code> ( <code>kwcoco.coco_sql_dataset.KeypointCategory attribute</code> ), 275
<code>primary_asset()</code> ( <code>kwcoco.coco_image.CocoImage method</code> ), 255	<code>Reloadable</code> ( <code>class in kwcoco.util.util_monkey</code> ), 179
<code>primary_asset()</code> ( <code>kwcoco.CocoImage method</code> ), 323	<code>remove_annotation()</code> ( <code>kw- coco.coco_dataset.MixinCocoAddRemove method</code> ), 233
<code>primary_image_filepath()</code> ( <code>kw- coco.coco_image.CocoImage method</code> ), 255	<code>remove_annotation_keypoints()</code> ( <code>kw- coco.coco_dataset.MixinCocoAddRemove method</code> ), 235
<code>primary_image_filepath()</code> ( <code>kwcoco.CocoImage method</code> ), 323	<code>remove_annotations()</code> ( <code>kw- coco.coco_dataset.MixinCocoAddRemove method</code> ), 233
<code>print_graph()</code> ( <code>kwcoco.util.delayed_ops.DelayedOperation method</code> ), 155	<code>remove_categories()</code> ( <code>kw- coco.coco_dataset.MixinCocoAddRemove method</code> ), 234
<code>prob</code> ( <code>kwcoco.coco_sql_dataset.Annotation attribute</code> ), 277	<code>remove_images()</code> ( <code>kw- coco.coco_dataset.MixinCocoAddRemove method</code> ), 234
<code>pycocotools_confusion_vectors()</code> ( <code>in module kw- coco.metrics.detect_metrics</code> ), 100	<code>remove_keypoint_categories()</code> ( <code>kw- coco.coco_dataset.MixinCocoAddRemove method</code> ), 236
<b>Q</b>	<code>remove_videos()</code> ( <code>kw- coco.coco_dataset.MixinCocoAddRemove method</code> ), 235
<code>QuantifierElements</code> ( <code>class in kwcoco.util</code> ), 193	<code>rename_categories()</code> ( <code>kw- coco.coco_dataset.MixinCocoExtras method</code> ), 215
<code>QuantifierElements</code> ( <code>class in kw- coco.util.jsonschema_elements</code> ), 167	<code>render_background()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 60
<code>query_subset()</code> ( <code>in module kwcoco.cli.coco_subset</code> ), 16	<code>render_category()</code> ( <code>kw- coco.demo.toypatterns.CategoryPatterns method</code> ), 65
<code>queue_size</code> ( <code>kwcoco.metrics.confusion_measures.MeasureCombiner property</code> ), 82	<code>render_foreground()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 60
<b>R</b>	<code>render_toy_dataset()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 56
<code>random()</code> ( <code>kwcoco.coco_dataset.MixinCocoExtras class method</code> ), 214	<code>render_toy_image()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 58
<code>random_category()</code> ( <code>kw- coco.demo.toypatterns.CategoryPatterns method</code> ), 64	<code>rerooot()</code> ( <code>kwcoco.coco_dataset.MixinCocoExtras method</code> ), 216
<code>random_multi_object_path()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 60	<code>resize()</code> ( <code>kwcoco.util.delayed_ops.ImageOpsMixin method</code> ), 163
<code>random_path()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 60	<code>resolution()</code> ( <code>kwcoco.coco_image.CocoImage method</code> ), 262
<code>random_single_video_dset()</code> ( <code>in module kw- coco.demo.toydata</code> ), 31	<code>resolution()</code> ( <code>kwkoco.CocoImage method</code> ), 329
<code>random_single_video_dset()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 51	<code>resolve_directory_symlinks()</code> ( <code>in module kw- coco.util</code> ), 198
<code>random_video_dset()</code> ( <code>in module kw- coco.demo.toydata</code> ), 37	<code>resolve_directory_symlinks()</code> ( <code>in module kw- coco.util.util_reroot</code> ), 182
<code>random_video_dset()</code> ( <code>in module kw- coco.demo.toydata_video</code> ), 48	<code>resolve_relative_to()</code> ( <code>in module kwcoco.util</code> ), 198
<code>Rasters</code> ( <code>class in kwcoco.demo.toypatterns</code> ), 65	
<code>raw_table()</code> ( <code>kwkoco.coco_sql_dataset.CocoSqlDatabase method</code> ), 283	
<code>raw_table()</code> ( <code>kwkoco.CocoSqlDatabase method</code> ), 333	
<code>read()</code> ( <code>kwkoco.util.Archive method</code> ), 184	
<code>read()</code> ( <code>kwkoco.util.util_archive.Archive method</code> ), 173	

resolve\_relative\_to() (in module `coco.util.util_reroot`), 180  
reversible\_diff() (in module `coco.metrics.confusion_measures`), 79  
rgb\_to\_cid() (in module `kwcoco.data.grab_camvid`), 20

**S**

ScalarElements (class in `kwcoco.util`), 194  
ScalarElements (class in `kwcoco.util.jsonschema_elements`), 167  
scale() (`kwcoco.util.delayed_ops.ImageOpsMixin method`), 163  
SchemaElements (class in `kwcoco.util`), 194  
SchemaElements (class in `kwcoco.util.jsonschema_elements`), 169  
score (`kwcoco.coco_sql_dataset.Annotation attribute`), 276  
score() (`kwcoco.metrics.voc_metrics.VOC_Metrics method`), 109  
score\_coco() (`kwcoco.metrics.detect_metrics.DetectionMetrics method`), 95  
score\_coco() (`kwcoco.metrics.DetectionMetrics method`), 122  
score\_kwant() (`kwcoco.metrics.detect_metrics.DetectionMetrics method`), 93  
score\_kwant() (`kwcoco.metrics.DetectionMetrics method`), 120  
score\_kwkcoco() (`kwcoco.metrics.detect_metrics.DetectionMetrics method`), 93  
score\_kwkcoco() (`kwcoco.metrics.DetectionMetrics method`), 120  
score\_pycocotools() (`kwcoco.metrics.detect_metrics.DetectionMetrics method`), 94  
score\_pycocotools() (`kwcoco.metrics.DetectionMetrics method`), 121  
score\_voc() (`kwcoco.metrics.detect_metrics.DetectionMetrics method`), 93  
score\_voc() (`kwcoco.metrics.DetectionMetrics method`), 120  
segmentation (`kwcoco.coco_sql_dataset.Annotation attribute`), 276  
send() (`kwcoco.util.IndexableWalker method`), 190  
SensorChanSpec (class in `kwcoco`), 338  
set() (`kwcoco.coco_objects1d.ObjectList1D method`), 266  
set\_annotation\_category() (`kwcoco.coco_dataset.MixinCocoAddRemove method`), 236  
setitem() (`kwcoco.util.dict_like.DictLike method`), 165  
setitem() (`kwcoco.util.DictLike method`), 186

shape (`kwcoco.util.delayed_ops.DelayedArray property`), 137  
shape (`kwcoco.util.delayed_ops.DelayedChannelConcat property`), 139  
shape (`kwcoco.util.delayed_ops.DelayedConcat property`), 144  
shape (`kwcoco.util.delayed_ops.DelayedImage property`), 146  
shape (`kwcoco.util.delayed_ops.DelayedOperation property`), 155  
shape (`kwcoco.util.delayed_ops.DelayedStack property`), 157  
show() (`kwcoco.category_tree.CategoryTree method`), 204  
show() (`kwcoco.CategoryTree method`), 302  
show\_image() (`kwcoco.coco_dataset.MixinCocoDraw method`), 225  
showAnns() (`kwcoco.compat_dataset.COCO method`), 287  
shutdown() (`kwcoco.util.util_futures.Executor method`), 174  
shutdown() (`kwcoco.util.util_futures.JobPool method`), 175  
size (`kwcoco.coco_objects1d.Images property`), 268  
sizes() (`kwcoco.ChannelSpec method`), 308  
sizes() (`kwcoco.FusedChannelSpec method`), 336  
smart\_truncate() (in module `kwcoco.util`), 199  
smart\_truncate() (in module `kwcoco.util`), 200  
spec (`kwcoco.ChannelSpec property`), 305  
spec (`kwcoco.FusedChannelSpec property`), 334  
special\_reroot\_single() (in module `kwcoco.util`), 199  
special\_reroot\_single() (in module `kwcoco.util_reroot`), 180  
split() (`kwcoco.util.StratifiedGroupKFold method`), 196  
split() (`kwcoco.util.util_sklearn.StratifiedGroupKFold method`), 182  
SqlDictProxy (class in `kwcoco.coco_sql_dataset`), 277  
SqlIdGroupDictProxy (class in `kwcoco.coco_sql_dataset`), 279  
SqlListProxy (class in `kwcoco.coco_sql_dataset`), 277  
star() (in module `kwcoco.demo.toypatterns`), 65  
stats() (`kwcoco.coco_dataset.MixinCocoStats method`), 222  
stats() (`kwcoco.coco_image.CocoImage method`), 254  
stats() (`kwcoco.CocoImage method`), 322  
step() (`kwcoco.demo.boids.Boids method`), 26  
StratifiedGroupKFold (class in `kwcoco.util`), 196  
StratifiedGroupKFold (class in `kwcoco.util_sklearn`), 182  
streams() (`kwcoco.ChannelSpec method`), 306  
streams() (`kwcoco.FusedChannelSpec method`), 338

**s**  
**streams()** (*kwcoco.SensorChanSpec method*), 340  
**STRING** (*kwcoco.util.jsonschema\_elements.ScalarElements take\_channels()*)  
*(kwcoco.util.delayed\_ops.DelayedImage method)*, 146  
**STRING** (*kwcoco.util.ScalarElements property*), 194  
**submit()** (*kwcoco.metrics.confusion\_measures.MeasureCombinerBackend*)  
*(in module kwcoco.examples.getting\_started\_existing\_dataset), 146*  
**submit()** (*kwcoco.metrics.confusion\_measures.OneVersusRestMeasureCombiner*)  
*(method), 82*  
**submit()** (*kwcoco.util.util\_futures.Executor method*), 174  
**submit()** (*kwcoco.util.util\_futures.JobPool method*), 175  
**subset()** (*kwcoco.coco\_dataset.CocoDataset method*), 246  
**subset()** (*kwcoco.CocoDataset method*), 319  
**summarize()** (*kwcoco.metrics.detect\_metrics.DetectionMetrics method*), 98  
**summarize()** (*kwcoco.metrics.DetectionMetrics method*), 125  
**summary()** (*kwcoco.metrics.confusion\_measures.Measures track\_id*)  
*(kwcoco.coco\_sql\_dataset.Annotation attribute), 276*  
**summary()** (*kwcoco.metrics.confusion\_measures.PerClass\_Measures transform*)  
*(kwcoco.util.delayed\_ops.DelayedWarp property), 158*  
**summary()** (*kwcoco.metrics.Measures method*), 128  
**summary()** (*kwcoco.metrics.PerClass\_Measures method*), 135  
**summary\_plot()** (*kwcoco.metrics.confusion\_measures.Measures method*), 74  
**summary\_plot()** (*kwcoco.metrics.confusion\_measures.PerClass\_Measures method*), 80  
**summary\_plot()** (*kwcoco.metrics.Measures method*), 129  
**summary\_plot()** (*kwcoco.metrics.PerClass\_Measures method*), 135  
**supercategory** (*kwcoco.coco\_objects1d.Categories property*), 267  
**supercategory** (*kwcoco.coco\_sql\_dataset.Category attribute*), 275  
**supercategory** (*kwcoco.coco\_sql\_dataset.KeypointCategory attribute*), 275  
**superstar()** (*kwcoco.demo.toypatterns.Rasters static method*), 65  
**SupressPrint** (*class in kwcoco.util.util\_monkey*), 179

**T**

**tabular\_targets()** (*kwcoco.coco\_sql\_dataset.CocoSqlDatabase method*), 284  
**tabular\_targets()** (*kwcoco.CocoSqlDatabase method*), 333  
**take()** (*kwcoco.coco\_objects1d.ObjectListID method*), 263  
**take\_channels()** (*kwcoco.util.delayed\_ops.DelayedChannelConcat method*), 139

**method), 139**  
**method), 146**  
**method), 146**  
**method), 174**  
**method), 175**  
**method), 246**  
**method), 319**  
**method), 98**  
**method), 125**  
**method), 276**  
**method), 301**  
**method), 290**  
**method), 165**  
**method), 186**  
**method), 336**  
**method), 336**  
**method), 276**  
**method), 158**  
**method), 26**  
**method), 92**  
**method), 119**  
**method), 274**

**U**

**unarchive\_file()** (*in module kwcoco.util*), 199  
**unarchive\_file()** (*in module kwcoco.util.util\_archive*), 173  
**undo\_warp()** (*kwcoco.util.delayed\_ops.DelayedImage method*), 148  
**undo\_warps()** (*kwcoco.util.delayed\_ops.DelayedChannelConcat method*), 141  
**union()** (*kwcoco.ChannelSpec method*), 308  
**union()** (*kwcoco.coco\_dataset.CocoDataset method*), 244  
**union()** (*kwcoco.CocoDataset method*), 317  
**union()** (*kwcoco.FusedChannelSpec method*), 337  
**unique()** (*kwcoco.ChannelSpec method*), 308  
**unique()** (*kwcoco.coco\_objects1d.ObjectListID method*), 263  
**unique()** (*kwcoco.FusedChannelSpec method*), 335  
**update()** (*kwcoco.util.dict\_like.DictLike method*), 165  
**update()** (*kwcoco.util.DictLike method*), 187  
**update\_neighbors()** (*kwcoco.demo.boids.Boids method*), 25

**V**

valid\_region() (kwcoco.coco\_image.CocoImage method), 261  
valid\_region() (kwcoco.CocoImage method), 329  
validate() (kwcoco.coco\_dataset.MixinCocoStats method), 221  
validate() (kwcoco.util.Element method), 188  
validate() (kwcoco.util.jsonschema\_elements.Element method), 167  
values() (kwcoco.ChannelSpec method), 306  
values() (kwcoco.coco\_sql\_dataset.SqlDictProxy method), 279  
values() (kwcoco.coco\_sql\_dataset.SqlIdGroupDictProxy method), 280  
values() (kwcoco.util.dict\_like.DictLike method), 165  
values() (kwcoco.util.DictLike method), 186  
Video (class in kwcoco.coco\_sql\_dataset), 275  
video (kwcoco.coco\_image.CocoImage property), 254  
video (kwcoco.CocoImage property), 322  
video\_id (kwcoco.coco\_sql\_dataset.Image attribute), 276  
Videos (class in kwcoco.coco\_objects1d), 267  
videos() (kwcoco.coco\_dataset.MixinCocoObjects method), 219  
view\_sql() (kwcoco.coco\_dataset.CocoDataset method), 247  
view\_sql() (kwcoco.CocoDataset method), 320  
VOC\_Metrics (class in kwcoco.metrics.voc\_metrics), 109

**X**

xywh (kwcoco.coco\_objects1d.Annots property), 271

warp() (kwcoco.util.delayed\_ops.ImageOpsMixin method), 162  
warp\_img\_from\_vid (kwcoco.coco\_image.CocoImage property), 261  
warp\_img\_from\_vid (kwcoco.CocoImage property), 329  
warp\_img\_to\_vid (kwcoco.coco\_sql\_dataset.Image attribute), 276  
warp\_vid\_from\_img (kwcoco.coco\_image.CocoImage property), 261  
warp\_vid\_from\_img (kwcoco.CocoImage property), 329  
weight (kwcoco.coco\_sql\_dataset.Annotation attribute), 276  
whats\_the\_difference\_between\_Images\_and\_CocoImage() (in module kwcoco.examples.faq), 67  
width (kwcoco.coco\_objects1d.Images property), 268  
width (kwcoco.coco\_sql\_dataset.Image attribute), 276  
width (kwcoco.coco\_sql\_dataset.Video attribute), 276  
write\_network\_text() (kwcoco.util.delayed\_ops.DelayedOperation method), 155